

Bid Project 2016 – 04 Huebner Rd. Rehabilitation

Pre-Bid Meeting 5/24/16 - Clarification

1. Huebner Rd. street classification falls under the category of Primary and Secondary Arterials. The minimum surface aggregate classification is “A”; Surface Course PG 76-22.
2. **Q.** What is the Project Sequencing?
A. This is the contractor’s responsibility and shall be in accordance with the contractor’s provided traffic control plan for which there is no separate pay item. Project scheduling is such that the project must be completed before the start of the NISD school year.
3. **Q.** What are Traffic control / Police Requirements for the job?
A. This is the contractor’s responsibility. A traffic control plan is required during each phase of project construction and shall be provided by the contractor to the City Engineer for approval prior to construction. Traffic shall be maintained and controlled in accordance with the latest edition of the Texas Manual on Uniform Traffic Control Devices for streets and highways. Safety for both motorists and construction staff is high priority. Two lanes of traffic must be maintained at all times during the project. There is no separate pay item for traffic control measures or plans. Traffic control measures payment shall be included in the unit costs as follows:

Base Bid – Under item 205.4 Hot mix asphaltic pavement (per square yard)

Additive Alternate #1 – Under item SP-4.8 Concrete Bus Pads