SOUTHWEST ENGINEERS
Civil | Environmental | Land Development
TBPE NO. F-1909
www.swengineers.com
307 St. Lawrence Street, Gonzales, TX 78629
P: 830.672.7546 F: 830.672.2034

City of Leon Valley
2016-01 – City of Leon Valley Municipal Water Well Project
Water Wells No. 3 and 4
2016-02 City of Leon Valley Municipal Water Well Project
Yard Piping and Electrical and San Antonio Water System (SAWS)
Interconnection for Wells No. 3 and 4
SWE Project No. 0617-001-15
March 4, 2016

TO ALL PLAN HOLDERS:

Good questions! Keep them coming!

1. Each site is located within the chain link fence. I'm sure the City can provide more frequent police patrols during the construction process for both contractors. If you feel the need for more than that, then it would be up to you.

2. It may be necessary to remove the fence at the Grass Hill site for access by the rig. If removed, it must be replaced that same day.

3. The City has indicated there would be no change for the construction permit. The City will work with you in setting up barricades at the Grass Hill site. None would be required at Huebner.

4. Yes, we will add an Add/Deduct item for the cost of cement and gravel above or below that shown on the Plans and send out as on Addenda.

5. We will send the neighbors any where they want - at your cost. Some neighbors have suggested places I would also like to go. This may require approval from higher authority.

6. At the Grass Hill site, the Plant Contractor will remove all above grade discharge piping from the well head to below grade before the Drilling Contractor arrives.

7. You may set not less than a 22" surface conductor casing.

8. The Grass Hill Site Plan shows the locations of the existing buried pipelines as heavy lines. The heavy line from the building to the street is a small steel gas line. Other lines are 12" AC pipe. Valves are located by the valve boxes.

Clarence