



**BID #2020-02 - GRASS HILL ELEVATED STORAGE TANK PAINTING AND  
REHABILITATION - FEBRUARY 25, 2020, 10:00 A.M.**

**Maguire Iron, Inc.**  
PO Box 1446  
Sioux Falls, SD 57101  
(605) 334-9749

**TMI Coatings, Inc**  
3291 Terminal Dr  
St Paul, MN 55121  
(651) 452-6100

Item	Qty	Unit	Description	Unit Price	Extended Price	Unit Price	Extended Price
1	1	LS	Furnish all materials, equipment, labor, superintendence and incidental work to abrasive blast per SSPC-SP6, clean, prime and coat with Containment and Dust Collection the Exterior of the existing 150,000-gallon EST, all appendages, ladder, vent, hatch, railing, tank piping, valves, etc., as indicated on the drawings and specifications part 2.04.A and part 3.07 except where specifically covered by other bid items.	\$ 106,000.00	\$ 106,000.00	\$ 350,200.00	\$ 350,200.00
2	1	LS	Furnish all materials, equipment, labor, superintendence and incidental work to spot blast for inspection and identification of repairs, abrasive blast per SSPC-SP10, clean, prime, stripe coat and coat with Dehumidification the Interior of the existing 150,000-gallon EST, all appendages, ladder, vent, hatch, weir box, etc., as indicated on the drawings and specifications part 2.04.B and part 3.06, except where specifically covered by other bid items.	\$ 58,500.00	\$ 58,500.00	\$ 138,500.00	\$ 138,500.00
3	1	LS	Furnish all materials, equipment, labor, superintendence and incidental work to Dehumidify the interior of the existing 150,000-gallon EST, during surface preparation and coating, including hoses, filters, etc., as indicated on the drawings and specifications part 3.06, except where specifically covered by other bid items.	\$ 15,000.00	\$ 15,000.00	\$ 13,000.00	\$ 13,000.00
4	1	LS	Furnish all materials, equipment, labor, superintendence and incidental work to provide Containment and Dust Collection as indicated on the drawings and specifications part 3.07, except where specifically covered by other bid items.	\$ 90,000.00	\$ 90,000.00	\$ 108,000.00	\$ 108,000.00
5	40	MH	Furnish all materials, equipment, labor, superintendence and incidental work to perform General Repairs; grinding, welding and general work to repair corrosion related surfaces and remove or make operable the liquid target as deemed necessary in accordance with this Section "Technical Specification" Part 3.01.A	\$ 240.00	\$ 9,600.00	\$ 150.00	\$ 6,000.00
6	1	LS	Furnish all materials, equipment, labor, superintendence and incidental work to install a 20"Ø AWWA approved aluminum Roof Vent, including a new weld-on C.S. flanged neck to accommodate the bolt on installation of the new aluminum vent, as indicated on the drawings and specifications except where specifically covered by other bid items. Provide drawing with P.E. seal for submittal.	\$ 8,500.00	\$ 8,500.00	\$ 8,200.00	\$ 8,200.00
7	1	LS	Furnish all materials, equipment, labor, superintendence and incidental work to perform Interior and Exterior ladder replacement, balcony mid-railing modifications and rendering all OSHA Compliant as indicated on the drawings and specifications, except where specifically covered by other bid items.	\$ 27,500.00	\$ 27,500.00	\$ 37,200.00	\$ 37,200.00
8	1	LS	Furnish all materials, equipment, labor, superintendence and incidental work to install a New Riser Manway 18"x24" oval or 24" diameter AWWA D100 approved and TCEQ compliant as indicated on the drawings and specifications, except where specifically covered by other bid items.	\$ 9,500.00	\$ 9,500.00	\$ 6,600.00	\$ 6,600.00
9	50	PER TUBE	Furnish all materials, equipment, labor, superintendence and incidental work to perform Caulking and or Seam Sealing work to seams and areas as deemed necessary, as indicated on the drawings and specifications part 3.01.A.2, except where specifically covered by other bid items.	\$ 30.00	\$ 1,500.00	\$ 86.00	\$ 4,300.00
10	1	LS	Furnish all materials, equipment, labor, superintendence and incidental work to perform removing and reinstalling electrical conduit and antennas (to be re-used) as needed for the tank rehabilitation, and one (1) run of new conduit with electrical from the base of the leg ladder to the top of the balcony to terminate inside the J-box.	\$ 10,500.00	\$ 10,500.00	\$ 5,700.00	\$ 5,700.00
<b>TOTAL BID</b>					<b>\$ 336,600.00</b>		<b>\$ 677,700.00</b>