

Specifications

**Proposal for 2013-01
LEON VALLEY PUBLIC LIBRARY
CHILDREN'S WING
6425 EVERS RD.
LEON VALLEY, TEXAS 78238**

November 2012

Architect

Richard Mogas & Associates, Inc.
317 Lexington, Suite 4
San Antonio, Texas 78215
Phone: (210) 226-2220 (210) 226-1846
rmogas@richardmogas.com

Structural

AccuTech Consulting LLC
909 N.E. Loop 410, Suite 900
San Antonio, Texas 78209
Phone: (210) 930-5355 Fax: (210) 930-5460

Mechanical/Electrical/Plumbing

HMG & Associates, Inc.
70 N.E. Loop 410, Suite 1070
San Antonio, Texas 78216
Phone: (210) 349-0800 Fax: (210) 349-2736

TECHNICAL SPECIFICATIONS INDEX

Proposal Information Packet

Proposal Invitation
Proposal Form
Performance Bond and Payment Bond
Proposal Bond
Non-collusion Affidavit of Prime Bidder
Proposal Disclosure Statement
Evaluation Criteria

Technical Specifications

Scope of Work
General Requirements
General Conditions of the Contract for Construction (view at www.aiasa.org)
Supplemental General Conditions

Division 1 - General Requirements

Section 01000 - Special Conditions
01300 - Submittals
01341 - Structural Engineer: Shop Drawings and Field Visits
01400 - Quality Control
01500 - Temporary Facilities & Control
01650 - Allowances
01700 - Project Closeout

Division 2 - Sitework

Section 02010 - Subsurface and Soil Conditions
02100 - Site Preparation
02221 - Removing existing Pavement and Structures
02224 - Foundation Earthwork
See Struct. Sht. S-3.1 For earthwork specifications
02230 - Site Clearing
02251 - Termite Control
02362 - Drilled Footings Section not in contract
02550 - Site Utilities
02700 - Piped utilities

Division 3 - Concrete

03100 - Concrete Formwork
03200 - Concrete Reinforcement
03300 - Cast-in-Place Concrete

Division 4 - Masonry

04200 – Unit Masonry & Masonry Veneer

Division 5 - Metals

Section	05100 - Structural Steel	Section not in contract
	05210 - Open Web Steel Joists	Section not in contract
	05300 - Metal Decking	Section not in contract
	05500 - Metal Work	

Division 6 - Wood and Plastics

Section 06100 - Carpentry and Millwork

Division 7 - Thermal and Moisture Protection

Section 07200 - Insulation
 07600 - Flashing and Sheet Metal
 7610 - Preformed Metal Roofing
 07720 – Roof Accessories
 07900 - Sealants

Division 8 - Doors and Windows

Section 08400 - Entrances and Storefronts
 08710 - Finish Hardware
 08800 - Glazing

Division 9 - Finishes

Section 09250 - Gypsum Drywall
 09300 - Tile
 09680 – Carpet Tiles
 09900 - Painting

Division 10 - Specialties

Section 10160 - Toilet partitions
 10520 - Fire Extinguishers, Cabinets & Accessories

Division 11 - Equipment

Section not in Contract

Division 12 – Furnishings

Section not in Contract

Division 13 - Special Construction

13121 – Pre-Engineered Metal Buildings
 See Structural. Sht. S-3.1 for additional notes

Division 14 - Conveying Systems

Section not in Contract

See civil, mechanical, electrical, plumbing specifications.
 Structural specifications notes are included on structural drawings..



**REQUEST FOR PROPOSALS
2013-01 - LEON VALLEY PUBLIC LIBRARY CHILDREN'S WING**

The City of Leon Valley is currently accepting competitive sealed proposals for the construction of a new 1-story building addition, estimated at \$501,610. The City will accept sealed proposals until 10:00 a.m. Friday, December 21, 2012, in the Office of the Purchasing Agent, located at 6400 El Verde Rd, Leon Valley, TX 78238. A public opening will not be held for this proposal.

Plans and specifications are available on the City of Leon Valley's website at www.leonvalleytexas.gov/government/finance/purchasing.php. For assistance, please call (210) 684-1391 ext 222.

Proposals must be submitted on the furnished form furnished and submitted in a sealed envelope and shall be clearly endorsed "**Request for Proposals 2013-01 - Leon Valley Public Library Children's Wing**". Each proposal shall be accompanied by a proposal guarantee in the form of a certified check, cashier's check, or bid bond in the amount of five percent (5%) of the total proposal price. Any proposal received after closing time will be returned unopened.

The successful proposer will be required to furnish a one hundred percent (100%) Performance Bond and one hundred percent (100%) Payment Bond.

The City of Leon Valley reserves the right to reject any and all bids, to award the contract in what it deems its best interest and to waive any informality or technicality in the proposal, and agrees to take action within sixty (60) days after the bid opening.

PROPOSAL FORM

PROPOSAL OF: _____
(Name of Proposer)

NAME OF PROJECT:
2013-01 - LEON VALLEY PUBLIC LIBRARY CHILDREN'S WING

Dear Sirs:

The undersigned, having examined the Drawings, Specifications and related documents, the site and premises of the proposed work, being familiar with all of the conditions relating to the construction for the proposed project, including the availability of materials and labor, hereby propose to furnish all labor, materials, services and equipment required in connection with or required for the construction of the building, including all addenda and in strict conformance with the following Specifications and Drawings:

Specification Sections: Proposing Documents; AIA General Conditions of the Contract for Construction (AIA Document A201); Supplementary Conditions; Division 1 through 16, as indexed in the forepart of the Specifications.

Prepared by Richard Mogas & Associates, Inc.
317 Lexington, Suite 4, San Antonio, TX 78215, Telephone: (210) 266-2220 Fax: (210) 226-1846
rmogas@richardmogas.com

Proposer acknowledges receipt of the following addenda (if any): _____

Proposal _____

DOLLARS (\$ _____)

Amounts are to be shown in both words and numeric figures. In case of discrepancy, the amount shown in words will govern.

Submit a certificate of insurance for workers compensation or a certificate of authority to self insure with proposal.

Time of Completion:

No. of Calendar Days to complete the Project: _____

The undersigned further agrees, if awarded the Contract, to complete all work as outlined by the Plans and Specifications within the number of calendar days indicated for in the Proposal Form.

Notification:

The undersigned hereby notifies the Owner that he/she understands that the Owner reserves the right to reject any or all proposals and to waive any informalities and to award the Contract in the best interest of the project.

For every day exceeding the number of stipulated construction days as stated in the Contractor's proposal, the Contractor shall be charged \$250 per calendar day until the project is completed to the satisfaction of

the Owner. Additionally, the City will retain ten percent (10%) of the total proposal amount, which will be paid within thirty (30) days of Owner satisfied completion.

It is understood that all proposal documents become a part of the Contract Documents upon signing of the contract. Failure to comply with any part of this proposal will be taken as failure to comply with said Contract and will be just cause for rejection of the work.

I agree to perform all the work described in the PROPOSAL for the preceding prices.

Respectfully Submitted,

(Legal Name of Corporation)

(Legal Name of Proposing Firm)

(State of Incorporation)

(Address)

(Type Name of Officer)

(Type Name of Officer)

(Signature of Officer)

(Signature of Officer)

(Title of Officer)

(Title of Officer)

(Date)

(Date)

(Legal Name Witness)

(Address of Witness)

(Signature of Witness)

(Address of Witness)

(Date)

Seal of Corporation

2013-01 - Leon Valley Public Library Children's Wing

Note: To be valid, signature of Proposer, including Corporation Proposer, must be witnessed and dated.

PROPOSAL BOND

Proposal's (Name and Address): _____

SURETY (Name and of Principal Place of Business): _____

OWNER

City of Leon Valley
6400 El Verde Road
Leon Valley, Texas 78238

PROPOSAL

PROPOSAL DUE DATE: **December 21, 2012 @ 10:00am**
PROJECT: **2012-03 - Leon Valley Public Library Children's Wing**

BOND

BOND AMOUNT: 5% of the total Proposal price.
BOND NUMBER: _____
DATE (Not later than Proposal due date) _____
PENAL SUM: _____
(Words) (Figures)

IN WITNESS WHEREOF, Surety and Proposal, intending to be legally bound hereby, subject to the terms printed on the reverse side hereof, do each cause this Bid Bond to be duly executed on its behalf by its authorized officer, agent, or representative.

PROPOSAL

SURETY

_____(Seal) _____(Seal)
Proposal's Name and Corporate Seal Surety's Name and Corporate Seal

By: _____
Signature and Title

By: _____
Signature and Title
(Attach Power of Attorney)

Attest: _____
Signature and Title

Attest: _____
Signature and Title

Note: (1) Above addresses are to be used for giving required notice.

- (2) Any singular reference to Proposal, Surety, OWNER or other party shall be considered plural where applicable.

1. Proposal and Surety, jointly and severally, bind themselves, their heirs, executors, administrators, successors and assigns to pay to OWNER upon default of Bidder the penal sum set forth on the face of this Bond.

2. Default of Proposal shall occur upon the failure of Bidder to deliver within the time required by the Proposal Documents (or any extension thereof agreed to in writing by OWNER) the executed Agreement required by the Bidding Documents and any performance and payment Bonds required by the Bidding Documents.

3. This obligation shall be null and void if:

3.1. OWNER accepts Bidder's Proposal and Bidder delivers within the time required by the Bidding Documents (or any extension thereof agreed to in writing by OWNER) the executed Agreement required by the Proposal Documents and any performance and payment Bonds required by the Bidding Documents, or

3.2. All Proposals are rejected by OWNER, or

3.3. OWNER fails to issue a Notice of Award to Bidder within the time specified in the Bidding Documents (or any extension thereof agreed to in writing by Bidder and, if applicable, consented to by Surety when required by paragraph 5 hereof).

4. Payment under this Bond will be due and payable upon default by Bidder and within 30 calendar days after receipt by Bidder and Surety of written notice of default from OWNER, which notice will be given with reasonable promptness, identifying this Bond and the Project and including a statement of the amount due.

5. Surety waives notice of and any and all defenses based on or arising out of any time extension to issue Notice of Award agreed to in writing by OWNER and Bidder, provided that the total time for issuing Notice of Award including extensions shall not in the aggregate exceed

120 days from Proposal due date without Surety's written consent.

6. No suit or action shall be commenced under this Bond prior to 30 calendar days after the notice of default required in paragraph 4 above is received by Bidder and Surety and in no case later than one year after Bid due date.

7. Any suit or action under this Bond shall be commenced only in a court of competent jurisdiction located in the state in which the Project is located.

8. Notices required hereunder shall be in writing and sent to Bidder and Surety at their respective addresses shown on the face of this Bond. Such notices may be sent by personal delivery, commercial courier or by United States Registered or Certified Mail, return receipt requested, postage pre-paid, and shall be deemed to be effective upon receipt by the party concerned.

9. Surety shall cause to be attached to this Bond a current and effective Power or Attorney evidencing the authority of the officer, agent or representative who executed this Bond on behalf of Surety to execute, seal and deliver such Bond and bind the Surety thereby.

10. This Bond is intended to conform to all applicable statutory requirements. Any applicable requirement of any applicable statute that has been omitted from this Bond shall be deemed to be included herein as if set forth at length. If any provision of this Bond conflicts with any applicable statute, then the provision of said statute shall govern and the remainder of this Bond that is not in conflict therewith shall continue in full force and effect.

11. The term "Proposal" as used herein includes a Bid, offer or proposal as applicable.

NON-COLLUSION AFFIDAVIT OF PRIME BIDDER/PROPOSER

State of _____ §
County of _____

_____ being first duly sworn, deposes and says that:

- (1) He/She _____ of _____, the Bidder/Proposer that has submitted the attached Bid/Proposal;
- (2) He/She is fully informed respecting the preparation and contents of the attached Bid/Proposal and of all pertinent circumstances respecting such Bid/Proposal;
- (3) Such Bid/Proposal is genuine and is not a collusive or sham Bid/Proposal;
- (4) Neither the said Bidder/Proposer nor any of its officers, partners, owners, agents, representatives, employees or parties in interest, including this affiant, has in any way colluded, conspired, connived or agreed, directly or indirectly with another Bidder/Proposer, firm or person to submit a collusive or sham Bid/Proposal in connection with the Contract for which the attached Bid/Proposal has been submitted or to refrain from bidding/proposing in connection with such contract, or has in any manner, directly or indirectly, sought by agreement or collusion or communication or conference with any other Bidder/Proposer, firm or person to fix the price or prices in the attached Bid/Proposal or of any other Bidder/Proposer, or to fix an overhead, profit or cost element of the Bid/Proposal price or the Bid/Proposal price of any other Bidder/Proposer, or to secure through any collusion, conspiracy, connivance or unlawful agreement any advantage against the City of Leon Valley or any person interested in the proposed Contract; and
- (5) The price or prices quoted in the attached Bid/Proposal are fair and proper and are not tainted by an collusion, conspiracy, connivance or unlawful agreement on the part of the Bidder/Proposer or any of its agents, representatives, owners, employees, or parties in interest, including this affiant.

Signature _____

Printed Name _____

Title _____

STATE OF _____
COUNTY OF _____

Subscribed and sworn to me this _____ day of _____, 20_____.

By _____ My Commission Expires _____

(NOTARY SEAL)

6. What projects does your organization have under way as of this date?

Contract Amount	Type of Work	% Completed	Owner's Name, Address, and Telephone Number

7. Have you ever failed to complete any work awarded to you? Yes No. If "Yes", state where and why. _____

8. Are you now or have you been involve with or party to any lawsuits involving construction work of any type? Yes No. If "Yes", explain:

9. If this contract is awarded to you, your company's office administrative manager for the work will be _____, and your resident construction superintendent will be _____

10. What experience in this type of work does the individual designated as resident superintendent above have? _____

11. What portion of the work do you intend to subcontract? _____

12. What equipment do you own that is available for the proposed work?

Qty	Description, Size, Capacity, Etc.	Condition	Years in Service	Present Location

13. Have you received firm offers from suppliers or manufacturers for all major items of material and/or equipment within the price totals used in preparing your proposal?

Yes No

Credit Available: \$ _____ Bank reference: _____

Bonding capacity available: \$ _____

The undersigned hereby authorizes and requests any person, firm or corporation to furnish any information requested by the Engineer and Owner in verification of the recitals comprising this Bid/Proposal Disclosure Statement.

The signatory of this questionnaire guarantees the truth and accuracy of all statements herein made and all answers herein expressed.

Signature _____

Printed Name _____

Title _____

STATE OF _____

COUNTY OF _____

Subscribed and sworn to me this _____ day of _____, 20____.

By _____ My Commission Expires _____

(NOTARY SEAL)



**REQUEST FOR PROPOSALS
2013-01 - LEON VALLEY PUBLIC LIBRARY CHILDREN'S WING**

EVALUATION CRITERIA

Each proposal will be evaluated on the following criteria:

- A. Experience of Prime Contractor (25%)
 - 1. Similar projects
 - 2. Number of employees employed by the prime contractor
 - 3. Equipment list

- B. Price (25%)

- C. Completed projects in the last three years (20%)
 - 1. % completed within owners construction budget
 - 2. % completed within owners budget schedule
 - 3. # of change orders

- D. Background and qualifications of prime contractor (15%)

- E. Background and qualifications of sub contractors (15%)

SCOPE OF WORK

The Scope of Work entails the construction of a new 1-story building addition. It includes but is not limited to site work, concrete, metals, carpentry, metal roofing, insulation, sealants, aluminum windows, glazing, aluminum doors,, wood doors, hardware, drywall, painting/sealers, specialties, HVAC, electrical,, lighting, plumbing, etc...

Note: The City of Leon Valley will be responsible for the following:

1. New asphalt repair and resurfacing
2. The concrete curbing at parking area
3. Landscape and irrigation

Schedule

General Contractor will be required to provide the number of calendar days required to substantially complete the project from the date of issuance of the building permit.

Liquidating Damages:

For every day exceeding the number of stipulated construction days, as stipulated in the Contractor's bid, the Contractor shall be charged \$250 per calendar day until project is completed to the satisfaction of the Owner.

Prime Contract

All work, including general construction, mechanical and electrical work will be awarded under a single prime contract.

END OF SECTION

GENERAL REQUIREMENTS

- 1.1 The "General Conditions of the Contract for Construction", A.I.A. Document A201, 2007 Edition, is a part of this Contract.
- 1.2 The Contractor and Subcontractor are responsible for verifying all dimensions and conditions incidental to this work and taking site measurements for all items requiring fitting to work previously built or set.
- 1.3 Contractor is responsible for carefully inspecting work completed and verifying its accuracy and quality before subsequent work is commenced. If problems exist, contact Architect before starting work.
- 1.4 Contractor is responsible for installing all materials and equipment according to the manufacturer's recommendations. At least one qualified person who is familiar with the proper procedure and manufacturer's requirements shall be present during installation.
- 1.5 The Contractor shall remove and replace all defective work at his own expense.
- 1.6 The Contractor shall haul, stack and store all materials as is proper for their kind to protect them at all times.
- 1.7 The Contractor is responsible for hauling away trash, debris and surplus building materials.
- 1.8 Approval of shop drawings does not remove Contractor's responsibility for quantities, measurements, etc.
- 1.9 The Contractor shall guarantee the work under this contract for one (1) year from final acceptance date against defects in materials, equipment and workmanship and shall repair or replace defects to the Owner's satisfaction at no cost to the Owner. With the request for final payment, Contractor shall deliver to Owner all warranties and guarantees which extend beyond his own.
- 1.10 Project Closeout: The Contract will be considered fulfilled when all work has been completed; the final inspection made by Owner and Architect and final acceptance and final payment by the Owner. When the Architect and Owner determine that all work is substantially complete, they will prepare a punch list to give to the Contractor so he can make any adjustments or corrections as required to complete the project. The failure to include any items on such list does not alter the Contractor's responsibility to complete all work according to drawings and specifications.

END OF SECTION

SUPPLEMENTAL GENERAL CONDITIONS

The General Conditions of this Contract are the American Institute of Architect's Document A-201, "General Conditions of the Contract for Construction", View www.AIA.ORG which is hereby made a part of these Specifications and shall apply to all contractors and subcontractors.

In event Document A201 is not bound herewith, a copy may be referred to or obtained from the office of the Architect.

THE SUPPLEMENTAL GENERAL CONDITIONS

The Supplemental General Conditions contain changes and additions to the AIA General Conditions. Where any part of the AIA General Conditions is modified or deleted by these Supplemental General Conditions, the unaltered provisions shall remain in effect.

MODIFICATIONS TO THE VARIOUS ARTICLES OF THE GENERAL CONDITIONS:

ARTICLE 1 - GENERAL PROVISIONS

- 1.1 Basic Definitions: Add the following sentence to paragraph 1.1.1, THE CONTRACT DOCUMENTS: "The Agreement takes precedence over all other Contract Documents".
- 1.2 Execution, Correlation, and Intent: Add the following paragraphs:
 - 1.2.6 Titles of Sections and Articles in these specifications are introduced merely for convenience and are not to be construed as a correct or complete segregation or tabulation of the various units or materials and/or work. The Contractor shall be solely responsible for omissions or duplications by the Contractor or any Subcontractors due to real or alleged error, either direct or implied, in agreement of matter on the Contract Documents.
 - 1.2.7 Contractor shall check drawings and specifications immediately upon their receipt, and shall notify the Architect in

writing not later than Ten (10) days after receipt of them, of errors, discrepancies or omissions. Contractor shall verify dimensions and details before ordering materials or laying out work and shall be responsible for errors that might have been avoided by such check. Deviations from drawings and dimensions shall be made only with the Architect's permission.

- 1.2.8 Specifications and Drawings are intended to be complementary and in agreement with each other. All work or material called for by either shall be performed and/or furnished as if called for by both. In cases of discrepancy concerning dimensions, quantities and location, the Contractor shall in writing, call to the attention of the Architect any discrepancies between Specifications, Plans, Details or Schedules. The Architect will then inform the Contractor in writing which document takes precedence.

ARTICLE 3 - CONTRACTOR

- 3.4 Labor and Materials: Add the following paragraph:

- 3.4.3 Contractor and Subcontractors shall conform to the labor laws of the State of Texas, and the various acts amendatory and supplementary thereto, and to all other laws, ordinances and legal requirements applicable thereto. Applicable Federal Laws shall be complied with.

- 3.6 Taxes: Add the following paragraph:

- 3.6.2 The Contractor shall pay all taxes and insurances required by the State and Federal Laws.

- 3.7 Permits, Fees and Notices: Add the following paragraph:

- 3.7.5 The City of Leon Valley shall wave all costs related to all permitting. Licenses, etc., required in the prosecution of the work, whether of a permanent or temporary nature shall be paid by the Contractor. Upon completion of the work the Contractor shall deliver to the Owner through the Architect all required certificates of inspection.

ARTICLE 5 - SUBCONTRACTORS

5.1 Definitions: Add the following paragraph:

5.1.3 There shall be no obligation on the part of the Owner to pay or see to the payment of any sums due any Contractor or Subcontractor, nor create any obligation of any kind, express or implied, upon the Owner or the Architect in favor of any Subcontractor or Sub-subcontractor.

ARTICLE 6 - CONSTRUCTION BY OWNER OR BY SEPARATE CONTRACTORS

6.2 Mutual Responsibility: Add the following paragraph:

6.2.7 The Contractor shall be responsible for the fitting of all work and for the coordination of the operation of all trades, other Contractors, Subcontractors and material suppliers engaged upon or in connection with the work, as well as those of his own employees and he shall exercise every effort to assure a harmonious cooperative effort on the part of all those concerned. He shall be prepared to guarantee to each of his subcontractors and foremen all of the dimensions which they may require for the fitting of their own work to adjoining work and shall do or cause to do, all fittings and adjusting necessary to make the several parts of the work come together properly and fit the work to receive or be received by the work of other Contractors.

ARTICLE 7 - CHANGES IN THE WORK

7.3 Construction Change Directives

7.3.6 A "reasonable allowance for overhead and profit" as referred to in the first sentence of this paragraph shall not exceed fifteen percent (15%).

ARTICLE 9 - PAYMENTS AND COMPLETION

9.5 Decisions to Withhold Certification: Add the following paragraph:

9.5.1 The Architect will not issue any Certificates of Payment for any progress payment to the Contractor subsequent to the work completion date specified in Article 3 of the AIA Document A101, "Standard Form of Agreement Between Owner and Contractor", 1987 Edition.

9.6 Progress Payments: Delete in its entirety 9.6.1 and add the following paragraph:

9.6.1 After the Architect has issued a Certificate of Payment, and unless otherwise provided in the Agreement, the Owner shall make payment on account of Contract on or about the Fifteenth (15th) day of each month as follows:

- a. Prior to application for first payment, file with the Architect a complete schedule on AIA Documents G702 "Application and Certificate for Payment and G702A "Continuation Sheet", showing the value of various portions of the work in detail. The Contractor, upon approval of the Architect, may use other formats in lieu of G702 & G702A as long as all information required is supplied.
- b. Contractor's Application for Payment shall be submitted on Documents G702 and G702A on or before the last day of each month, Ninety percent (90%) of the value based on the Contract prices of labor and materials suitably stored at the site thereof, or in a bonded warehouse up to the last day of that month, as estimated by the Architect, less the aggregate of previous payments. Upon approval of the Owner, the Contractor may make application on the middle and last day of each month.
- c. Final payment shall be due Thirty (30) days after acceptance as Substantial Completion of the work, provided the work be then fully completed, and the Contract fully performed. Contractor shall submit to the Architect a notarized statement stating that all bills for labor and materials have been paid in full.

ARTICLE 11 - INSURANCE:

Each bid shall be accompanied by a bid guarantee in the form of a certified check, cashier's check, or bid bond in the amount of five percent (5%) of the total bid price.

The successful bidder will be required to furnish a one hundred percent (100%) Performance Bond and one hundred percent (100%) Payment Bond.

11.1 Workmen's Compensation and Employer's Liability Insurance

11.1.1 For the duration of this Contract, the Contractor shall maintain Statutory Workmen's Compensation and shall maintain Employer's Liability Insurance with minimum limits of not less than \$100,000.00. Contractor shall require Subcontractors to provide workmen's Compensation and Employer's Liability Insurance with the same minimum limits.

11.2 Comprehensive General Liability Insurance

11.2.1 For the duration of this Contract, the Contractor shall maintain comprehensive General Liability Insurance with Minimum Bodily Injury limits of not less than \$500,000.00 for each person and not less than \$500,000.00 for each accident. He shall maintain Property Damage Insurance with minimum limits of not less than \$500,000.00 for each accident and not less than \$500,000.00 aggregate. In addition, the Contractor shall maintain in force an Umbrella Liability Policy covering Bodily Injury and Property Damage in the amount of not less than \$500,000.00. Each policy shall include contractor's Protective Liability Insurance with the same minimum limits and completed operations coverage.

11.4 Owner's Liability Insurance

11.4.1 For the duration of this Contract, the Contractor shall purchase and maintain insurance described in paragraphs 11.2.1 in the minimum amount of the cost of construction and for the Owner's Liability and shall contain the same specific endorsements which the Contractor places on the insurance required by paragraphs 11.2.1.

11.5 All Risk Builders' Risk

11.5.1 For the duration of this Contract, the Contractor shall maintain an All Risk Builder's Risk Policy including collapse endorsements up to 100% of the insurable value of the work. This insurance shall include the interest of the Contractor, Subcontractors and the Owner. Form of policy used shall be Builder's Risk.

11.6 General Insurance Requirements

11.6.1 The Contractor shall not commence work at the site under this Contract until he has obtained all the required insurance and until such insurance has been approved by the Owner and the Architect. Contractor shall not allow any Subcontractor to commence work until all similar required insurance has been obtained and approved. Approval of insurance by the Owner and the Architect shall not relieve or decrease the liability of the Contractor hereunder.

11.6.2 Certificates of Insurance shall be filed with the Owner and the Architect prior to commencing the work. Failure to furnish either satisfactory insurance or the required certificates within Ten (10) days of Notice to Proceed shall not be considered cause for modification of any contractual time limits.

11.6.3 The required insurance must be written by a company licensed to do business in Texas at the time policy is issued. In addition the Company must be acceptable to the Owner.

11.6.4 The Contractor shall not cause any insurance to be cancelled or permit any insurance to lapse. All insurance policies shall include a clause to the effect that the policy shall not be cancelled or reduced, restricted or limited until Fifteen (15) days after the Owner has received written notice as evidenced by return receipt of registered or certified letter.

11.6.5 Certificates of Insurance shall contain transcripts from the proper Officer of the Insurer, evidencing in particular those insured, the extent of the insurance, the location and the

operations in which the insurance applies, the expiration date and the above mentioned Notice of Cancellation Clause.

ARTICLE 12 - UNCOVERING AND CORRECTION OF WORK

12.2 Correction of Work: Add the following paragraph:

12.2.7 The Contractor shall furnish the Owner with a written guarantee against defective material and workmanship for a period of ONE YEAR from the date of FINAL ACCEPTANCE OF THE WORK. He shall secure all written guarantees and warranties called for in the specification. The Contractor is responsible for the guarantee on the entire work performed under this agreement with the Owner. Where guarantees are specified in any section of the specifications for longer periods, such longer periods shall apply.

ARTICLE 14 - TERMINATION OR SUSPENSION OF THE CONTRACT

14.2 Termination by the Owner for Cause: Add the following sentence:

14.2.4 The cost incurred by the Owner as herein provided and damage incurred through the Contractor's default shall be certified by the Architect, and his findings shall be prima facie evidence as to the facts of such damage and expense.

END OF SECTION

SECTION 01000

SPECIAL CONDITIONS

DIVISION 1 - GENERAL REQUIREMENTS

Part 1 - Site

- 1.1 This property is located in Leon Valley (Bexar County), Texas.
- 1.2 The Contractor should familiarize themselves with the site including topography, utilities, trees to remain and all other conditions that may affect the project. For new construction the Contractor shall "stake" the project with the Architect's approval before commencing work. Any discrepancies from the site drawings should be brought to the immediate attention of the Architect.

Part 2 - Summary of the Work

- 2.1 Work under the Contract: The Contractor shall supply all labor and materials, transportation, apparatus, light, energy, scaffolding, and tools necessary for the proper execution and completion of the work. He shall install, maintain and be responsible for the safe, proper and lawful maintenance and use of the same. Construct in the best and most workmanlike manner the complete project and everything properly incidental thereto as shown on the drawings, stated in the specifications or reasonably implied therefrom, and in accordance with the Contract documents. This contract includes Structural, Mechanical and Electrical Work.

Part 3 - Construction Procedures

- 3.1 The use of insufficient labor or equipment for construction purposes or inadequate scheduling of materials or equipment to be installed will not be allowed as the cause for delay. Labor, materials, and equipment shall be scheduled to the site in such quantities as required for the uninterrupted progress of the work and the least obstruction of the premises. No extension of time or extra cost will be allowed for failure by the Contractor to order on time in sufficient quantities.

- 3.2 Protect finished work: Cover and protect finished floors, steps, treads, etc., against damage by workmen, equipment, etc., during the work. Wherever concrete, paint, cement, equipment, etc., are hoisted or carried into the building, the brick walls, aluminum work, windows, etc., adjacent to the hoisting must be covered with a heavy layer of building paper, and floors and steps over which any material is carried must be well covered to protect all work against damage.
- 3.3 Measurements: Before ordering any material or starting any work each Contractor shall verify all measurements at the building and shall be responsible for the correctness of same. No exchange or compensation will be allowed on account of difference between actual dimensions and measurements indicated on the drawings. Any difference which may be found shall be submitted to the Architect for instructions before proceeding with the work.

Part 4 - Compliance with Ordinances and Public Safety

- 4.1 The Contractor shall secure and pay for all necessary permits and shall comply with ordinances pertaining to the work. He shall provide and maintain temporary walkways, where needed, fences and other structures required by Federal and State Regulations and Local Ordinances in such manner as not to interfere with traffic in public streets. He shall leave access to fire hydrants and protect public and adjacent property at all times during the progress of the work. The proper signs shall be posted at all truck entrances, and all other proper safety precautions observed. Contractor shall comply with all applicable provisions of the National Occupational Safety and Health Act (NOSHA), 1970. Contractor will be held liable for damage to property or persons.

Part 5 - Materials and Equipment

- 5.1 Materials and Workmanship: Unless specified to the contrary, all materials of construction shall be new and of best grade and kinds specified, and all workmanship shall be of the best recognized standards known to the various trades.
- 5.2 Transportation and Handling: Methods of crating, transportation and handling of materials and equipment, on or off the site, shall be such as to assure their ultimate installation is undamaged and in perfect working condition.
- 5.3 Storage and Protection: Provide weather protection of the work, materials and equipment, whether incorporated in the building or not. Cover building openings to protect interior from weather when necessary. Provide absolute watertight protection at all times.

Part 6 - Separate Contracts

- 6.1 Although it is contemplated that this Contract shall include all the work to be done at this time, it is possible that the Owner may let other contracts in connection with the work herein specified. In the event, the Owner reserves the right to do so, in which case the Contractor will afford reasonable opportunity for the storage of materials and execution of the work done by others.

Part 7 - Scaffolds and Runways

- 7.1 The Contractor shall furnish and erect and maintain for the duration of the Contract as required, all scaffolds, runways, guard-rails and forms and similar temporary construction as may be necessary for the performance of the Contract. Such facilities shall be of type and arrangement as required for their specific use; shall be substantially constructed throughout, strongly supported and well secured and shall comply with all applicable rules and regulations of Federal, State and Local Codes. The several levels of the structure shall be connected by means of suitable ladders, ramps and temporary stairs; provided however that the permanent stairways may be used for such purposes if adequately protected against damage. Open halls and shafts shall be enclosed as required by the Department of Public Safety.

END OF SECTION

SECTION 01300**SUBMITTALS****1. Standards:**

Reference in these specifications to any article, device, product, materials, fixture, form or type of construction, etc., by proprietary name, make or catalog number, shall be interpreted as establishing a standard of quality and shall not be construed as limiting competition. All materials, supplies and articles furnished shall be the standard products of recognized reputable manufacturers.

2. Substitutions:

Should the Contractor desire to substitute any equal material or brand or manufacturer other than that specified, he shall, within seven (7) days after the Contract is awarded, submit to the Architect a written request for approval of all the substitutions he wishes to make. Such requests shall be accompanied, if feasible, by samples of each material proposed as a substitute. In all instances, such requests shall be accompanied by complete descriptive literature and performance data. The Architect will investigate all such requests and render written decisions thereon as promptly as is reasonably possible, and such decisions shall be final.

3. Shop Drawings:

Shop drawings of all trades shall be submitted only by the General Contractor, who shall indicate by signed stamp on each sheet of the drawings that the work shown is in accordance with the Contract requirements and has been checked for dimensions, quantities, and relationship with work of all trades involved. Any shop drawings submitted without the General Contractor's signed stamp thereon will be returned unchecked. The Architect's checking of shop drawings shall be for design and general conformity only. Shop drawings shall be required only on items requiring special construction.

END OF SECTION

SECTION 01341**STRUCTURAL ENGINEER: SHOP DRAWINGS AND FIELD VISITS****PART 1 - GENERAL****1.1 RELATED DOCUMENTS**

Construction drawings and the general provisions of the Contract.

1.2 SCOPE

This section describes specific items of Article 4 of the Contract that are peculiar to the responsibility of the structural engineer.

PART 2 - DEFINITIONS**2.1 STRUCTURAL ENGINEER OF RECORD**

The engineer responsible for the design of the primary structural system and whose seal and signature appears on the contract structural drawings. The responsibility for any secondary structural and non-structural systems not shown on the contract structural documents rests with the prime professional, the architect.

2.2 SPECIALTY ENGINEER

The engineer who is licensed in the state in which the project is being constructed to seal plans and designs for pre-engineered elements and systems which will become part of the overall building.

2.3 SUBMITTALS

Items identified in the contract documents to be submitted by the contractor. Refer to individual sections of these specifications for specific items to be submitted.

2.4 SITE VISITS

Visits to the project jobsite by the structural engineer-of-record or his authorized representative to ascertain whether the work is generally in accordance with the contract structural documents. These observations are not exhaustive nor continuous.

PART 3 - PROCEDURES**3.1 SUBMITTALS**

Refer to the Architect for specific requirements for number of copies to be submitted, time for review, etc. All submittals must come by way of the general contractor through the architect. Certain submittals, identified in specific sections of these specifications, generally regarding Pre-engineered elements, will require a specialty engineer's seal and Signature.

3.2 SITE VISITS

Structural engineer shall be notified at least 24 hours in advance of any action that will cover up structural elements that have not been observed by an authorized representative of the office of the structural engineer of record.

3.3 ENGINEER'S ACTIONS**A. SUBMITTALS WITH SPECIALTY ENGINEER'S SEAL AND SIGNATURE**

Certain submittals may be identified in specific sections of these specifications pertaining to pre-engineered structural elements specified by the structural engineer-of-record and designed by the specialty engineers. Submittals shall bear the signature and seal of the specialty engineer responsible for the design as required by the contract documents. The structural engineer shall review the submittal for type, position, and connection to other elements of the primary structural system, and for criteria and loads used for their design.

B. SHOP DRAWINGS

In accordance with the General Conditions, the structural engineer of record will review shop drawings for the limited purpose of checking for general conformance with information given and the design concept expressed in the contract structural documents.

The structural engineer-of-record shall review each submittal and return them to the architect with one of the following statements checked off on the stamp.

1. "NO EXCEPTIONS TAKEN" informs the Architect that the structural engineer takes no exception to the submittal being approved as per and in accordance with AIA Document 201, section 4.2.7.

2. "MAKE CORRECTIONS NOTED" informs the Architect that the structural engineer has made corrections or comments on the submittals but otherwise takes no exception to the submittal being approved as per and in accordance with AIA Document 201, section 4.2.7.
3. "REVISE AND RESUBMIT" indicates important items must be corrected and resubmitted. Comments made on the submittal may not necessarily cover all of the defects of the submittal. This action constitutes the structural engineer's concern and his recommendation to the Architect that the submittal be reviewed and resubmitted as per and in accordance with AIA Document 201, section 4.2.7.
4. "RETURN ONE CORRECTED COPY FOR FILE" informs the Architect that the submittal may be approved as per AIA Document 201, section 4.2.7, but a single corrected copy showing that corrections have been acknowledged must be returned for the structural engineer's file.

3.4 VISITS TO THE PROJECT SITE

- A. The structural engineer-of-record ("SER") will make site visits at appropriate stages of construction and as defined by the contract to visually observe the quality and the progress of the construction work relative to the primary structural system. The general contractor is responsible to notify the SER when structural elements are ready for review and prior to their being covered up. Failure to do so may result in key observations not being made, preventing the engineer from recommending acceptance of the work. A written report will be made of each visit describing what was observed and listing discrepancies, if any. One copy will be given to contractor's representative at the jobsite, and one copy will be mailed to the office of the Architect. If a subsequent visit is necessary it will be so noted on the report.
- B. The SER shall not have control over or charge of and shall not be responsible for means and methods of construction, techniques, sequences or procedures, or for safety precautions and programs in connection with the Work for This Part of the Project. These are solely the Contractor's responsibility under the Contract for Construction. The SER shall not be responsible for the Contractor's or a Subcontractor's schedule or failure to carry out the Work in accordance with the Contract Documents. The SER shall not have control over or charge of acts or omissions of the Contractor, Subcontractors, their agents or employees or other persons performing portions of the Work.

END OF SECTION 01341

SECTION 01400**QUALITY CONTROL**

1. **GENERAL:**
 - 1.1 Unless specified otherwise in the Contract documents, testing laboratory services for Quality Control shall be conducted by a recognized independent testing agency selected by the Architect and paid for by the Owner.
 - 1.2 In the event certain materials of construction do not measure up to the required standards or certain performance obligations are not met, the defective material and or work shall be removed and replaced at the contractor's expense and subsequent testing and related work necessitated by the replacement shall be paid by the Contractor and / or related Sub-contractor.
 - 1.3 The laboratory shall submit detailed invoices, based on agreed unit prices, monthly to the Architect for payment.
 - 1.4 Professional laboratory services shall include but not necessarily be limited to the following:
 - .1 Soil compaction
 - .2 Cast in place concrete, including making and testing of concrete cylinders during progress of the work, including related slump tests.
 - 1.5 Testing and services by Contractor / Sub contractor and laboratories: Concrete mix designs.
 - 1.6 Responsibilities of Contractor and/or Sub contractor regarding testing laboratory: Selection of the Laboratory by the Architect in no way relieves the Contractor and/or Sub contractor of his/their responsibility to furnish materials and construction in full compliance with the drawings and specifications.
 - 1.7 Advise the selected laboratory sufficiently in advance of construction operations to allow laboratory to complete any required check tests and assign personnel for field inspection and testing as specified.
 - 1.8 Provide adequate facilities for safe storage and proper curing of concrete test samples on project site for the first 24 hours and also for subsequent field curing required.
 - 1.9 Authority and duties of laboratory personnel: Should it appear that the material furnished and/or work performed by the Contractor and/or Sub contractor fail to meet requirements of the Contract Documents, the

Laboratory Inspector shall direct the attention of the Contractor and the Architect to such failure and infringement.

1.10 The Laboratory Inspector is not authorized to revoke, alter, relax, enlarge or release any requirements of the drawings and specifications, or to approve or accept any portion of the work

1.11 Reports: The laboratory shall report to the Owner on each and every service rendered, with copies mailed as follows:

One (1) Copy to the Architect as directed.

Two (2) Copies to the Contractor as directed.

One (1) Copy to each related Engineer and/or Consultant as directed.

END OF SECTION

SECTION 01500**TEMPORARY FACILITIES & CONTROL**

1. The Contractor shall provide a complete set of drawings and specifications on the job site, which shall remain until the full completion of the work.
2. **TEMPORARY UTILITIES:** The Contractor shall make all necessary arrangements and pay for all water and electric power as may be required during the period of construction for whatever purpose such service may be required and until such time as the construction is completed and accepted by the Owner. The Contractor will be required to pay for the providing and installations of all conduits, wires, switches, storage tanks, piping, valves, fittings, hose connections, safety devices, etc. necessary for this purpose and shall maintain the same in good condition throughout the period of their use and shall remove them upon completion of the work. Proper precautions shall be taken to prevent leaks, short circuits, etc. and any such defects which develop will be promptly and efficiently repaired.
3. **TEMPORARY HOISTS:** The Contractor shall install and operate all temporary hoists as his needs may require. The contractor shall erect such temporary stairs as may be required for his operations. The Contractor shall erect and maintain suitable handrails and toeboards around all openings in floors and roofs and wherever else required for proper safety precautions. All the foregoing requirements shall be constructed in accordance with the requirements of the Occupational Safety and Health Act of 1970.
4. **TEMPORARY HEAT:** The contractor shall provide and maintain temporary heat as required for the work during and throughout the entire period of construction to protect all work, materials and equipment against injuries from dampness and cold. The permanent heating system may be utilized for this purpose after installation. However, if so utilized, the contractor shall:
 - 4.1 Pay for all charges in conjunction with repairs and/or replacement to heating equipment and devices during his use of such equipment in order that heating equipment shall be turned over to the Owner in first class operating and equal to new condition with all filters and ductwork cleaned as necessary. If required replace filters.
 - 4.2 **Insurance:** Builder's Risk Insurance Policies shall be endorsed to permit the operation of permanently installed equipment (other than a testing basis) for temporary use by the Contractor or Owner.
 - 4.3 Temporary use of equipment shall in no manner effect warranties and guarantees. Warranty and Guarantee periods shall be effective from the date of acceptance of the equipment by the Owner.

5. **TEMPORARY SANITARY FACILITIES:** The Contractor shall furnish, install and maintain ample sanitary facilities for the use of his workmen and those of sub-contractors. Portable type facilities will be permitted. Sanitary facilities shall be furnished at the time work is commenced and shall be maintained in compliance with all applicable health laws and regulations and the use of such facilities shall be enforced. Mechanics and laborers in the employ of the Contractor and sub-contractors shall not be permitted to use other than the toilet facilities provided. Upon completion of the work the Contractor shall remove the temporary sanitary facilities and all traces thereof.
6. **TEMPORARY ELECTRIC LIGHTING:** The General Contractor shall provide for temporary electricity to be used for lighting within the building during construction work. Sufficient lighting shall be provided in rooms and areas where crafts or trades are working so that quality work performed will be in accordance with the acceptable standards of the trade.
7. **CUTTING AND FITTING:** Except as otherwise specified, each sub-contractor shall execute all cutting and fitting in his work that may be required by others so that the engagements between the various materials will be neat and proper. Cutting of any structural portions of the building shall not be permitted except as approved by the Architect. Each sub-contractor shall locate and provide sleeves, suitable to the Architect, for all holes, chases, openings or blockouts required for the installation of the work. All such openings shall be straight, true and of the proper size. No excessive cutting will be permitted. After the work has been installed, all openings shall be carefully fitted around as directed and to the satisfaction of the Architect.
8. **LABOR:** The Contractor and each sub-contractor shall comply with all applicable laws regulating the employment of labor.
9. **PROGRESS MEETINGS:** The contractor and selected sub-contractors shall meet at the building site or at some other designated meeting place at such intervals as necessary to maintain optimum degree of communication for the progress of the work.
10. **SUPERVISION:** Each sub-contractor shall designate some one person of its employ, having the responsibility and authority to act as so directed by the Contractor to accomplish the terms and conditions of the Agreement, Drawings and Specifications. The sub-contractor shall bear full responsibility for any delays caused by failure to comply with this requirement.
11. **CLEANING:** Each sub-contractor shall be responsible for leaving all finish surfaces cleaned and, where applicable, polished and left in perfect condition. All areas shall be broom cleaned and rubbish removed from the premises at completion of each phase of the work or as directed by the Contractor. The contractor shall promptly remove from the lot, sidewalks and streets all rubbish and dirt due to the work done under the contract. The Contractor shall provide and maintain suitable refuse cans for the use of workmen (lunch sacks, garbage, etc.).
12. **FIRE PROTECTION:** The Contractor and sub-contractors shall observe and the Contractor shall enforce throughout the work during the whole period of construction all requirements of

City Ordinances, State and Insurance Authorities, O.S.H.A., to minimize the fire hazards during the progress of the work.

END OF SECTION

SECTION 01650**ALLOWANCES****1.0 SCOPE**

- 1.1 Cash Allowances are for materials only except where noted otherwise. Allowances include cost of delivery to the job site and all taxes paid.
- 1.2 Cash Allowances are hereby established for the time and in the amounts listed below. If any items exceed the amount listed, such excess cost shall be paid by the Owner. If any items cost less than the amount Contractor or Sub-Contractor(s) paid, whichever makes the direct purchase, the difference in cost shall be credited to the owner.

2.0 ALLOWANCE ITEMS:

2.1	<u>Item</u>	<u>Allowance</u>
A.	Contingency Allowance	\$ 10,000
B.	Furniture by owner. (Built-in computer stations in contract.)	
C.	Carpet Tiles	\$21 per S Y
D.	Security; Consult owner for coordination of "tie in" to existing library security system. This work is not in the scope of this project.	
E.	Ceramic tile at Toilet Room walls and base	\$ 3 per SF
F.	Porcelain Tile at Toilet Room floors	\$5 per SF
G.	Wall mounted light sconces at Toilet Rooms (2 each)	\$200 per fixture

3.0

Contractor to coordinate with Owner and Architect the selection of all items listed above.

END OF SECTION

Children's Wing

Leon Valley Public Library

SECTION 01700**PROJECT CLOSEOUT**

1. **COMPLETION OF CONTRACT:** The contract will be considered fulfilled, save as provided in any maintenance stipulations, bond, or by law, when all the work has been completed, the final inspection made by the Final Inspection Team, and final acceptance and final payment by the Owner.
2. **USE PRIOR TO COMPLETION:** When in the opinion of the Architects any section or portion of the work is in suitable condition, it may be put into use upon the written order of the Architect, and such usage shall not be held in any way an acceptance of said work or any part thereof or as a waiver of any of the provisions of the Contract Documents pending final completion and acceptance of the work; all necessary repairs and removals of any portion of the work so put into use, due to defective materials or workmanship or to operations of the Contractor, shall be performed by the Contractor at his own expense.
3. **PROCEDURES AT COMPLETION:** When the Architects determine that all of the work is substantially complete the Architects will prepare and submit to the contractor a punch list of items to be completed or corrected prior to the final inspection. The failure to include any items on such list does not alter the responsibility of the Contractor to complete all work in accordance with the Contract Documents. After receiving the punch list from the Architects, the Contractor shall proceed immediately to correct the items thereon. When all items on the punch list have been corrected, the Contractor shall notify the Architects that the work is ready for final inspection.
4. **FINAL INSPECTION AND ACCEPTANCE:** When the work has been satisfactorily completed, including correction items contained on the punch list, and all detailed inspections and test requirements has been satisfied, the Contractor shall notify the Architects in writing to make the final inspection. Provided the work is ready for final inspection, such inspection will be commenced within ten (10) days after date of such notification, and will be completed as promptly as practicable. The final inspection will be made by the Final Inspection Team which shall include representatives of the Owner and the Architects. After final inspection, if the work is found to be satisfactory, notice of final acceptance by the Owner will be provided in writing by the Architects to the Contractor. If the work is found to be unacceptable at the time of the final inspection, the Architects will inform the Contractor of the particular defects that must be remedied before final acceptance will be made. Also at this time, the Owner may elect to advise the Contractor in writing that a conditional acceptance has been made. The conditional acceptance shall to the extent set for therein relieve the Contractor of responsibility for the maintenance, security, and insurance on the work and shall also be used to establish the time of the work; in no case, however, will a conditional acceptance relieve the Contractor of the responsibility for performing all the work set forth in the Contract including the correction of

deficiencies noted at the time that the conditional acceptance is made; and the Owner shall be entitled to retain from the Contractor's payment an amount to commensurate with the work remaining to be accomplished.

5. **MAINTENANCE PROVISIONS FULFILLMENT:** Prior to the expiration of the specified maintenance period provided for in the Contract, the Architects will make a detailed inspection of the work and will advise the Contractor and his surety of the items that require correction. The Architects will make a subsequent inspection and if the corrections have been properly performed, the Architects will issue a letter of release on the maintenance stipulations to the Contractor and his surety. If for any reason the Contractor has not made the required corrections before the expiration of the maintenance period, the maintenance stipulations as provided for in the Contract shall remain in effect until the corrections have been properly performed and a letter of release issued.
6. **RECORD DRAWINGS:** As work progresses, the Contractor shall keep complete and accurate records of all changes or deviations from the Contract documents including drawings and specifications indicating the work as actually installed. All such changes shall be neatly and correctly shown on black-line prints of the Contract drawings affected or in the specifications with appropriate supplemental notes. This record set of prints of the drawings and specifications shall be kept at the job site.

CERTIFICATION OF RECORD DRAWINGS - At the completion of the work the contractor shall certify by endorsement thereof that each of the revised drawings is complete and accurate. Prior to the Contractor's application for final payment, and as a condition to its approval by the Owner, the Contractor shall deliver the certified record drawings, as specified above to the Owner, indexed and marked for each division of the work.

7. **MANUALS, PARTS, LISTS AND INSTRUCTIONS:** After the approval of selected equipment and materials, and prior to final acceptance, the Contractor shall submit to the Architects a minimum of two (2) copies of manuals, parts lists and instructions necessary for the operation and maintenance of such items.
 - 7.1 **Manual and Spare Parts Lists:** The Contractor shall submit manufacturer and vendor data, to include operating and maintenance manuals, operation instruction and parts lists, as required by the technical provisions. Technical adequacy of this data shall be subject to approval by the Architects.
 - 7.2 **Presentation of Data:** Wherever possible data shall be presented on 8-1/2" x 11" sheets. Foldouts will normally be limited to 11" x 17" sheets. Light sensitive reproduction techniques are acceptable provided finished pages are clear, legible, and not subject to fading.

NOTE: Caution and Warning indications shall be clearly identified.

- 7.3 Spare Parts Lists: A spare parts list shall be furnished which shall include those repair parts recommended by the manufacturer to assure efficient operation for one year's normal operation following expiration of the guaranty period.
8. REPORTS CERTIFICATED AND SPECIAL GUARANTEES: The Contractor shall submit, prior to final payment, reports, certificates and special guarantees required by the Contract Documents.

The Contractor shall and hereby does warrant and/or guarantee all work for a period of one (1) year from the date of completion, as evidenced by the date of final acceptance of this work. This provision shall not be considered as conflicting with stated guarantees for longer periods. The guarantees imply and require that faulty materials, workmanship and/or errors be promptly corrected by the Contractor without cost to the Owner.

9. PERIODIC AND FINAL PAYMENTS: Shall be in accordance with the terms of the Contract.

END OF SECTION

SECTION 02010 - SUBSURFACE CONDITIONS

PART 1 - GENERAL

1.1 GENERAL

An independent Geotechnical Consultant and Testing Laboratory has been employed by the owner to perform a soil and foundation investigation for this Project Site. A report of their findings is available for examination at the Architect's Office.

1.2 REPORT CONTENTS

- A. The information and recommendations contained in the soils report were obtained by the Owner only for the use of the Architect and the Structural Engineer in the design and preparation of the Contract Documents for this Project. This report is not intended to be used for any other purposes.
- B. The report is not a warranty of subsurface conditions at the Project site.
- C. Bidders are encouraged to visit the Project site and acquaint themselves with all existing conditions prior to bidding. Bidders may, at their own expense, perform additional subsurface investigations; however, all such investigations must be performed under arrangements approved in advance by the Architect.

1.3 TESTING AND INSPECTIONS

Refer to Section 02224 Foundation Earthwork for Buildings.

END OF SECTION 02010

SECTION 02100

SITE PREPARATION

PREFACE

The general provisions of the Contract, including the Conditions of the Contract (General, Supplementary and other Conditions) and Division 1 as appropriate, apply to the Work specified in this Section.

1.0 SCOPE

1.1 This Section covers the removal of sections of existing asphalt and concrete curb as indicated on plans, vegetation; topsoil stripping; clearing and grubbing; removing above-grade improvements; removing below-grade improvements.

1.2 Project Conditions

Traffic: Conduct site clearing operations to ensure minimum interference with roads, walks, and other adjacent occupied or used facilities. Do not obstruct streets, walks or other occupied or used facilities without permission from authorities having jurisdiction.

Protect improvements on adjoining properties and on Owner's property.

1.3 Existing Services

Arrange and pay for disconnecting, removing, capping and plugging utility services. Notify affected utility companies in advance and obtain approval before starting this work.

1.4 Site Clearing

Remove trees, shrubs, grass and other vegetation, improvements, or obstructions, as required to permit installation of new construction. Removing abandoned underground piping or conduits interfering with construction is included under this section.

1.5 Disposal of Waste Materials

Burning on Owner's Property is not permitted.
Remove waste materials and unsuitable or excess topsoil from Owner's Property.

END OF SECTION

SECTION 02221

REMOVING EXISTING PAVEMENT AND STRUCTURES

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Removing asphalt paving and portion of concrete curb.

1.02 REGULATORY REQUIREMENTS

- A. Conform to applicable codes for disposal of debris.
- B. Coordinate removal work with utility companies.

PART 2 PRODUCTS – NOT USED

PART 3 EXECUTION

3.01 PREPARATION

- A. Obtain advance approval from Project Manager for dimensions and limits of removal work.
- B. Identify known utilities below grade. Stake and flag locations.

3.02 PROTECTION

- A. Protect following from damage or displacement:
 - 1. Adjacent public and private property.
 - 2. Trees, plants, and other landscape features designated to remain.
 - 3. Utilities designated to remain.
 - 4. Pavement and utility structures designated to remain.
 - 5. Bench marks, monuments, and existing structures designated to remain.

3.03 REMOVALS

- A. Remove pavements and structures by methods that will not damage underground utilities. Do not use drop hammer near existing underground utilities.
- B. Minimize amount of earth loaded during removal operations.
- C. Where existing pavement is to remain, make straight saw cuts in existing pavement to provide clean breaks prior to removal.

- D. Where new curb connects to existing portions of remaining curb, provide an ½” compressible filler material between face cut of existing curb and new curb face.

3.04 BACKFILL

- A. Backfill of removal areas shall be in accordance with jurisdictional standards.

3.05 DISPOSAL

- A. Remove from site, debris resulting from work under this section in accordance with jurisdictional standards.

END OF SECTION

SECTION 02224 - FOUNDATION EARTHWORK FOR BUILDINGS

1.1 RELATED DOCUMENTS

Construction drawings and general provisions of the contract, including General and Supplementary Conditions and Division-1 Specification sections, apply to work of this section of these specifications.

1.2 RELATED WORK SPECIFIED ELSEWHERE

A. Site Clearing Section 02110

1.3 DESCRIPTION OF WORK

A. DEFINITIONS

1. "Excavation" consists of removal of all material encountered to subgrade elevations indicated and subsequent, proper disposal of material removed.
2. "Building" shall include any attached walkway or other foundations shown on the contract structural drawings.

B. EXTENT OF WORK

Earthwork in this section is limited to the requirements of construction of the building foundation.

C. MECHANICAL/ELECTRICAL WORK EXCAVATIONS

Excavation and backfill required in conjunction with underground mechanical and electrical utilities, and buried mechanical and electrical utilities, and buried mechanical and electrical appurtenances is specified elsewhere.

1.4 QUALITY CONTROL

The contractor shall employ, at his expense, a commercial construction testing laboratory to perform soil testing and inspection service for quality control during earthwork operations, as specified elsewhere. The laboratory shall be the original Project Geotechnical Engineer or an alternate approved by the Structural Engineer.

1.5 SUBMITTALS

TEST REPORTS-EXCAVATING

Submit the following reports directly to Architect/Engineer from the testing laboratory, with copies to Contractor:

- A. Verification of specified depth of excavation.
- B. Field density test reports, as follows:
 - 1. One optimum moisture-maximum density curve for each type of soil encountered.
 - 2. Report of actual unconfined compressive strength and/or results of bearing tests of each strata tested.

PART 2 - PRODUCTS

2.1 SELECT FILL MATERIAL

Refer to contract drawings.

PART 3 - EXECUTION

3.1 EXCAVATIONS

A. EXCAVATION

Refer to contract drawings.

B. UNCLASSIFIED EXCAVATION

Excavation is unclassified, and includes excavation to subgrade elevations indicated, regardless of character of materials and obstructions encountered.

C. UNAUTHORIZED EXCAVATION

- 1. Unauthorized excavation consists of removal of materials beyond indicated subgrade elevations or dimensions without specific

direction of Architect/Engineer. Unauthorized excavation, as well as remedial work directed by Architect, shall be at the Contractor's expense.

2. Earthwork described above shall be performed before trenching for grade beams and mechanical lines.

3.2 DE-WATERING

- A. Contractor shall implement a plan to prevent surface water and subsurface or ground water from flowing into excavations and from flooding building site and surrounding area.
- B. Establish and maintain temporary drainage ditches and other diversions outside excavation limits to convey rain water and water removed from excavations to run-off areas. Trench excavations shall not be used as temporary drainage ditches.
- C. Water shall not be allowed to accumulate in excavations. Remove water to prevent softening of foundation bottoms, undercutting footings, and soil changes detrimental to stability or subgrades and foundation. Provide and maintain pumps, well points, sumps, suction and discharge lines, and other de-watering system components necessary to convey water away from excavations.

3.3 PROOF ROLLING OF SUBGRADE

After initial excavation of surface soils, the exposed subgrade shall be proof rolled to locate density weak and compressible zones utilizing a 15 ton piece of equipment. Any soft spots identified shall be removed and replaced with select fill compacted as specified herein.

3.4 COMPACTION

Refer to contract drawings.

3.5 QUALITY CONTROL

- A. Testing laboratory shall be allowed to inspect and approve subgrades and fill layers before further construction work is performed.

- B. Field density tests shall be in accordance with ASTM D698.

3.6 TESTING OF SUBGRADE AND COMPACTED FILL

- A. If, in opinion of the testing laboratory and/or the Architect/Engineer, based on testing service reports and inspection, subgrade or fills which have been placed are below specified density, the contractor shall perform additional compaction and testing at no additional expense to the owner.

3.7 MAINTENANCE

- A. Protect newly graded areas from traffic and erosion.
- B. Keep area free of trash and debris.

3.8 RECONDITIONING COMPACTED AREAS

Completed compacted areas which are disturbed by subsequent construction operations or adverse weather, shall be scarified, re-shaped, and compacted to specified densities prior to further construction.

3.9 DISPOSAL OF EXCESS AND WASTE MATERIALS

All waste materials, including unacceptable excavated material, trash and debris, and shall be disposed off the Owner's property.

END OF SECTION 02224

SECTION 02230**SITE CLEARING****PART 1 - GENERAL****1.1 SCOPE**

- A. Perform all work required to complete the project as indicated by the Contract Documents, and furnish all supplementary items necessary for the completion of all work specified in this Section.
- B. Completely coordinate with work of all other trades.
- C. Although such work is not specifically indicated, furnish and install all supplementary or miscellaneous items, appurtenances and devices incidental to or necessary for a sound, secure and complete installation. Also included in this section: the preparation of the storm water pollution prevention plan; completion of the "Notice of Intent"; submittal of the "Notice of Intent" per the Environmental Protection Agency (EPA) requirements; installation of the erosion control devices per the erosion control plan.

1.2 RELATED WORK SPECIFIED ELSEWHERE

- A. Section 02210 - Site Earthwork
- B. Section 02920 - Topsoiling and Finished Grading

1.3 QUALITY ASSURANCE

- A. Perform work in accord with OSHA and EPA requirements and state and local requirements.

PART 2 - EXECUTION**2.1 SUBMITTALS**

- A. Complete EPA "Notice of Intent" and submit per the EPA requirements.

2.2 PROTECTION

- A. Provide barricades, coverings, and other protection necessary to prevent damage to existing improvements to remain.
 - 1. Protect improvements on adjoining properties as well as those on Owner's property.
 - 2. Restore improvements damaged by this work to original condition, as acceptable to Owner, other parties, and authorities having jurisdiction.
- B. Protect existing vegetation, including trees, to remain against damage.
- C. Repair or replace vegetation, including trees, damaged by construction operations.

2.3 IMPROVEMENTS ON ADJOINING PROPERTY:

- A. Owner will obtain authority for performing removal and alteration work, if any, on adjoining property.

2.4 SITE CLEARING - GENERAL

- A. Install Erosion Control Devices
- B. Remove vegetation, improvements, or obstructions that interfere with new construction.
 - 1. Removal includes stumps of the trees and their roots.
 - 2. Removal includes all structures that interfere with new construction to a depth of two feet below finished grade.
 - 3. All open structures below grade, shall be filled to finish grade. Backfill of open structures shall meet the requirements as specified in Section 02210.
- C. Remove other items when specifically indicated.

2.5 CLEARING

- A. Clear from above surface of existing ground all brush, downed timber, rotten wood, heavy growth of grass and weeds, vines, rubbish, debris that interferes with new construction and legally dispose of offsite. Remove stones larger than 4 in. in any dimension and tree roots larger than 2 inches in diameter and legally dispose of offsite.
- B. Limits of clearing to include all areas that are disturbed in the course of work.

2.6 REMOVAL OF IMPROVEMENTS

- A. Remove surfacing and pavements, including bases, concrete slabs, concrete and masonry walls, structures, buildings, posts, poles, fences, and other items on the property.

2.7 STRIPPING SITE

- A. Strip all vegetated areas that are to be disturbed by construction to a depth of two inches.
 - 1. Strip to prevent intermingling with underlying topsoil.
 - 2. Strippings shall be removed from the site.

2.8 TOPSOIL REMOVAL AND SALVAGE

- A. DEFINITIONS
 - 1. Topsoil: A layer of organic material typically 6 to 12 inches thick below the two inches of material to be stripped.
- B. Remove topsoil under proposed pavements, extending 2 ft. minimum beyond the pavement edge. Remove to prevent intermingling with underlying subsoil or objectionable material.
- C. Stockpile the amount of topsoil required to complete the work specified in Section 02920.
- D. Stockpile topsoil in areas as indicated by the owner or owner's representative.
 - 1. Maximum stockpile height shall be 8 feet.
 - 2. Maximum stockpile side slopes shall be 3 (horizontal) to 1 (vertical).
 - 3. Construct storage pile to freely drain surface water.
 - 4. Seed or cover storage piles to prevent erosion.

2.9 DISPOSAL OF WASTE MATERIALS

- A. Burning of materials is not allowed.
- B. Remove all waste materials from site and dispose of in a legal manner.
- C. Remove concrete and masonry from site.

END OF SECTION

SECTION 02251
TERMITE CONTROL

PREFACE

The general provisions of the Contract, including the Conditions of the Contract (General, Supplementary and other Conditions) and Division 1 as appropriate, apply to the Work specified in this Section.

1.0 SCOPE

- 1.1 This section includes Soil Treatment
- 1.2 Submit five year guarantee for the effectiveness of the treatment.

2.0 MATERIALS

- 2.1 Use soil treatment chemicals and concentrations acceptable by FHA standards or passing a U.S. Forest service five year test.

3.0 EXECUTION

- 3.1 Treat areas under slab and grade beams before placing vapor barrier.

END OF SECTION

SECTION 02550

SITE UTILITIES

PREFACE

The general provisions of the Contract, including the Conditions of the Contract (General, Supplementary and other Conditions) and Division 1 as appropriate, apply to the Work specified in this Section.

1.0 SCOPE

- 1.1 The requirements of this section include the furnishing of all materials, labor, and equipment required for the completion of the Work. See the drawings for the extent of the utility work under this contract.

2.0 MATERIALS

As required for Bexar County, Texas Compliance installation

3.0 EXECUTION

- 3.1 Contractor, Owner, and Architect shall review all Proposals prior to construction.

END OF SECTION

**SECTION 02700
ONSITE PIPED UTILITIES**

PART 1 - GENERAL**1.1 SUMMARY**

- A. Perform all work required to complete the project as indicated by the Contract Documents, and furnish all supplementary items necessary for the completion of all work specified in this Section.
- B. The work included in this Section, while not all inclusive but listed as a guide, shall include furnishing all labor, tools, materials and incidentals required to complete the work; the complete installation of conduit for site lighting and sleeving for future use; and cleaning up.

1.2 RELATED WORK SPECIFIED ELSEWHERE

- A. Section 02210 – Site Earthwork

1.3 STANDARDS

- A. Standards will meet the requirements and recommendations of applicable portions of the standards listed:
 - 1. American Society of Testing and Materials, ASTM.
 - 2. Local Jurisdictional Standards

1.4 JOB CONDITIONS**A. Site Information:**

- 1. The data on indicated subsurface conditions is not intended as representations or warranties of the accuracy or continuity between soil borings. It is expressly understood that the Owner will not be responsible for interpretation or conclusions drawn there from by the Contractor. The data is made available for the convenience of the Contractor. The Contractor, at no cost to the Owner, may make additional test borings and other exploratory operations.

B. Existing Utilities

- 1. It shall be the Contractor's responsibility to verify the location (horizontal and vertical depth) of all utilities prior to beginning construction. If utilities are to remain in place, provide protection from damage during construction operations.
- 2. The Contractor shall notify the Owner and utility companies when working in areas where utility lines might be encountered. The Contractor will be held responsible for all damage to utility lines as a result of work under this contract.
- 3. The Contractor shall not interrupt existing utilities serving facilities occupied and used by the Owner. In the event that service from an active utility line should need to be discontinued for any period of time, the utility will be shut down by the respective utilities. Prior to discontinuing service on any active utility line, the Contractor shall submit a request, in writing, to the Owner stating the need to shut down a specific utility. This request shall be submitted to the Owner a minimum of seven (7) days prior to service being discontinued.

PART 2 - PRODUCTS**2.1 MATERIALS**

- A. Underground Pipe Conduit and sleeving shall be Schedule 40 PVC Pipe unless otherwise noted on the Drawings. The Contractor shall locate and flag all conduits so that they will be readily identifiable by the Owner.

PART 3 - EXECUTION**3.1 GENERAL**

- A. The Contractor shall comply with all requirements of TXDOT Standards and with those specified herein. The most stringent will apply.
- B. It shall be the responsibility of the Contractor to insure that all trenches resulting from the placement of underground utilities are backfilled in accordance with the specifications set forth for this project. In the event that any subcontractor or public utility company fails to properly backfill their trenches, the Contractor at no additional cost shall do this work for the Owner.

3.2 EXCAVATION

- A. The Contractor shall excavate all materials encountered regardless of the difficulties encountered. The ditch shall be no greater in width or depth than is necessary to permit construction in accordance with the plans and these specifications. The maximum width of trench at top of pipe without sheeting, shoring, and bracing shall not be more than the external diameter of pipe plus 16 inches.
- B. All trench excavations shall meet the requirements of the TXDOT and O.S.H.A
- C. Soft, spongy or otherwise unstable material which will not provide a firm foundation for the pipe shall be removed and replaced to the extent required by the Architect. The material thus removed shall be replaced with suitable selected material from the excavation or other sources approved by the Owner and shall be compacted as provided in these Specifications. When unstable conditions are not corrected by the above means, the Contractor will be required to use rock, gravel, concrete or timber foundations. The Engineer shall determine the type of foundation. There will be no extra compensation for this work.

3.3 BEDDING

- A. The bedding for pipe shall provide a firm foundation of uniform density throughout the entire length of the pipe. Recesses for bells of the pipe shall be excavated for every joint and shall be of sufficient size and depth to relieve the bell of the load, permitting the barrel of the pipe to lie firmly throughout the entire length. The pipe positively will not be supported on blocks in order to raise the bell.
- B. Earth bedding shall be used unless another type is designated on the Drawings or specified per the City standards and specifications for construction. The pipe shall be placed on the natural undisturbed earth foundation that has been carefully shaped to fit the lower part of the conduit for not less than 1/4 of its circumference. When rock, shale or boulders are encountered in the trench, they shall be removed to a depth of six (6) inches below the grade line and the trench shall be refilled with good, sound earth, gravel or granular material up to the original grade and tamped into place. Bell holes will be required as above.
- C. Other types of bedding and embedment shall be provided when designated on the Drawings.

3.4 EMBEDMENT AND BACKFILLING

- A. In areas outside of pavement areas the remainder of the backfill shall be placed in layers not exceeding eight (8) inches loose depth and shall be compacted by an approved method, which will obtain the density of the adjacent undisturbed soil. Backfill under pavements shall be compacted in thin, uniform, loose layers eight (8) inches or less in thickness with the maximum particle or rock size being four inches in diameter prior to compaction. Uniformly compact each lift to between 95% and 100% of maximum dry density as defined by ASTM D698, with the moisture content between optimum and four (4) percent above optimum. Water jetting will not be permitted.
- B. Bedding and Backfill shall conform to local jurisdictional requirements for pipe embedment.

3.5 CLEANING UP

- A. Upon completion of the work covered by this Section, the Contractor shall clean up all work areas by removing all debris, surplus material and equipment from the site. The ground surface will be restored to within 0.10 foot of its original position.

END OF SECTION

SECTION 03100 – CONCRETE FORMWORK

PART 1 - GENERAL

1.1 SCOPE

Provide formwork and related accessories for all cast-in-place concrete indicated on the Contract Drawings and subsequently remove all such formwork.

1.2 RELATED WORK SPECIFIED ELSEWHERE

- A. Concrete Reinforcement Section 03200
- B. Cast-in-Place Concrete Section 03300
- C. Concrete formwork included in other Sections of these Specifications that is not specifically described shall meet the requirements of this Section.

1.3 QUALITY CONTROL

A. CODES AND STANDARDS

1. Comply with all pertinent codes and regulations including but not limited to ACI 301 "Specifications for Structural Concrete for Buildings" and ACI 318 "Building Code Requirements for Reinforced Concrete".
2. Whenever provisions of pertinent codes and standards conflict with each other or requirements of this Section of these Specifications, the more stringent provisions shall govern.

B. QUALIFICATION OF WORKMEN

At least one quality control person shall be present at all times during the execution of this portion of the Work. This person shall be thoroughly familiar with the type of materials being installed, the referenced standards, and the requirements of this Work, and who shall direct all work performed under this Section of these specifications.

PART 2 – PRODUCTS

2.1 MATERIALS

A. WOOD FORMS

Shall comply with all requirements described in the FORM CONSTRUCTION paragraph in this Section.

B. EXPOSED SURFACES

New or like-new moisture resistant fir form plywood. Surface must be smooth, completely free from scratches, indentations, unsound surface knots, ripples, etching, prominent grain, depressions, warps or breaks. "Exposed surfaces" include concrete surfaces which are to be painted or dash coated.

C. UNEXPOSED SURFACES

#2 common or better, plywood.

2.2 PRODUCT HANDLING**A. PROTECTION**

Use all means necessary to protect all formwork materials before, during, and after installation and to protect work and materials of all other trades.

B. REPLACEMENTS

In the event of product damage, make immediate repairs to the approval of the Structural Engineer and Architect and at no additional cost to the Owner.

2.3 MISCELLANEOUS MATERIALS**A. EXPANSION JOINT FORMING MATERIAL**

Preformed asphaltic expansion joint material, thickness as indicated on contract drawings, as manufactured by W.R. Grace & Company or W.R. Meadows, Inc. See section 03300 for forming materials and sealed expansion joints.

B. FORM TIES

Form ties shall be of a type which does not leave an opening through the concrete (regular snap ties) and which permits neat and solid patching of every hole.

PART 3 – EXECUTION

3.1 FORM CONSTRUCTION

The design, construction, upkeep, maintenance and subsequent removal of all aspects of formwork, is the Contractor's responsibility. The Contractor shall provide formwork that is safe and properly designed for the specific method of concrete placement, type of vibration and construction loads which he will employ.

3.2 SURFACES TO BE FORMED

Form both sides and soffit of all suspended beams, joists, slabs and all other structural concrete below and above existing or finish grade unless shown otherwise on plans.

3.3 FORMING DETAILS

Conform to shape, lines, grade and dimensions required by contract drawings; use plywood sheets as large as practical; all surfaces shall be straight, plumb and properly braced; joints shall be accurately matched and mortar-tight. Reinforce sufficiently to prevent deformation under load. If adequate foundation for shores cannot be secured, provide trussed supports. Clean and oil forms before reuse. Forms shall be readily removable without hammering or prying against concrete.

3.4 FORM TIES

Regular shape ties should be used.

No metal shall be within one inch of finished surface when forms are removed. Wire ties will not be permitted.

3.5 CHAMFER STRIPS

Provide at all angles of concrete which are exposed to view, unless shown otherwise.

3.6 CONDUIT IN SLABS

Individual conduits in slabs shall not exceed 1" diameter. Groups of conduits or conduits larger than 1" diameter will require slab to be thickened to maintain full design thickness.

3.7 CONSTRUCTION JOINTS

See Section 03300, Cast-in-Place Concrete, for requirements.

3.8 OILING OF FORMS

- A. Lightly coat with nonstaining form oil for exposed surfaces. Before placing reinforcing, remove surplus oil.
- B. In lieu of using an oil coat, forms for unexposed surfaces may be thoroughly wetted with water, immediately before placing concrete.

3.9 STRIPPING OF FORMS

- A. Side forms of beams may be removed after cumulatively curing at not less than 50 degrees F(10 degrees C) for 24 hours after placing concrete, provided concrete is sufficiently hard to not be damaged by form removal operations, and provided curing and protection operations are maintained.

END OF SECTION 03100

SECTION 03200 - CONCRETE REINFORCEMENT

PART 1 - GENERAL

1.1 SCOPE

Furnish and install all reinforcement and related items required and/or indicated on the Contract Drawings for all cast-in-place concrete.

1.2 RELATED WORK SPECIFIED ELSEWHERE

- | | | |
|----|------------------------|---------------|
| A. | Concrete Formwork | Section 03100 |
| B. | Cast-in-Place Concrete | Section 03300 |

1.3 QUALITY ASSURANCE

A. CODES AND STANDARDS

1. Comply with all pertinent codes and regulations. Concrete reinforcement, unless otherwise noted, shall meet requirements of ACI 301 "Specifications for Structural Concrete for Buildings" and/or ACI 318 "Building Code Requirements for Reinforced Concrete".
2. Whenever provisions of pertinent codes and standards conflict with each other or requirements of this section, the more stringent provisions shall govern.

B. QUALIFICATIONS OF WORKMEN

At least one quality control person shall be present at all times during execution of this portion of the work. This person shall be thoroughly familiar with the type of materials being installed and the best methods for their installation and shall direct all work performed under this section.

1.4 SUBMITTALS

A. CERTIFICATES

When requested by the Engineer, supplier of reinforcing steel and other embedded materials shall furnish certified evidence that all materials

delivered to the project meet the requirements of this Section of the Specification.

B. SHOP DRAWINGS

1. The Contractor shall obtain completely detailed shop drawings showing placement plans, bar bending lists and diagrams, etc. Shop drawings shall include the specific location and size of all accessories, chairs and bar supports. The Contractor shall carefully check these drawings, then submit them to the Architect/Engineer. The Architect/Engineer may conduct limited spot checks aimed solely at determining general compliance with the design intent, then return them to the Contractor. The Contractor shall then carefully recheck the shop drawings and approve them prior to fabrication.
2. The Engineer's limited spot checks shall not relieve the Contractor from correcting, at his own expense, any items that may thereafter be found not to comply with the contract drawings and these specifications.
3. All straight and bent bars shall be tagged with the member mark, regardless of the fabricator's standard policy or other industry standards of practice. If the fabricator elects to use member marks other than those shown on the structural drawings, the members must also be labeled with the original engineer's member marks in addition to those of the fabricator.

1.5 PRODUCT HANDLING

A. PROTECTION

1. Protect concrete reinforcement and installed work and materials of other trades before, during, and after installation.
2. Store reinforcing in a manner to prevent excessive rusting and fouling with dirt, grease and other bond-breaking coatings.
3. Use all means necessary to maintain identification after the bundles are broken.

PART 2 - PRODUCTS

2.1 MATERIALS

A. REINFORCING BARS

All reinforcing bars shall comply with ASTM A-615, Grade 60, except beam stirrups and column ties may be Grade 40 unless noted otherwise.

B. WELDED WIRE MESH

Flat sheets only. Comply with ASTM A-185.

C. ACCESSORIES

1. Comply with the latest edition of "Manual of Standard Practice for Detailing Reinforced Concrete Structures" (ACI-SP66), except that beam reinforcing larger than #9 shall be supported on individual bar chairs spaced no greater than 2'-0" apart. Accessories resting on forms where underside is left exposed to view, or where plaster, paint, stucco, or dash coat is to be applied shall be galvanized or have plastic leg tips at all points of contact with forms.
2. Accessories fabricated completely from plastic will not be permitted.
3. Accessories for use on cardboard carton forms shall have continuous metal sand plates.
4. Steel other than that of domestic manufacture will not be permitted.

PART 3 - EXECUTION

3.1 FABRICATION

- A. The Contractor shall be responsible for obtaining properly fabricated reinforcing and placing it properly. Reinforcing shall be fabricated in accordance with the latest edition of the "Manual of Standard Building Code Requirements for Reinforced Concrete" (ACI 318).
- B. Reinforcing steel shall be free from rust, scale, dried concrete, or other coatings that will destroy or reduce bond.

- C. Reinforcing steel shall be accurately bent and placed in position, securely tied or supported to prevent movement during placing of concrete. Field bends will not be permitted without prior approval from Engineer.
- D. Spacer bars, supports and accessories are not scheduled but are to be furnished and placed as described under MATERIALS paragraph in this Section.
- E. Raising of reinforcement (including welded wire fabric) during the pour will not be permitted.

3.2 CONCRETE COVER

- A. Reinforcing bars shall have concrete cover as follows, unless noted otherwise:
 - 1. Beam Stirrups; top, bottom and sides, 1-1/2".
 - 2. Column ties and spirals, 1-1/2".
 - 3. Concrete joists, 1-1/2"
 - 4. Concrete slabs, 3/4".
 - 5. Drilled footings, 2-1/2".
 - 6. Spread or spot footings, 3".
 - 7. Waterproofed walls or above grade walls, 3/4".
 - 8. Below grade walls (without waterproofing), 1-1/2".

3.3 SLAB AND BEAMS ON FILL

- A. Reinforcing shall be held securely in position with concrete cover as follows:
 - 1. Beam stirrups; top, 1-1/2", bottom and sides 2-1/2".
 - 2. Slab bars; 1-1/2" from top.
- B. Support reinforcing steel on concrete blocks or bricks spaced at approximately 4'-0" o.c. in each direction.

3.4 SPLICES

Splices not shown on contract drawings or otherwise noted shall be in accordance with ACI specifications for bar sizes up to #11 size, but not less than 55 bar diameters. Splices in bars larger than #11 shall be made with approved thermal or mechanical coupling devices. Welding wire fabric shall be lapped 1-1/2 meshes, with a minimum lap of 8".

3.5 SLAB OPENINGS

At slab openings of 12" or less, spread main reinforcing around opening. At slab openings greater than 12", provide 2 #4x4'-0" bottom placed diagonally at each corner. At sides of openings, provide one full bar for each bar cut at opening. No main reinforcing bars shall be cut without Engineer's approval.

3.6 EQUIPMENT/DUCTS

Provide adequate reinforcing as approved by Engineer for all required openings through beams, slabs, joists, walls, etc., and for distribution of equipment loads to structural members.

3.7 CONDUITS IN SLABS

Electrical and mechanical conduit in slabs shall run under upper layer of reinforcing or wire mesh; provide a minimum of 1-1/2" clear between conduits and between conduit and parallel reinforcing. Do not "bundle" conduits. See Section 03100 for thickened slab required at conduits larger than 1".

3.8 BEAM INTERSECTIONS

Unless shown otherwise on plans, at corners, angle bends and at junction with other beams, provide four #7x7'-0" "corner bars" (3.5 ft. each leg), 2 top and 2 bottom. For deep beams with scheduled intermediate bars, provide matching 110 diameter "corner bars" of same size. At "T" intersection, place all "corner bars" so that one leg is in outside face of outside beam.

3.9 TOPPING REINFORCEMENT

Reinforcement (including welded wire fabric) shall be chaired to proper depth as shown on plans and sections. Raising of reinforcement during pour is not acceptable.

3.10 CONSTRUCTION JOINTS

- A. All reinforcing shall continue through the joint.
- B. Add extra reinforcing if so directed by Engineer.

END OF SECTION 03200

SECTION 03300 - CAST-IN-PLACE CONCRETE

PART 1 - GENERAL

1.1 SCOPE

Cast-in-place concrete required for this work is indicated on the Contract Drawings.

1.2 RELATED WORK DESCRIBED ELSEWHERE

- | | | |
|----|---|---------------|
| A. | Structural Engineer: Shop Drawings and Field Visits | Section 01341 |
| B. | Concrete Formwork | Section 03100 |
| C. | Concrete Reinforcement | Section 03200 |

1.3 QUALITY CONTROL

A. CODES AND STANDARDS

Comply with all pertinent codes and regulations, including but not limited to the requirements of ACI 301, "Specifications for Structural Concrete for Buildings" and ACI 318, "Building Code Requirements for Reinforced Concrete". Also, refer to ACI 302 "Guide for Concrete Floor and Slab Construction."

B. QUALIFICATIONS OF WORKMEN

At least one quality control person shall be present at all times during execution of this portion of the work. This person shall be thoroughly familiar and experienced in placing the types of concrete specified and shall direct all work performed under this Section. Finishing of exposed surfaces of the concrete, shall be performed by thoroughly trained and experienced journeyman concrete finishers.

C. CONCRETE QUALITY

The Contractor shall be responsible for all aspects of concrete production, including maintenance and control of the quality of the concrete through

batching, mixing, placing and curing of the concrete. He shall take whatever measures he deems necessary to accomplish this. To assure the Owner of the quality of the work, the contractor shall employ an independent testing laboratory to perform certain services as described below. The performance of these services does not relieve the Contractor of his responsibility.

D. CONCRETE MIX DESIGN

1. Design each type of concrete to be used on the project based on aggregate size and cement proportions specified in Part 2 - Products. Laboratory shall go to the designated concrete supplier's batching plant and obtain samples of ingredients which shall be used in determination of compliance with ASTM C-33 and in the preparation of confirmatory test specimens.
2. Using the proposed mix design, the laboratory shall make one set of four test cylinders for each type of concrete. The results of two 7-day compression tests shall be submitted with the proposed mix design prior to placement of concrete on the job. Subsequently, results of two 28-day compression tests shall be submitted and the strength shall be at least 25% greater than the specified minimum strength for concrete placed on the job.
3. In lieu of new mix designs, the laboratory may submit data of previously prepared "standard" mix designs provided:
 - a. The mix design was prepared by the laboratory in strict accordance with the provisions of this section of the specifications.
 - b. The mix design shall have been prepared within the preceding six months. Documentation shall not reference any specific construction project.
 - c. The laboratory shall submit written certification that the materials used in the submitted mix designs are currently stocked at the batching plant.

E. CONCRETE TESTING

1. Concrete tests shall be performed by a commercial testing laboratory approved by the Structural Engineer. Services as set out below shall be paid by the General Contractor.

2. The Laboratory shall take samples and perform slump and compression tests in accordance with ASTM C-39 on concrete placed each day at the rate of one set of four cylinders for each 80 cu. yds. or fraction thereof. When more than 80 cu. yds. is being continuously placed, the interval between test samples shall be at least 50 cu. yds. so as to be representative of the whole day's pour. Samples shall be taken at the point of deposit in the field and all cylinders shall be accurately marked and referenced to show date, time and exact location in the structure from which they came. Make 7-day test on two cylinders and 28-day test on two cylinders. Reports of tests shall be promptly sent as follows: two to the Architect, one to the Engineer, and one to the Contractor.

F. BELOW STRENGTH CONCRETE

If the 28-day cylinder strengths fall below the specified strength, the concrete represented by such test cylinders shall be considered unacceptable and subject to removal. Consideration will be given to the acceptance of such concrete if it can be demonstrated to the satisfaction of the Engineer that the cylinder tests do not accurately represent the strength of the concrete in place, or that the structure is fully capable of carrying the loads for which it was designed. This data may be obtained by a series of non-destructive tests and core tests in accordance with ASTM C-42. The general contractor is responsible for all costs in connection with this additional testing and/or removal and replacement of defective concrete.

1.4 SUBMITTALS

A. MATERIALS LIST

Within 35 days after award of Contract, and before any concrete is delivered to the job site, submit to the Architect in accordance with Section 01300 of these Specifications a complete list of all materials proposed to be furnished and installed under this portion of the Work, showing manufacturer's name and catalog number of all items such as admixture and membrane, and the name and address of transit-mix concrete supplier.

B. TRANSIT-MIX DELIVERY SLIPS

1. Keep a record at the job site showing time and place of each pour of concrete together with transit-mix delivery slip certifying contents of the pour.

2. Make the record available to the Architect/Engineer for his inspection upon request.
3. Upon completion of this portion of the Work, deliver the record and the delivery slips to the Architect.

1.5 PRODUCT HANDLING

A. PROTECTION

Protect cast-in-place concrete materials before, during, and after installation. Protect the work and materials of all other trades.

B. REPLACEMENTS

In the event of damage, at no additional cost to the Owner, immediately make all repairs and replacements necessary to the approval of the Architect/Engineer.

PART 2 - PRODUCTS

2.1 MATERIALS

When requested by Engineer, supplier of concrete materials shall furnish certified evidence that all materials delivered to the project meet the requirements of this section.

2.2 PORTLAND CEMENT

Type 1 or Type 3, comply with ASTM C-150.

2.3 FLY ASH

Fly ash may be used as a pozzolan to replace a portion of the Portland Cement in a concrete mix, subject to the approval of the Structural Engineer. Fly ash, when used, shall conform to ASTM C-618. Concrete mixes using fly ash shall be proportioned to account for the properties of the specific fly ash used and to account for the specific properties of the fly ash concrete thus resulting. The ratio of the amount of the fly ash to the total amount of fly ash and cement in the mix shall not exceed 20 percent by weight.

2.4 CONCRETE AGGREGATES

Comply with ASTM C-33. Maximum aggregate size is 1-1/2".

2.5 WATER

Potable.

2.6 CONCRETE

A. PROPORTIONS

Use the following cement content minimums:

<u>28 day strength Specified</u>	<u>Sacks of Cement/ cu.yd. of Concrete</u>
1. 3000 psi, reg.wt., with admixture	5

B. CONCRETE SLUMP

Concrete shall be mixed and delivered in accordance with "Standard Specifications for Ready-Mixed Concrete", ASTM C-94. Maximum slump: 5 inches.

C. GROUT

Equal parts sand and cement. See STRUCTURAL STEEL Section for special grouts.

2.7 MIXING CONCRETE

Concrete shall be mixed and delivered in accordance with "Standard Specifications for Ready-Mixed Concrete", ASTM C-94.

2.8 EXPANSION JOINT FORMING MATERIAL

Preformed asphaltic expansion joint material, thickness as indicated, as manufactured by W. R. Grace & Company or W. R. Meadows, Inc.

2.9 SEALED EXPANSION JOINTS MATERIALS

Sealant: Two-component polyurethane elastomeric sealant, "Daraseal-U, Traffic Grade" as manufactured by W. R. Grace & Company or equal.

2.10 JOINT FILLER

Resilient, preformed, non-extruding type such as cork, sponge rubber, or PVC foam, as manufactured by W. R. Grace & Company, or equal, and which is recommended by the Manufacturer to be used with sealant selected.

2.11 CURING MATERIAL

- A. For all slabs except those on which additional concrete or other toppings are to be bonded, use a water-based acrylic membrane curing compound that has a maximum volatile organic compound (VOC) rating of 350 g/L (3 lbs/gal.) complying with ASTM C309, Type I, Class B. Available products include VOCOMP-20 (W. R. Meadows, Inc.), MasterKure 100W (Master Builders, Inc.), Dress and Seal WB (L & M Construction Chemicals, Inc.), or approved equal.
- B. For slabs having bonded toppings, use "Sisalkraft" paper as manufactured by the American Sisalkraft Company.

2.12 EMBEDMENTS

Metal sleeves, anchors, hangers, dovetail anchor slots and all embedments; furnish and locate by respective trade or by General Contractor. Secure approval of Engineer for installation of sleeves and conduits in structural members.

PART 3 - EXECUTION

3.1 CONCRETE PLACEMENT

- A. Unless otherwise noted, concrete shall be mixed and placed in accordance with ACI "Standard Building Code Requirements for reinforced Concrete" (ACI 318), latest edition.
- B. Before placing concrete in a given section, the following items shall be completed:
 - 1. All reinforcing, base plates, dowels, etc., shall be completely and securely tied in place for the entire section to be concreted. Anchor

bolts and embedded items requiring accurate location shall be positioned and leveled by the use of templates and instruments, and securely held in place so that no movement occurs during the placement of concrete.

2. All forming, bulkheads, construction joints, keyways, sleeves inserts, plates etc., and embedded work of other trades shall be complete for the entire section to be concreted.
 3. All materials and equipment for curing and protecting concrete shall be at the job site.
 4. Runways shall be provided for wheeled equipment to protect reinforcing steel. Runways and equipment used in mixing, conveying, lifting and depositing the concrete shall be in good condition, adequate to support all construction loads and suitable and safe for the workmen.
 5. Water and debris shall be removed from space to be occupied by concrete.
- C. See CONCRETE FORMWORK Section for wetting of forms immediately before placing concrete.

3.2 NOTIFICATION OF POURING SCHEDULE

- A. Before batching concrete for placement, the Contractor shall see that all applicable provisions of the contract drawings and specification have been complied with for the entire section to be concreted, and he shall notify the Architect/Engineer of this fact. This notification shall be given at least 24 hours prior to the time that the concrete placement is scheduled to begin and no concrete shall be placed until authorized by the Architect/Engineer. The Contractor shall inform himself of possibly unfavorable weather conditions and shall give due consideration to the weather in scheduling the placement of concrete.
- B. Concrete shall not be deposited during rain unless adequately protected. Preparations shall be on hand to protect newly placed concrete from rain until it has hardened sufficiently so that it will not be damaged. In the event rain starts falling during the placement of concrete, the Contractor shall take

such measures as are required to assure that the strength of the structure will not be impaired and the surface finishes will be as specified.

3.3 COLD WEATHER PLACING

- A. Concrete at the time it is deposited shall have a temperature not below 50 degrees F. and not above 90 degrees F.
- B. When the temperature of the surrounding air is below 40 degrees F. suitable means shall be provided for maintaining the concrete at a temperature not below 50 degrees F. for 5 days after placing; except when high early strength cement is used, the time may be reduced to 3 days.
- C. Special protection shall be carefully planned and all materials, equipment, etc., shall be at the job site prior to placing of any concrete. In general, these measures may include temporary heaters, coverings, and enclosures. The enclosures, coverings, etc., used in connection with this special protection shall remain in place and intact at least 24 hours after the artificial heating is discontinued so that the temperature change in the concrete will occur gradually.
- D. In scheduling forming and shoring removal, Contractor shall take into account the fact that at temperatures below 50 degrees F., concrete gains strength very slowly.
- E. Use of salt or chemicals shall not be mixed with the concrete to prevent freezing.

3.4 HOT WEATHER PLACING

- A. Concrete at the time it is deposited shall have a temperature not higher than 90 degrees F.
- B. Steps shall be taken to reduce concrete temperature and water evaporation by proper attention to ingredients, production methods, handling, placing, protection and curing.

3.5 PLACING CONCRETE

Convey continuously until the entire section to be concreted is completed. Partially hardened or initially set concrete shall not be used. Compaction by

mechanical vibrating equipment shall be required for all concrete. Place in layers not over 12" deep and compact each layer, supplemented by hand-spading, rodding and tamping.

3.6 CONVEYING

Concrete shall be conveyed from the mixer to the forms as rapidly as practicable by proper methods which will not cause segregation or loss of ingredients. It shall be deposited as nearly as practicable in its final position in the forms. At any point in the conveying, the free vertical drop of the concrete shall not exceed 4 feet. Chuting will be permitted only where the concrete is deposited into a hopper before it is placed in the forms. Chutes shall be constructed of metal or shall be metal lined. Conveying equipment shall be cleaned thoroughly before each run. All concrete shall be deposited as soon as practicable after the forms and the reinforcement have been observed by the Engineer. Concrete which has segregated in conveying shall be removed.

3.7 SURFACE DEFECTS

Patch honeycomb, tie rod holes, and minor defects with one part cement and two parts sand immediately after removing forms and before concrete is thoroughly dry. Remove fins and rough edges.

3.8 BONDING NEW CONCRETE TO OLD

Clean, roughen, and coat with latex bonding agent.

3.9 CONSTRUCTION JOINTS

- A. Provide in monolithic concrete framing so that not more than 400 cubic yards is placed in one day and no side dimension of the section being concreted is greater than 150 feet. Larger areas require approval by the Engineer.
- B. Location shall generally be near the middle of the spans of slabs and beams with wood or steel-formed soffits. When soffits are formed with cardboard cartons, locate construction joint on centerline of pier..
- C. Provisions shall be made for transfer of shear and other forces through the joint. Generally this shall consist of forming horizontal keyways at

mid-depth, 1-1/2" deep X 1/3 of beam or slab depth and allowing all reinforcing to continue through the joint. Add extra reinforcing if so directed by Engineer.

3.10 EXPANSION JOINTS

- A. For flatwork, sidewalks, drives, approaches, form expansion joints with preformed asphaltic expansion joint material.
- B. No part of the expansion joint material shall extend above the surface of the concrete. Trim off any excess as required.

3.11 SEALED EXPANSION JOINTS

Provide unless otherwise indicated on the Drawings. Follow manufacturer's recommendations and instructions in all phases including filler installation, cleaning, bond breaking between filler and sealant, priming, mixing and application of sealant. Sealant shall be installed only by experienced personnel and shall have a thickness of one-half the width of the joints except the minimum thickness shall be 1/2".

3.12 FINISHES

Refer to architectural drawings for all floor finishes, locations and dimensions of slab drops and depressions floor checks, chamfers, and special concrete treatments. Carefully work out all finishes to agree with other materials and finishes. Verify all elevations, levels and conditions. Carefully tool all exposed edges.

3.13 FLOORS

Edge forms and intermediate screed strips shall be set accurately to produce the designated elevations and contours of the finished surface, and shall be capable of supporting all screeding operations. Refer to Architectural Drawings for all floor and roof finishes, floor coverings, and dimensions and locations of slab drops, slopes, and depressions. Unless otherwise noted, concrete slab finishes and tolerances including consolidation, floating, troweling, brooming, etc., shall be as described in ACI 301, Chapter 11, for the type of surface indicated on Architectural Drawings.

3.14 FLOOR FLATNESS AND LEVELNESS

- A. Flatness and levelness tolerances for floors shall conform to the requirements set forth in ACI 117, "Standard Tolerances for Concrete

Construction and Materials", particularly section 4.5.6 and 4.5.7. Either of the following specifications is acceptable.

1. Face Floor Profile Numbers (F-Numbers):
CONVENTIONAL, BULL-FLOATED; Flatness $F_f = 15$ Level $F_l = 13$
CONVENTIONAL STRAIGHTEDGED; Flatness $F_f = 20$ Level $F_l = 15$
FLAT; Flatness $F_f = 30$ Level $F_l = 20$
VERY FLAT; Flatness $F_f = 50$ Level $F_l = 30$
2. 10-ft. Straightedge Method:
CONVENTIONAL, BULL-FLOATED; 1/2 in.
CONVENTIONAL, STRAIGHTEDGED; 5/16 in.
FLAT; 3/16 in.
VERY FLAT; 1/8 in.

B. Unless noted otherwise, slab surfaces shall conform to the following criteria:

1. Offices, classrooms, corridors, etc: FLAT.
2. Warehouses, storerooms, equipment rooms: STRAIGHTEDGED.
3. Sidewalks, plazas, pavement: BULL-FLOATED.

3.15 FINISHES OTHER THAN FLOORS AND SLABS

Concrete exposed to view, both interior and exterior, shall be rubbed with Carborundum bricks and water no sooner than 48 hours and not later than one week after pouring. Plastering such surfaces will not be permitted. Remove all form marks, bulges, and irregularities. Finished surfaces shall be true and uniform in texture.

3.16 CURING AND PROTECTION

- A. All concrete shall be protected from premature drying for at least the first 7 days after placement. Curing compound shall be applied in strict accordance with manufacturer's directions just as soon as concrete has taken it's initial set and can receive compound without damaging the finish. All curing materials and equipment shall be on the jobsite before concrete is ordered.

- B. Floor areas which are designated to have a permanently exposed concrete surface require a two-coat application of curing and sealing compound. Apply one coat at the time of finishing and a second coat immediately prior to "Substantial Completion" of project.
- C. At floor areas scheduled to receive ordinary floor finishes (except bonded concrete or cementitious materials) apply one coat of specified curing compound in accordance with manufacturer's directions.
- D. At floor areas scheduled to receive bonded concrete topping, ceramic tile, terrazzo or other cementitious floor finishes, **DO NOT USE CURING COMPOUND**. Such areas shall be cured with lapped and taped "Sisalkraft" paper or absorptive mats or fabric kept continuously wet during the entire curing process.
- E. Vertical surfaces such as walls, columns, etc., may be cured by loosening the form and allowing water to run down between the concrete and the form, or by keeping the forms continuously wet.

3.17 CEMENT WASH

Where required at locations such as vents, grilles, ledgers; provide neatly finished cement wash of one part cement to 2-1/2 parts clean sand.

3.18 CLEANING

Clean all concrete work of mortar, plaster, paint, grease, oils, etc. Defective areas shall be replaced or repaired.

END OF SECTION 03300

SECTION 04200

UNIT MASONRY & MASONRY VENEER

PREFACE

The general provisions of the Contract, including the Conditions of the Contract (General, Supplementary and other Conditions) and Division 1 as appropriate, apply to the Work specified in this Section.

1.0 SCOPE

1.1 This section includes stone veneer, mortar and accessories.

2.0 MATERIALS

2.1 Stone color and shape to match existing portions of stone wall.

2.3 Hydrated Lime: ASTM C-207, Type S

2.4 Sand: ASTM C-144

2.5 Water: Clean Drinkable

2.6 Mortar shall be placed accurately proportioned and mixed thoroughly by hand or machine to a uniform consistency and color. Re-tempering or partially set mortar shall not be permitted.

2.7 Mortar for all masonry work shall be mixed as follows:

1 part Portland Cement (white)

1 part Lime

6 parts yellow Sand

Exact color of mortar to match existing mortar at stone walls.

2.8 Masonry Accessories

Adjustable hot-dipped galvanized masonry ties for brick veneer from Hohmann & Bernard or approved equal.

Weep holes to be formed by ¼" round x 4" long medium density polyethylene plastic tubes spaced at 32" o.c. horizontally at base of wall.

- 2.3 Steel lintels to conform to specification for structural steel in Division 5. Steel reinforcing to conform to specification for reinforcing in Division 3.

3.0 EXECUTION

- 3.1 Verify all dimensions and conditions relating to masonry work. Report any conditions which may prevent proper execution of masonry work to the Architect. Commencement of work will be construed as acceptance of conditions.
- 3.2 Coordinate masonry work with related work. Allow for or install all mechanical and electrical parts, leaving all chases, recesses, openings. Bolts and anchors required by other subcontractors shall be set to templates or dimensions furnished by them. Build in all blocking and grounds required for the Project. Cooperate in setting and bedding all metal work built into or set in conjunction with masonry. Build in all flashing and waterproofing elements.
- 3.3 During erection, cover top of wall with heavy waterproof sheeting at the end of each day's work. Cover partially completed structures when work is not in progress. Extend cover a minimum of 24" down both sides and hold cover securely in place.
- 3.4 Do not apply concentrated loads for at least 3 days after building masonry walls.
- 3.5 Prevent grout or mortar from staining the face of masonry to be left exposed or painted. Remove immediately grout or mortar in contact with such masonry. Protect sills, ledges and projections from droppings of mortar.
- 3.6 Weather Protection:
1. When air temperature is from 40 to 32 degrees Fahrenheit, heat sand or mixing water to produce mortar temperatures between 40 & 120 degrees.
 2. When air temperature is from 32 to 25 degrees Fahrenheit, heat as described above and maintain temperature of mortar on boards above freezing.
 3. When air temperature is from 25 to 20 degrees, heat and maintain as described above and use salamanders or other heat sources on both sides of walls under construction; use wind breaks when wind is in excess of 15 mph.

4. When air temperature is 20 degrees and below, stop all masonry operations.
5. When mean daily air temperature is from 40 to 25 degrees, completely cover masonry with weather resistive membrane for at least 24 hours.
6. When mean daily air temperature is 25 degrees and below, completely cover masonry with insulation blankets or similar protection for at least 24 hours.
7. Do not lower the freezing point of mortar by use of admixtures.
8. Remove all masonry determined to be frozen or damaged by freezing conditions.

3.7 Mortar:

1. Measure and batch materials either by volume or weight such that the required proportions for mortar can be accurately controlled and maintained. Measurement of sand exclusively by shovel will not be permitted.
2. Mix mortars with the minimum amount of water consistent with workability to provided maximum tensile bond strength within the capacity of the mortar.
3. Mix mortar ingredients for a minimum of 5 minutes in a mechanical batch mixer. Do not use mortar, which has begun to set, or if more than 2-1/2 hours has elapsed since initial mixing. Re-temper mortar during 2-1/2 hour period as required to restore workability.

END OF SECTION

SECTION 05500

METAL WORK

PREFACE

The general provisions of the Contract, including the Conditions of the Contract (General, Supplementary and other Conditions) and Division 1 as appropriate, apply to the Work specified in this Section.

1.0 SCOPE

- 1.2 Miscellaneous Metal(s) – (i.e. grills, etc.)

2.0 MATERIALS

- 2.1 Steel Tubular products shall be cold formed structural quality carbon steel, welded or seamless complying with ASTM A500 Grade B and the latest AISC Specifications for the design, fabrication and erection. All steel shall be domestic manufacture.
- 2.2 Bolts, nuts and washers shall conform to the Specifications, High-Strength Steel Bolts for Structural Joints, ASTM A325, latest edition.
- 2.3 Welding electrodes for manual shielded metal-arc welding shall conform to E70 series of the specifications for Mild Steel Arc-Welding Electrodes, ASTM A233, latest edition.

3.0 EXECUTION

- 3.1 Fabricate steel in conformity with the dimensions, arrangement, size and thickness that are shown or noted on the drawings. Workmanship and finish shall be first class and equal to the best practices in modern steel fabrication shop. Connections of all steel shall be detailed and fabricated in accordance with standards, specifications and details given in the latest editions of the Steel Construction Manual, issued by the American Institute of Steel Construction, unless specifically noted otherwise on the plans.
- 3.2 Shop connections, except as otherwise specifically shown on the drawings, shall be welded. Welding shall be done only by welders who hold valid qualification certificates under the qualification procedures of the American Welding Society. Except as otherwise shown or noted, welded connections shall be equal to framed beam connections in Table IV, Part 4, AISC Manual for Welded Equivalents.
- 3.3 Field Connection: Except as otherwise indicated on the drawings, all field connections shall be made by welding and/or high tensile strength bolts. All joints shall be assembled and the joining surfaces shall be tightly drawn together with fitting bolts before welding or permanent bolting is started. After assembly and before permanent

connection is done, the building framework shall be checked for alignment, plumbness, and level. Attention shall be given to the plumbing of all exposed members and those to which exposed construction work is to be attached, in order that accurate alignment on such construction will be maintained.

- 3.4 Welded connections shall be provided where designated by the drawings. All welding shall be done by the electric shielded arc method, and only by competent welders qualified as to their ability and experience under the requirements of the American Welding Society. Surfaces are to be clean and free from rust, scale, dirt, grease, paint, and other foreign matter. Edges of plates, angles and sections to be welded shall be closed by service bolting, clamping, jigs or tack welding. Welds shall be made of clean metal, free from inclusions or porosity. The contour of all welds shall have a smooth finish, and shall indicate good fusion with parent metal. Unless specifically stipulated otherwise, all welds shall be continuous along all contact edges and shall be of proper dimensions to develop the full strength of the thinnest sectional area involved in the connection.
- 3.5 All field-welded areas shall be power tool cleaned and painted in accordance with painting specs.

END OF SECTION

SECTION 06100

CARPENTRY AND MILLWORK

PREFACE

The general provisions of the Contract, including the Conditions of the Contract (General, Supplementary and other Conditions) and Division 1 as appropriate, apply to the Work specified in this Section.

1.0 SCOPE

- 1.1 Labor, materials, equipment and appurtenant accessories for furnishing, fabricating and installing finish carpentry, millwork and cabinet work, as shown on the drawings and as specified. *** No particle board shall be used for any type of construction or fabrication in this project.**
- 1.2 Trex Deck and TEX DOT sign board materials installed at sun screens and mechanical equipment screen. See plans for details

2.0 MATERIALS

- 2.1 Lumber shall conform to American "Lumber Standards, Simplified Practice Recommendation R-16", latest edition, and to grading rules of manufacturer's association under whose rules it is produced. Lumber shall bear grade and trade mark of manufacturer's association. All lumber shall be dressed and kiln dried.
- 2.2 Hardwoods shall conform to current standards of the National Hardwood Lumber Association. All hardwoods shall be dressed and kiln dried.
- 2.3 Construction grade #1 fir shall be used for all nailing strips, ground, bucks and miscellaneous lumber less than 2" x 4" that is concealed from view.
- 2.4 WOOD TRIM: Furnish and install miscellaneous trim in sizes and locations where noted or required.
- 2.5 Trex Deck at sun screens: As manufactured by the TREX COMPANY, INC.

3.0 EXECUTION

- 3.1 Protect finished woodwork from weather while in transit from point of production or fabrication to building. When delivered to site immediately place under cover and adequately protect from weather. DO NOT store in wet or damp portions of the building.

- 3.2 Furnish all nails, screws, spikes, bolts, hooks, hangers, anchors, ties, clips and other accessories required for the proper installation of the work under this Section. Anchors or other items required to be built in shall be furnished in ample time for building-in and the Contractor shall supervise their installation to insure proper location.
- 3.3 All work shall be built plumb, level, true and square to the lines and dimensions shown. Position of openings and offsets and slopes and angles shall be laid off with extreme care. All work shall be rigidly fastened as best suited for each condition as needed to permanently hold the finished work to correct surfaces, lines and levels.
- 3.4 FINISH CARPENTRY AND MILLWORK:
 - .1 Work shall be assembled at the mill insofar as practicable and delivered ready for erection. Work shall be made in accordance with approved shop drawings and measurements taken at the job. Execute work in the highest standards of the trade as regards to strength and appearance. To conform to the quality, grade, species, called for as "Custom Grade" as defined in Architectural Woodwork Institute "Quality Standards", Section 400.
 - .2 Deliver millwork and commence installation at job site at time established by the Contractor.
- 3.5 NAILERS, PLATES AND BLOCKING: Provide permanent dressed wood, nailers, plates and blocking of sizes indicated or required for attachment of work of other trades. Closely fit and accurately set members to required lines and levels rigidly secured in place.
- 3.6 INSTALLATION OF MILLWORK: Install members, plumb, true and square in accord with drawing requirements. Drill holes in hardwood for nails. Blind nail wherever possible with surface nails set. Make joints tight in an approved manner to conceal shrinkage. Set nails and countersink screws. Draw members tight against finished surfaces. Secure all interior finish trim with fine finishing nails and glue where required to assure permanent tight joints.
- 3.7 Woodwork which is to be painted shall have exposed surfaces free of defects that would show after being painted.
- 3.8 CLEAN UP: Clean up all debris caused by work in this Section keeping premises neat and clean at all times.

TREX CONSTRUCTION

4.1 MATERIALS

This product is made from 95% recycled materials including plastic shopping bags, reclaimed wood and sawdust.

Use Trex 1" x 6" Square Edge Board (Actual dimensions...1" x 5.5") with smooth side out.

Submit samples for color selection by Architect

4.2 EXECUTION (See details Sheet A-1.3)

Trex materials are heavier and more flexible than wood. DO NOT try to lift the same Quantity of Trex boards as you would traditional lumber.

It is recommended that a carbide tipped blade be used for cutting.

Attach to steel frame with stainless steel through bolts, washers and nuts as noted in details

GENERAL TIPS:

- + Do not use permanent marking chalk lines and string. Use Irwin Straight Line "Dust Off" Marking Chalk
- + Do not sand surface
- + When drilling holes, periodically lift the drill bit out of the hole to remove the shavings
- + Store product on a flat and level surface
- + Do not stack over six bundles high
- + Cover material on job site until ready to install.

END OF SECTION

SECTION 07200

INSULATION

PREFACE

The general provisions of the Contract, including the Conditions of the Contract (General, Supplementary and other Conditions) and Division 1 as appropriate, apply to the Work specified in this Section.

1.0 SCOPE

- 1.1 This Section includes blanket type insulation at locations as noted on drawings. Full Sound Batt insulation at all Toilet Room walls and walls between Meeting Room and adjoining spaces.

2.0 MATERIALS

- 2.2 Foam joints at window and door frames and use foam gaskets at electrical cover plates.
- 2.3 Friction fit sound blankets between studs in designated wall cavities.
- 2.4 Insulation exposed at sloping ceilings to be R-20 Owens Corning Vinyl Face with 20Ga. wire support grid attached to steel structure.

3.0 EXECUTION

- 3.1 Extend insulation full thickness as indicated over entire roof area to be insulated. Cut and fit tightly around obstructions, and fill voids with insulation.
- 3.2 Exercise care to maintain an effective vapor barrier; patch punctures with foil tape. Remove and replace all torn or water soaked insulation.
- 3.3 Inspect final work to insure no insulation has been removed to accommodate other trades.

END OF SECTION

SECTION 07600**FLASHING & SHEET METAL****PREFACE**

The general provisions of the Contract, including the conditions of the Contract (General, Supplementary and other Conditions) and Division 1, as appropriate, apply to the Work specified in this section.

1.0 SCOPE

1.1 This Section includes flashing and sheet metal required to prevent penetration of water through the exterior shell of the building. Prefinished metal edges, gutters, counter flashing and expansion joints shall be supplied by the prime material manufacturer and included in the roof system warranty. Drawings and general provisions of contract apply to this section.

1.2 Quality Assurance:

- A. Qualifications of Installers: At least one person shall be present at all times during execution of this work who is thoroughly trained and experienced in the materials and methods required to fabricate and install the flashing and sheet metal work specified herein.
- B. Codes and Standards: Comply with all pertinent codes and regulations.

1.3 Codes and Standards:

- A. Comply with all pertinent codes and regulations.
- B. Comply with all pertinent recommendation of 1988 edition of "Architectural Sheet Metal Manual" of the Sheet Metal and Air Conditioning Contractors National Association, Inc. (SMACNA)

1.4 Submittals

- A. Product Data: Submit manufacturer's product specifications, installation instructions and general recommendations for each specified sheet material and fabricated product.
- B. Submit two (2)12" long completely finished units of specified factory-fabricated products exposed as finished work.
- C. Shop Drawings: Submit shop drawings for review showing layout, joining, profiles, and anchorage of fabricated work, including major counter flashings, trim/fascia units.

1.5 Product Handling

- A. Protection: Protect flashing and sheet metal materials before and during installation.
- B. Replacements: In event of damage, make all repairs and replacements necessary.

2.0 MATERIALS

2.1 Materials and Gauges

- A. Where sheet metal is required and no material or gauge is indicated, furnish and install the highest quality and gauges commensurate with referenced standard.
- B. Sheet Metal: 24 gauge G90, galvanized with a Kynar 500 factory applied finished color to match the adjacent roof or wall panels.
- C. Lead Flashings: Sheet complying with FS QQ-L-201. Grade B; formed from Common Desilverized Pig Lead complying with ASTM B29. Weight 4.0 lbs./sq./ft. unless otherwise specified.

2.2 Nails, Rivets and Fasteners

- A. Annular Threaded Nails: Galvanized
- B. Rivets: Soft iron having rust resistive coating.
- C. Exposed Fasteners and Washers: Stainless Steel with neoprene washers.
- D. Masonry Anchors: Lead or Nylon where appropriate.
- E. Caulking: Terpolymer by the Garland Company or approved equal.

2.3 Related Material

- A. Flux: For use with galvanized iron or steel: Raw Muriatic Acid
- B. Solder: Conform with current ASTM B-32. 50% tin and 50% lead.
- C. Burning Rod for Lead: Same composition as lead
- D. Termination Bar: Aluminum slotted bar.

3.0 EXECUTION

3.1 Examination

- A. Verify all existing work is complete to point where this installation may commence.

- B. In the event of discrepancy, notify owner's representative. Do not proceed until discrepancies have been resolved.
- C. Field measure site conditions prior to fabricating work.

3.2 Fabrication

- A. Shop fabricate work to greatest extent possible. Comply with details shown, and with applicable requirements of SMACNA and other industry practices.
- B. Fabricate for waterproof and weather-resistant performance: with expansion provisions for running work, sufficient to permanently prevent leakage, damage or deterioration of work.
- C. Form exposed sheet metal work without excessive oil canning, buckling and tool marks, true to line and levels as indicated, with exposed edges folded back to form hems.
- D. All miters shall receive rivets. All joints or where metal overlaps shall receive Terpolymer sealants. This includes back up plates as well as cover plates.

3.3 Lead Flashing Installation

- A. Set all primed leads in a bed of roofing mastic. At pipe vents, turn lead down into pipe opening a minimum of 1 inch and crimp.

3.4 Fabrication Counter Flashing

- A. Fit flashing tight in place, making corners square surfaces true and straight in plane and accurate to profile.
- B. Secure counter flashing through butyl tape onto wall with lead anchors.
- C. Fill caulk through with Terpolymer caulking.

3.5 Fabrication Copping Cap

- A. Shop-fabricate work to greatest extent possible. Comply with details shown, and with applicable requirements of SMACNA and other industry practices.
- B. Fabricate for waterproof and weather resistant performance; with expansion provisions for running work, sufficient to permanently prevent leakage, damage or deterioration of work.
- C. Form exposed sheet metal work without excessive oil-canning, buckling and tool marks, true to line and levels as indicated, with exposed edges folded back to form hems.

- D. All miters shall be soldered. All joints or where metal overlaps shall receive Terpolymer sealant. This includes back up plates as well as cover plates.

3.6 Cleaning

- A. Clean exposed metal surface removing substances which might cause corrosion of metal or deterioration of finishes.

END OF SECTION

SECTION 07610

PREFORMED METAL ROOFING & WALL PANELS

PREFACE

The general provisions of the Contract, including the Conditions of the Contract (General, Supplementary and other Conditions) and Division 1 as appropriate, apply to the Work specified in this Section.

1.01 SECTION INCLUDES

- A. Preformed, **Galvalume "S-Panel" metal roofing** and flashings at **shade structures**.
- B. Preformed **Galvalume "S-Panel" wall panels**
- C. Miscellaneous trim, flashing, closures, drip flashing and accessories.
- D. Sealant
- E. Fastening devices.
- F. Roof Panels to match existing roof panels as closely as possible
Consult with architect if a direct match is not possible.

1.02 RELATED SECTIONS

- A. Section 05120: Structural Steel Framing.
- B. Section 05500: Miscellaneous metal fabrication.
- C. Section 06100: Rough Carpentry.
- D. Section 07631: Flashing and Sheet Metal Gutters.
- E. Section 07900: Sealants.

1.03 REFERENCES

- A. American Iron & Steel Institute (AISI) Specification for the Design of Cold formed Steel Structural Members.
- B. ASTM A-525 Steel Sheet, Zinc-Coated (Galvanized)
- C. ASTM E-1680
- D. ASTM E-1646
- E. ASTM E-1592
- E. Spec Data Sheet - Aluminum Zinc Alloy Coated Steel (Galvalume) Sheet Metal by Bethlehem Corp.
- F. SMACNA - Architectural Sheet Metal Manual.
- G. Building Materials Directory - Underwriter's Laboratories, Test Procedure 580.

1.04 ASSEMBLY DESCRIPTION

- A. The roofing assembly includes preformed Galvalume sheet metal panels, related accessories, valleys, hips, ridges, eaves, corners, rakes, miscellaneous flashing and attaching devices fabricated in sections to match as closely as possible to the existing roof panels..
- B. The wall panel assembly includes preformed Galvalume Berridge S-Panel corrugated metal panels.

1.05 SUBMITTALS

- A. Submit detailed drawings showing layout of panels, anchoring details, joint details, trim, flashing, and accessories. Show details of weatherproofing, terminations, and penetrations of metal work.
- B. Submit a sample of each type of roof and wall panel, complete with factory finish.
- C. Submit results indicating compliance with minimum requirements of the following performance tests:
 - 1. Air Infiltration ASTM E 1680
 - 2. Water Infiltration ASTM E 1646
 - 3. Wind Uplift - U.L.90
- D. Submit calculations with registered engineer seal, verifying roof and wall panel and attachment method resists wind pressures imposed on it pursuant to applicable building codes.

1.06 QUALITY ASSURANCE

- A. Manufacturer: Company specializing in Architectural Sheet Metal Products with ten (10) years minimum experience.
- B. No product substitutions shall be permitted without meeting specifications.
- C. Substitutions shall be submitted 10 Days prior to Bid Date and acceptance put forth in an addendum.
- D. No substitutions shall be made after the Bid Date.

1.07 DELIVERY, STORAGE AND HANDLING

- A. Upon receipt of panels and other materials, installer shall examine the shipment for damage and completeness.
- B. Panels should be stored in a clean, dry place. One end should be elevated to allow moisture to run off.
- C. Stack all materials to prevent damage and to allow for adequate ventilation.

1.08 WARRANTY

- A. Galvalume material shall have a twenty year guarantee against failure due to corrosion, rupture or perforation.
- B. Applicator shall furnish guarantee covering water-tightness of the roofing system for the period of two (2) years from the date of substantial completion.

PART 2 PRODUCT

2.01 ACCEPTABLE MANUFACTURERS

- A. Berridge Manufacturing Company, Houston, Texas.
- B. Substitutions shall fully comply with specified requirements.

2.02 SHEET MATERIALS

- A. Prefinished Metal shall be pre-finished Galvalume 24 Gauge core steel - ASTM 792-86 AZ-55 .
- B. Unfinished Metal shall be Grade C Aluminum Zinc Alloy Coated Steel ASTM 792-86, AZ 55, "Satin Finish".

2.03 ACCESSORY MATERIALS

- A. Fasteners: Galvanized Steel with washers where required.
- B. Sealant: Sealant must be an ultra low modulus, high performance, one-part, moisture curing silicone joint sealant. (do not use a clear sealant or sealants which release a solvent or acid during curing).

Sealant must be resistant to environmental conditions such as wind loading, wind driven rain, snow, sleet, acid rain, ozone, ultraviolet light and extreme temperature variations.

Features must include joint movement capabilities of +100% & -50% ASTM C-719, capable of taking expansion, compression, transverse and longitudinal movement, service temperature range -65°F to 300°F (-54°C to 149°C), Flow, sag or slump: ASTM C-639; Nil, Hardness (Shore A): ASTM C-661; 15, Tensile strength at maximum elongation: ASTM D-412; 200 psi, Tensile strength at 100% elongation: ASTM D-412; 35 psi, Tear strength, (die "C"); ASTM D-624; 40 pli, Peel strength (Aluminum, Glass, Concrete): ASTM C-794; 30 pli

- C. Vinyl Weatherseal Insert.

2.04 FABRICATION

- A. All exposed adjacent flashing shall be of the same material and finish as the roof panels.
- B. Hem all exposed edges of flashing on underside, 1/2 inch.

2.05 PREFORMED METAL PANELS

Berridge or equal "S Panel" WALL PANEL

Installed as per manufacturers recommendation.

PART 3 EXECUTION

3.01 INSPECTION

- A. Substrate: At walls:
 - 1. Dens glass with "Ice and Water Shield" over 6" metal studs
 - 2. Inspect framing to verify free of depressions, waves or projections, level to ¼" in 20'
 - 3. Verify openings, curbs, pipes, sleeves, ducts or vents through wall are solidly set.
- B. Underlayment:
 - 1. Ensure that all nail heads are totally flush with the substrate.

3.02 INSTALLATION

- A. Comply with manufacturers standard instructions and conform to standards set forth in the Architectural Sheet Metal Manual published by SMACNA, in order to achieve a watertight installation.
- B. Install panels in such a manner that horizontal lines are true and level and vertical lines are plumb.
- D. Remove protective strippable film prior to installation of panels.
- E. Attach panels using manufacturer's standard clips and fasteners, spaced in accordance with approved shop drawings.
- F. Do not allow panels or trim to come into contact with dissimilar materials.
- G. Remove and replace any panels or components which are damaged beyond successful repair.

3.03 CLEANING

- A. Clean any grease, finger marks or stains from the panels per manufacturer's recommendations.
- B. Remove all scrap and construction debris from the site.

3.04 FINAL INSPECTION

- A. Final inspection will be performed by a firm appointed and paid for by the owner in accordance with section 01410.

END OF SECTION

SECTION 07720 - ROOF ACCESSORIES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes the following:
 - 1. Ridge vents.
- B. Related Sections include the following:
 - 1. Division 7 Section "Sheet Metal Flashing and Trim" for shop- and field-fabricated metal flashing and counterflashing, scuppers, gutters and downspouts, fasciae, roof expansion-joint covers, valleys, and miscellaneous sheet metal trim and accessories.
 - 2. Division 7 Section "Manufactured Roof Specialties" for fasciae, copings, gravel stops, and roof expansion-joint covers.
 - 3. Division 7 Sections for roofing accessories included as part of roofing Work.

1.3 SUBMITTALS

- A. Product Data: For each type of product indicated. Include construction details, materials, dimensions of individual components and profiles, and finishes.
- B. Shop Drawings: Show fabrication and installation details. Indicate dimensions, weights, loadings, required clearances, method of field assembly, and components. Include plans, elevations, sections, details, and attachments to other Work.
- C. Coordination Drawings: Roof plans drawn to scale and coordinating penetrations and roof-mounted items. Show the following:
 - 1. See drawings for size and location of unit.
 - 2. Method of recommended installation for existing ridge condition.
- D. Samples for Initial Selection: Manufacturer's color charts showing the full range of colors available for roof accessories with factory-applied color finishes.
- E. Samples for Verification: For each type of exposed finish required, prepared on Samples in manufacturer's standard sizes, and of same thickness and material indicated for the Work. If finishes involve normal color or shade variations, include sample sets showing the full range of variations expected.

1.4 QUALITY ASSURANCE

A. Standards: Comply with the following:

1. SMACNA's "Architectural Sheet Metal Manual" details for fabrication of units, including flanges and cap flashing to coordinate with type of roofing indicated.
2. NRCA's "Roofing and Waterproofing Manual" details for installing units.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

B. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1. Roof Curbs and Equipment Supports:

- a. AES Industries, Inc.
- b. Colony Custom Curbs.
- c. Commodity Products Company, Inc.
- d. Conn-Fab Sales, Inc.
- e. Curbs Plus, Inc.
- f. Custom Curb, Inc.
- g. Gieske Custom Metal Fabricators.
- h. Goeller Enterprises.
- i. LMCurbs.
- j. Loren Cook Company.
- k. Metallic Products Corporation.
- l. Pate Co.(The).
- m. Roof Products & Systems Corp.
- n. ThyCurb, Inc.
- o. Uni-Curb, Inc.
- p. Vent Products Co., Inc.
- q. Vent Products Co., Inc.
- r. Western Canwell.

2. Ridge Vents:

- a. Air Vent, Inc.
- b. Alcoa Building Products.
- c. Commodity Products Company, Inc.
- d. Cor-A-Vent, Inc.
- e. GAF Materials Corporation.
- f. Klauer Manufacturing Co.
- g. Metallic Products Corporation.
- h. Mid-America Building Products Corporation.

- i. Niff-Corr, Inc.
- j. Obdyke: Benjamin Obdyke, Inc.
- k. Petersen Aluminum Corp.
- l. Plyco Corporation.
- m. Solar Group (The).
- n. ThyCurb, Inc.
- o. Trimco, Inc.
- p. Trimline Roof Ventilation Systems.
- q. Western Canwell.

2.2 MATERIALS, GENERAL

- A. Aluminum Sheet: ASTM B 209 for alclad alloy 3005H25 or alloy and temper required to suit forming operations, with mill finish, unless otherwise indicated.
- B. Extruded Aluminum: ASTM B 221 alloy 6063-T52 or alloy and temper required to suit structural and finish requirements, with mill finish, unless otherwise indicated.
- C. Galvanized Steel Sheet: ASTM A 653/A 653M with G90 coating designation; commercial quality, unless otherwise indicated.
 - 1. Structural Quality: Grade 40, where indicated or as required for strength.
- D. Aluminum-Zinc Alloy-Coated Steel Sheet: ASTM A 792/A 792M with Class AZ-50 coating, structural quality, Grade 40, or as required for strength.
- E. Fasteners: Same metal as metals being fastened, or nonmagnetic stainless steel or other noncorrosive metal as recommended by manufacturer. Match finish of exposed fasteners with finish of material being fastened.
- F. Gaskets: Manufacturer's standard tubular or fingered design of neoprene, EPDM, or PVC; or flat design of foam rubber, sponge neoprene, or cork.
- G. Mastic Sealant: Polyisobutylene; nonhardening, nonskinning, nondrying, nonmigrating sealant.
- H. Elastomeric Sealant: Generic type recommended by unit manufacturer that is compatible with joint surfaces; ASTM C 920, Type S, Grade NS, Class 25, and Uses NT, G, A, and, as applicable to joint substrates indicated, O.
- I. Roofing Cement: ASTM D 4586, nonasbestos, fibrated asphalt cement designed for trowel application or other adhesive compatible with roofing system.
- J. Fabrication: Unless otherwise indicated or required for strength, fabricate units from minimum 0.0747-inch- thick, structural-quality, hot-dip galvanized or aluminum-zinc alloy-coated steel sheet; factory primed and prepared for painting with welded or sealed mechanical corner joints.
- K. Fabrication: Unless otherwise indicated or required for strength, fabricate units from minimum 0.063-inch- thick, sheet aluminum with welded corner joints.
 - 1. On ribbed or fluted metal roofs, form flange at perimeter bottom to conform to roof profile.

2.3 RIDGE VENTS

- A. General: Ventilating ridge cap with ventilating mesh providing a minimum net free area of 18 sq. in./ft., of manufacturer's standard design.
 - 1. Aluminum: Fabricate from sheet aluminum with baffles to prevent snow and rain entering and with weep holes to allow water to drain to roof. Provide required splice plates and end caps.
 - a. Finish: Clear anodic.
 - b. Finish: Color anodic.
 - c. Finish: Baked enamel.
 - d. Finish: High-performance organic coating.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. General: Comply with manufacturer's written instructions. Coordinate installation of roof accessories with installation of roof deck, roof insulation, flashing, roofing membranes, penetrations, equipment, and other construction involving roof accessories to ensure that each element of the Work performs properly and that combined elements are waterproof and weathertight. Anchor roof accessories securely to supporting structural substrates so they are capable of withstanding lateral and thermal stresses, and inward and outward loading pressures.
- B. Install roof accessory items according to construction details of NRCA's "Roofing and Waterproofing Manual," unless otherwise indicated,
- C. Separation: Separate metal from incompatible metal or corrosive substrates, including wood, by coating concealed surfaces, at locations of contact, with bituminous coating or providing other permanent separation.
- D. Flange Seals: Unless otherwise indicated, set flanges of accessory units in a thick bed of roofing cement to form a seal.
- E. Ridge Vents: Install according to manufacturer's written instructions.

3.2 CLEANING AND PROTECTION

- A. Clean exposed surfaces according to manufacturer's written instructions. Touch up damaged metal coatings.

END OF SECTION 07720

SECTION 07900**SEALANTS****PREFACE**

The general provisions of the Contract, including the conditions of the Contract (General, Supplementary and other Conditions) and Division 1, as appropriate, apply to the Work specified in this section.

1.0 SCOPE

- 1.1 This Section includes caulking and sealants.

2.0 MATERIALS

- 2.1 Exterior Silicon Rubber Sealant to be one-part elastomeric sealant, complying with FS TT-S-001543, Class A; recommended by manufacturer for exterior joints. Provide non-acid type wherever one or both joint faces are masonry, stone, concrete or other porous materials. Provide acid-type wherever both joint faces are metal, glass, plastic or other non-porous material.
- 2.2 For interior applications in wet areas and thresholds, provide butyl rubber sealant, polyisobutylene sealant (mastic) or silicon rubber sealant as above recommended by manufacturer for interior joints in wet areas, and when exposed, compounded specifically for mildew resistance.
- 2.3 Sealant for sheet metal flashing shall be one part polysulfide-base non-sag sealant conforming to Federal Specifications TT-s-00230C (2), Type II, Class A colored to match adjacent surfaces.
- 2.4 Provide ribbon or tape sealants, foam sealants, joint fillers, joint primer/sealers, bond breakers tape, and backer rod as necessary for proper execution of the work.
- 2.5 Exposed materials to be colored to match adjacent surfaces as approved by Architect.

3.0 EXECUTION

- 3.1 Examine sub-surfaces to receive work and report in writing any conditions detrimental to the work. Commencement of work will be construed as acceptance of all sub-surfaces.

- 3.2 Comply with manufacturer's written instructions except where more stringent requirements as shown or specified, and except where manufacturer's technical representative directs otherwise.

Employ proven installation techniques which will ensure that sealants will be deposited in uniform, continuous ribbons without gaps or air pockets, with complete "wetting" of the joint bond surfaces equally on opposite sides. Except as otherwise indicated, fill sealant rabbet to a slightly concave surface, slightly below adjoining surfaces. Where horizontal joints are between a horizontal surface and vertical surface, fill joint to form a slight cove, so that joint will not trap moisture and dirt.

- 3.3 Install sealants to depths as shown: if not shown, install as recommended by the sealant manufacturer but within the following limitations, measured at the center (thin) section of the bead:

- .1 For formal moving joints sealed with elastomeric sealants but not subject to traffic, fill joints to a depth equal to 50% of joint width, but neither more than 1/2" deep nor less than 1/4" deep.
- .2 For joints sealed with non-elastomeric sealants and caulking compounds, fill joints to a depth in the range of 75% to 125% of joint width.

- 3.4 Do not allow sealants or compounds to overflow or spill onto adjoining surfaces or to migrate into the voids of adjoining surfaces. Clean the adjoining surfaces by whatever means necessary to eliminate evidence of spillage.

END OF SECTION

SECTION 08400

ENTRANCES AND STOREFRONTS

PART 1 GENERAL

1.1 SECTION INCLUDES

A. Aluminum entrances and storefronts.

1.2 RELATED SECTIONS

A. Section 07920 - Sealants: Sealant product and installation requirements.

B. Section 08810 - Glass and Glazing: Glass and glazing requirements.

1.3 REFERENCES

A. ASTM B 209 - Standard Specification for Aluminum and Aluminum-Alloy Sheet and Plate.

B. ASTM B 221 - Standard Specification for Aluminum and Aluminum-Alloy Extruded Bars, Rods, Wire, Profiles, and Tubes.

C. ASTM B368 - Standard Method for Copper-Accelerated Acetic Acid-Salt Spray (Fog) Testing (CASS Test).

D. ASTM C 236 - Standard Test Method for Steady-State Thermal Performance of Building Assemblies by Means of a Guarded Hot Box.

E. ASTM C 864 - Standard Specification for Dense Elastomeric Compression Seal Gaskets, Setting Blocks, and Spacers.

F. ASTM E 283 - Standard Test Method for Determining Rate of Air Leakage Through Exterior Windows, Curtain Walls, and Doors Under Specified Pressure Differences Across the Specimen.

G. ASTM E 330 - Standard Test Method for Structural Performance of Exterior Windows, Doors, Skylights and Curtain Walls by Uniform Static Air Pressure Difference.

H. ASTM E 331 - Standard Test Method for Water Penetration of Exterior Windows, Skylights, Doors, and Curtain Walls by Uniform Static Air Pressure Difference.

1.4 STOREFRONT SYSTEM

A. Performance: Provide aluminum storefront systems that comply with performance requirements indicated, as demonstrated by testing manufacturer's assemblies in accordance with test method indicated.

1. Wind Loads: Completed storefront system shall withstand positive and negative wind and service pressure loads normal to wall plane.

2. Thermal Movement: Provide for thermal movement caused by 180 degrees F. (82.2 degrees C.) surface temperature, without causing buckling stresses on glass, joint seal

failure, undue stress on structural elements, damaging loads on fasteners, reduction of performance, or detrimental effects.

3. Deflection: Maximum allowable deflection in any member when tested in accordance with ASTM E 330-90 with allowable stress in accordance with AA Specifications for Aluminum Structures.

- a. Without Horizontals: L/175 or 3/4 inch (19.1mm) maximum. .
- b. With Horizontals: L/175 or L/240 + 1/4 inch (6.4mm) for spans greater than 13 feet-6 inches (4.1m) but less than 40 feet-0 inch (12.2m).

4. Air Infiltration: When tested in accordance with ASTM E 283-91 at differential static pressure of 6.24 PSF (299 Pa), completed storefront systems shall have maximum allowable infiltration of 0.03 CFM/FT² (0.56 m³/h*m²).

5. Air Infiltration: When tested in accordance with ASTM E 283-91 at differential static pressure of 6.24 PSF (299 Pa), completed storefront systems shall have maximum allowable infiltration of 0.02 CFM/FT² (0.37 m³/h*m²).

6. Air Infiltration: When tested in accordance with ASTM E 283-91 at differential static pressure of 6.24 PSF (299 Pa), completed storefront systems shall have maximum allowable infiltration of 0.01 CFM/FT² (0.19 m³/h*m²).

7. Water Infiltration: No uncontrolled water other than condensation on indoor face of any component when tested in accordance with ASTM E 331-93 at test pressure differential of 10 PSF (479 Pa).

8. Water Infiltration: No uncontrolled water other than condensation on indoor face of any component when tested in accordance with ASTM E 331-93 at test pressure differential of 12 PSF (718 Pa).

9. Water Infiltration: No uncontrolled water other than condensation on indoor face of any component when tested in accordance with ASTM E 331-93 at test pressure differential of 15 PSF (718 Pa).

10. Water Infiltration: No uncontrolled water other than condensation on indoor face of any component when tested in accordance with ASTM E 331-93 at test pressure differential of 25 PSF (1197 Pa).

11. Thermal Performance: When tested in accordance with AAMA 1503.1-88 and ASTM C 236-89:

- a. Condensation Resistance Factor (CRF): A minimum of 60.
- b. Thermal Transmittance U Value: 0.46 BTU/HR/FT²/ degrees F or less (frame only).

- c. Condensation Resistance Factor (CRF): A minimum of 61.
 - d. Thermal Transmittance U Value: 0.42 BTU/HR/FT²/ degrees F or less (frame only).
 - e. Condensation Resistance Factor (CRF): A minimum of 63.
 - f. Thermal Transmittance U Value: 0.46 BTU/HR/FT²/ degrees F or less (frame only).
1. Air Infiltration: Completed storefront systems shall have 0.01 CFM/FT² (0.18 m³/h*m²) maximum allowable infiltration when tested in accordance with ASTM E 283-91 at differential static pressure of 6.24 psf (299 Pa).
 2. Water Infiltration: No uncontrolled water other than condensation on indoor face of any component when tested in accordance with ASTM E 331-93 at test pressure differential of 10 psf (479 Pa). Water test to be performed immediately after design pressure test.
 3. Wind Loads: Completed storefront system shall withstand wind pressure loads normal to wall plane indicated:
 - a. Exterior Walls:
 - 1) Positive Pressure: 20 to 22 psf (3.1kPa).
 - 2) Negative Pressure: 20 to 22 psf (3.1kPa).
 4. Deflection: Maximum allowable deflection in any member when tested in accordance with ASTM E 330-90 with allowable stress in accordance with AA Specifications for Aluminum Structures.
 - a. Without Horizontals: L/175 or 3/4 inch (19.1mm) maximum. .
 - b. With Horizontals: L/175 or L/240 + 1/4 inch (6.4mm) for spans greater than 13 feet-6 inches (4.1m) but less than 40 feet-0 inch (12.2m).
 5. Thermal Movement: Provide for thermal movement caused by 180 degrees F. (82.2 degrees C.) surface temperature, without causing buckling stresses on glass, joint seal failure, undue stress on structural elements, damaging loads on fasteners, reduction of performance, or detrimental effects.
1. Air Infiltration: Completed storefront systems shall have 0.02 CFM/FT² (0.37 m³/h*m²) maximum allowable infiltration when tested in accordance with ASTM E 283-91 at differential static pressure of 6.24 psf (299 Pa).
 2. Air Infiltration: Completed storefront systems shall have 0.04 CFM/FT² (0.74 m³/h*m²) maximum allowable infiltration when tested in accordance with ASTM E 283-91 at differential static pressure of 6.24 psf (299 Pa).

3. Water Infiltration: No uncontrolled water other than condensation on indoor face of any component when tested in accordance with ASTM E 331-93 at test pressure differential of 12 psf (575 Pa). Water test to be performed immediately after design pressure test.

4. Wind Loads: Completed storefront system shall withstand wind pressure loads normal to wall plane indicated:

- a. Exterior Walls: with steel reinforcing.
 - 1) Positive Pressure: 20 to 22 psf (3.4 kPa).
 - 2) Negative Pressure: 25 to 30 psf (4.3 kPa).
- b. Exterior Walls: without steel reinforcing.
 - 1) Positive Pressure: 30 psf (2.4 kPa).
 - 2) Negative Pressure: 30 psf (3.4 kPa).

5. Deflection: Maximum allowable deflection in any member when tested in accordance with ASTM E 330-90 with allowable stress in accordance with AA Specifications for Aluminum Structures.

- a. Without Horizontals: L/175 or 3/4 inch (19.1mm) maximum. .
- b. With Horizontals: L/175 or L/240 + 1/4 inch (6.4mm) for spans greater than 13 feet-6 inches (4.1m) but less than 40 feet-0 inch (12.2m).

6. Thermal Movement: Provide for thermal movement caused by 180 degrees F. (82.2 degrees C.) surface temperature, without causing buckling stresses on glass, joint seal failure, undue stress on structural elements, damaging loads on fasteners, reduction of performance, or detrimental effects.

1.5 ENTRANCE SYSTEM

A. Provide aluminum swing doors that comply with the following performance requirements:

1. Air Infiltration (Single Acting Butt Hinges or Offset Pivots): Air infiltration shall be tested in accordance with ASTM E283-91 at static pressure of 1.57 PSF (75 Pa). Infiltration shall not exceed the following:

- a. 20D Single Doors: 0.18 CFM/FT (1.02 m³/h*m) of crack length.
 - b. 20D Pair of Doors: 0.27 CFM/FT (1.53 m³/h*m) of crack length.
 - c. 40D Single Doors: 0.40 CFM/FT (2.27 m³/h*m) of crack length.
 - d. 40D Pair of Doors: 1.22 CFM/FT (6.92 m³/h*m) of crack length.
 - e. 35D/50D Single Doors: 0.43 CFM/FT (2.44 m³/h*m) of crack length.
 - f. 35D/50D Pair of Doors: 0.50 CFM/FT (2.83 m³/h*m) of crack length.
- 2. Structural:** Door corner structural strength test using a dual moment loading criteria:
- a. Model: 20D Swing Door; 245 lbs (111 kg).
 - b. Model: 35D Swing Door; 290 lbs (132 kg).
 - c. Model: 40D Swing Door; 470 lbs (213 kg).

- d. Model: 50D Swing Door; 300 lbs (136 kg).
- 3. Structural Uniform Load Test:
 - a. Single Doors: 90 psf (4.3 kPa).
 - b. Pair of Doors: 90 psf (4.3 kPa).
- 4. Structural Uniform Load Test:
 - a. Single Doors: +90/-104 psf (4.3 kPa/-4.98 kPa).
 - b. Pair of Doors: +45/-45 psf (4.3 kPa/-2.2kPa).
- 5. Forced Entry Resistance: 300 lbs (136 kg) satisfactory.

1.6 SUBMITTALS

A. Submit under provisions of Section 01300.

B. Product Data - Manufacturer's data sheets on each product to be used, including:

- 1. Preparation instructions and recommendations.
- 2. Storage and handling requirements and recommendations.
- 3. Installation methods.

C. Shop Drawings:

- 1. Drawings showing layout, profiles, and product components, including anchorage, accessories, finish colors and textures.

D. Certifications:

- 1. Submit certified test reports showing compliance with specified performance characteristics and physical properties.

E. Selection Samples: For each finish product specified, two complete sets of color chips representing manufacturer's full range of available colors and patterns.

F. Verification Samples: For each finish product specified, two samples, minimum size 6 inches (150 mm) square, representing actual product, color, and patterns.

G. Project Record Documents: Submit project record documents for installed materials in accordance with Section 01700 - Project Closeout (Project Record Documents) Section.

1.7 QUALITY ASSURANCE

A. Manufacturer Qualifications:

- 1. Manufacturer capable of providing field service representation during construction, approving acceptable installer and approving application method.

B. Installer Qualifications:

- 1. Installer experienced to perform work of this section that has specialized in the

installation of work similar to that required for this project.

2. Submit reference list of completed projects.

C. Mock-Up: Provide a mock-up for evaluation of surface preparation techniques and application workmanship.

1. Install at project site a job mock-up using acceptable products and manufacturer approved installation methods in location designated by Architect.

2. Do not proceed with remaining work until workmanship, color, and sheen are approved by Architect.

3. Refinish mock-up area as required to produce acceptable work.

1.8 DELIVERY, STORAGE, AND HANDLING

A. Store products in manufacturer's unopened packaging until ready for installation.

B. Store and dispose of solvent-based materials, and materials used with solvent-based materials in accordance with requirements of local authorities having jurisdiction.

1.9 PROJECT CONDITIONS

A. Maintain environmental conditions (temperature, humidity, and ventilation) within limits recommended by manufacturer for optimum results. Do not install products under environmental conditions outside manufacturer's absolute limits.

1.10 WARRANTY

A. Manufacturer's Warranty: Submit, for Owner's acceptance, manufacturer's standard warranty document executed by authorized company official. Manufacturer's warranty is in addition to, and not a limitation of, other rights Owner may have under the Contract Documents.

1. Beneficiary: Issue warranty in the legal name of the project Owner.

2. Warranty Period: Ten (10) years commencing on Date of Substantial Completion.

3. Warranty Acceptance: Owner is sole authority who will determine acceptability of manufacturer's warranty documents.

PART 2 PRODUCTS

2.1 MANUFACTURERS

A. Acceptable Manufacturers:

1. YKK AP America, Inc.

2. Kawneer Co., Inc.

3. EFCO Corporation

B. Coordinate with requirements of Division 1 section on product options and substitutions.

C. Substitutions: Or Equal.

D. Requests for substitutions will be considered in accordance with provisions of Section 01600.

2.2 STOREFRONT APPLICATIONS/SCOPE

A. Center set, flush glazed; jambs continuous; head, sill, and jamb attached by screws into rough opening.

B. Center set, flush glazed; jambs and vertical mullions continuous; head, sill, intermediate horizontal attached by screw spline joinery. Manufacturer's standard extruded aluminum expansion mullions, 90 degree corner posts, three way corner post, entrance door framing, and indicated shapes.

C. Center set, flush glazed; head and sill members continuous; intermediate horizontals attached by means of shear block. Jambs and vertical mullions are captured inside the continuous head and sill members and held in place by filler inserts. Manufacturer's standard extruded aluminum expansion mullions, 0 - 15 degree hinged mullions, 90 degree corner posts, entrance door framing, and indicated shapes.

D. Center rabbet, exterior flush glazed; jambs and vertical mullions continuous; head, sill, intermediate horizontal attached by screw spline joinery. Manufacturer's standard extruded aluminum expansion mullions, 0- 15 degree hinged mullions, 90 degree corner posts, flexible corner posts, three way corner post, 93- 170 degree flexible corner posts, entrance door framing, and indicated shapes.

E. Center set, exterior flush glazed; jambs and vertical mullions continuous; head, sill, intermediate horizontal attached by screw spline joinery. Manufacturer's standard extruded aluminum mullions, 90 degree corner posts, entrance door framing, and indicated shapes. Provide continuous thermal barrier by means of 6/6 nylon polyamide glass fiber reinforced pressure extruded bars. Systems employing non-structural thermal barriers are not acceptable.

F. Center set, exterior flush glazed; jambs and vertical mullions continuous; head, sill, intermediate horizontal attached by screw spline joinery or shear block attachment. Manufacturer's standard extruded aluminum mullions, 90 degree corner posts, entrance door framing, and indicated shapes. Provide continuous thermal barrier by means of a poured and debridged pocket consisting of a two-part, chemically curing high density polyurethane which is bonded to the aluminum by YKK ThermaBond Plus. Systems employing non-structural thermal barriers are not acceptable.

H. Thermally broken, exterior flush glazed; horizontal and vertical framing members shall have a nominal face dimension of 1-3/4 inches (44.5 mm). Intermediate horizontals attached by screw spline and/or shear block joinery with concealed fasteners. Manufacturer's standard extruded aluminum mullions, entrance door framing, and indicated shapes.

- a. 1 inch (25 mm) glass with DuPont SentryGlas Composite laminate.
- b. 1-5/16 inches (33 mm) Saf-Glas by Security Impact Glass with 0.070 inch (1.8 mm) Polycarbonate interlayer. Annealed, heat strengthened, or tempered as required unless otherwise noted.
- c. 1-5/16 inches (33 mm) Solutia Saflex HP with 0.100 inch (2.5 mm) PVB interlayer (heat strengthened only).
- 3. Glass for Small Missile Impact:
 - a. 1-5/16 inches (33 mm) Solutia Saflex with 0.060 inch (1.5 mm) PVB interlayer (heat strengthened only).
 - b. 1-5/16 inches (33 mm) laminated glass with 0.060 inch (1.5 mm) Butacite PVB interlayer (heat strengthened only).
- 4. Glazing: Dow Corning 995 Structural Silicone Adhesive.

2.3 ENTRANCE APPLICATIONS/SCOPE

A. Standard Entrances: See Architectural drawings for door pattern.

- 1. Corner Construction: Fabricate door corners joined by concealed reinforcement secured with screws, and sigma deep penetration welding.
- 2. Glazing Stops: Manufacturer's standard snap-in glazing stops with EPDM glazing gaskets to prevent water infiltration.
- 3. Weatherstripping: Manufacturer's standard pile type in replaceable rabbets for stiles; manufacturer's standard EPDM bulb type in door frames.
- 4. Hardware: Manufacturer's standard as selected by Architect.

B. Hurricane Resistant Doors:

- 1. Corner Construction: Fabricate door corners joined by concealed reinforcement secured with screws, and sigma deep penetration welding.
- 2. Glazing Stops: Manufacturer's standard snap-in glazing stops with EPDM glazing gaskets to prevent water infiltration.
- 3. Weatherstripping: Manufacturer's standard pile type in replaceable rabbets for stiles; manufacturer's standard EPDM bulb type in door frames.
- 4. Hardware (Per Leaf):
 - a. (1-1/2) pair mortise butt hinges, Ball bearing, 4-1/2 by 4, (H-2301).
 - b. (1) Adams Rite MS1850 three point hook bolt lock.
 - c. (2) H-4202 Keyed cylinders (H-4204 thumb turn on inside optional).
 - d. (1) Set type "A" standard YKK AP push/pull.
 - e. (1) Type "C" 1 inch diameter tubular push/pull.
 - f. (1) E9-0482 mill finish aluminum threshold with E2-0051 elastomer weather strip, wept, and counterflashed.

1.2 MATERIALS

A. Extrusions: ASTM B 221 (ASTM B 221M), 6063-T5 Aluminum Alloy.

B. Aluminum Sheet:

- 1. Anodized Finish: ASTM B 209 (ASTM B 209M), 5005-H14 Aluminum Alloy, 0.050 inch (1.27 mm) minimum thickness.
- 2. Painted Finish: ASTM B 209 (ASTM B 209M), 3003-H14 Aluminum Alloy, 0.080

inch (1.95 mm) minimum thickness.

C. Accessories:

1. Fasteners: Zinc plated steel concealed fasteners; Hardened aluminum alloys or AISI 300 series stainless steel exposed fasteners, countersunk, finish to match aluminum color.
2. Sealant: Non-skinning type, AAMA 803.3.
3. Glazing: Setting blocks, edge blocks, and spacers in accordance with ASTM C 864, shore durometer hardness as recommended by manufacturer; Glazing gaskets in accordance with ASTM C 864.

1.3 FABRICATION

A. Frame Construction:

1. Fabricate and assemble units with joints only at intersection of aluminum members with uniform hairline joints; rigidly secure, and sealed in accordance with manufacturer's recommendations.
2. Hardware: Drill and cut to template for hardware. Reinforce frames and door stiles to receive hardware in accordance with manufacturer's recommendations.
3. Welding: Conceal welds on aluminum members in accordance with AWS recommendations or methods recommended by manufacturer. Members showing welding bloom or discoloration on finish or material distortion will be rejected.

B. Door Construction:

1. Corner Construction: Fabricate door corners joined by concealed reinforcement secured with screws, and sigma deep penetration welding.
2. Glazing Stops: Manufacturer's standard snap-in glazing stops with EPDM glazing gaskets to prevent water infiltration.
3. Weatherstripping: Manufacturer's standard pile type in replaceable rabbets for stiles; manufacturer's standard EPDM bulb type in door frames.
4. Hardware: Manufacturer's standard as selected by Architect.

C. Fabrication Tolerances:

1. Material Cuts: Square to 1/32 inch (0.8 mm) off square, maximum, over largest dimension; proportionate amount of
2. 1/32 inch (0.8 mm) on other two dimensions.
3. Maximum Offset: 1/64 inch (0.4 mm) in alignment between two consecutive members in line, end to end.
4. Maximum Offset: 1/64 inch (0.4 mm) between framing members at glazing pocket corners.
5. Joints (Between adjacent members in same assembly): Hairline and square to adjacent member.
6. Variation (In squaring diagonals for doors and fabricated assemblies): 1/16 inch (1.6 mm).
7. Flatness (For doors and fabricated assemblies): +/- 1/16 inch (+/- 1.6 mm) off neutral plane.

1.4 FINISH

- A. Anodized Finishing:** Prepare aluminum surfaces for specified finish; apply shop finish in

accordance with the following:

1. Anodic Coating: Electrolytic color coating followed by an organic seal applied in accordance with the requirements of AAMA 612-02. Aluminum extrusions shall be produced from quality controlled billets meeting AA-6063-T5.
 - a. Exposed Surfaces shall be free of scratches and other serious blemishes.
 - b. Extrusions shall be given a caustic etch followed by an anodic oxide treatment and then sealed with an organic coating applied with an electrodepositioning process.
 - c. The anodized coating shall comply with the requirements of AAMA 612-02: Voluntary Specifications, Performance Requirements and Test Procedures for Combined Coatings of Anodic Oxide and Transparent Organic Coatings on Architectural Aluminum. Testing shall demonstrate the ability of the finish to resist damage from mortar, salt spray, and chemicals commonly found on construction sites, and to resist the loss of color and gloss.
 - d. Overall coating thickness for finishes shall be a minimum of 0.7 mils (.018 mm).
2. CASS Corrosion Resistance Test, CASS 240/ASTM B368 Test Method.
3. AAMA 2605 Performance Tests:
 - a. 7.3 Dry Film Hardness.
 - b. 7.8.2 Salt Spray Resistance.

C. Finishes Testing:

1. Apply 0.5 percent solution NaOH, sodium hydroxide, to small area of finished sample area; leave in place for sixty minutes; lightly wipe off NaOH; Do not clean area further.
2. Submit samples with test area noted on each sample.

PART 2 EXECUTION

2.1 EXAMINATION

- A.** Do not begin installation until openings have been properly prepared.
- B.** If opening preparation is the responsibility of another installer, notify Architect of unsatisfactory conditions before proceeding.
- C.** Verify actual measurements/openings by field measurements before fabrication; show recorded measurements on shop drawings. Coordinate field measurements, fabrication schedule with construction progress to avoid construction delays.

2.2 INSTALLATION

- A.** Install in accordance with manufacturer's instructions.
- B.** Install manufacturer's system in accordance with shop drawings, and within specified tolerances.
 1. Protect aluminum members in contact with masonry, steel, concrete, or dissimilar materials using nylon pads or bituminous coating.
 2. Shim and brace aluminum system before anchoring to structure.

3. Seal metal to metal sash joints using sealant recommended by system manufacturer.
4. Verify storefront system allows water entering system to be collected in gutters and wept to exterior.
5. Locate expansion mullions where indicated on reviewed shop drawings.

C. Manufacturer's Field Services: Provide manufacturer's field service consisting of product use recommendations and periodic site visit for inspection of product installation in accordance with manufacturer's instructions.

2.3 TESTING

A. Field Test: Conduct field test to determine water tightness of storefront and entrance system. Conduct test in accordance with AAMA 501.3-94 at locations selected by Architect.

2.4 PROTECTION

- A.** Adjust swing doors for operation in accordance with manufacturer's recommendations.
- B.** Clean installed products in accordance with manufacturer's instructions prior to owner's acceptance, and remove construction debris from project site. Legally dispose of debris.
- C.** Protect the installed product's finish surfaces from damage during construction.
- D.** Touch-up, repair or replace damaged products before Substantial Completion.

END OF SECTION

SECTION 08 71 00**DOOR HARDWARE****PART 1 - GENERAL****1.1 SUMMARY:**

- A. Section Includes: Finish Hardware for door openings, except as otherwise specified herein.
 - 1. Door hardware for steel (hollow metal) doors.
 - 2. Door hardware for aluminum doors.
 - 3. Door hardware for wood doors.
 - 4. Door hardware for other doors indicated.
 - 5. Keyed cylinders as indicated.

- B. Related Sections:
 - 1. Division 6: Rough Carpentry.
 - 2. Division 8: Aluminum Doors and Frames
 - 3. Division 8: Hollow Metal Doors and Frames.
 - 4. Division 8: Wood Doors.
 - 5. Division 26 Electrical
 - 6. Division 28: Electronic Security

- C. References: Comply with applicable requirements of the following standards. Where these standards conflict with other specific requirements, the most restrictive shall govern.
 - 1. Builders Hardware Manufacturing Association (BHMA)
 - 2. NFPA 101 Life Safety Code
 - 3. NFPA 80 -Fire Doors and Windows
 - 4. ANSI-A156.xx- Various Performance Standards for Finish Hardware
 - 5. UL10C – Positive Pressure Fire Test of Door Assemblies
 - 6. ANSI-A117.1 – Accessible and Usable Buildings and Facilities
 - 7. DHI /ANSI A115.IG – Installation Guide for Doors and Hardware

- D. Intent of Hardware Groups
 - 1. Should items of hardware not definitely specified be required for completion of the Work, furnish such items of type and quality comparable to adjacent hardware and appropriate for service required.
 - 2. Where items of hardware aren't definitely or correctly specified, are required for completion of the Work, a written statement of such omission, error, or other discrepancy to Architect, prior to date specified for receipt of bids for clarification by addendum; or, furnish such items in the type and quality established by this specification, and appropriate to the service intended.

- E. Allowances
 - 1. Refer to Division 1 for allowance amount and procedures.

- F. Alternates
 - 1. Refer to Division 1 for Alternates and procedures.

1.2 SUBSTITUTIONS:

- A. Comply with Division 1.

1.3 SUBMITTALS:

- A. Comply with Division 1.
- B. Special Submittal Requirements: Combine submittals of this Section with Sections listed below to ensure the "design intent" of the system/assembly is understood and can be reviewed together.
- C. Product Data: Manufacturer's specifications and technical data including the following:
 - 1. Detailed specification of construction and fabrication.
 - 2. Manufacturer's installation instructions.
 - 3. Wiring diagrams for each electric product specified. Coordinate voltage with electrical before submitting.
 - 4. Submit 6 copies of catalog cuts with hardware schedule.
 - 5. Provide 9001-Quality Management and 14001-Environmental Management for products listed in Materials Section 2.2
- D. Shop Drawings - Hardware Schedule: Submit 6 complete reproducible copy of detailed hardware schedule in a vertical format.
 - 1. List groups and suffixes in proper sequence.
 - 2. Completely describe door and list architectural door number.
 - 3. Manufacturer, product name, and catalog number.
 - 4. Function, type, and style.
 - 5. Size and finish of each item.
 - 6. Mounting heights.
 - 7. Explanation of abbreviations and symbols used within schedule.
 - 8. Detailed wiring diagrams, specially developed for each opening, indicating all electric hardware, security equipment and access control equipment, and door and frame rough-ins required for specific opening.
- E. Templates: Submit templates and "reviewed Hardware Schedule" to door and frame supplier and others as applicable to enable proper and accurate sizing and locations of cutouts and reinforcing.
 - 1. Templates, wiring diagrams and "reviewed Hardware Schedule" of electrical terms to electrical for coordination and verification of voltages and locations.
- F. Samples: (If requested by the Architect)
 - 1. 1 sample of Lever and Rose/Escutcheon design, (pair).
 - 2. 3 samples of metal finishes
- G. Contract Closeout Submittals: Comply with Division 1 including specific requirements indicated.
 - 1. Operating and maintenance manuals: Submit 3 sets containing the following.
 - a. Complete information in care, maintenance, and adjustment, and data on repair and replacement parts, and information on preservation of finishes.
 - b. Catalog pages for each product.

- c. Name, address, and phone number of local representative for each manufacturer.
 - d. Parts list for each product.
2. Copy of final hardware schedule, edited to reflect, "As installed".
 3. Copy of final keying schedule
 4. As installed "Wiring Diagrams" for each piece of hardware connected to power, both low voltage and 110 volts.
 5. One set of special tools required for maintenance and adjustment of hardware, including changing of cylinders.

1.4 QUALITY ASSURANCE

A. Comply with Division 1.

1. Statement of qualification for distributor and installers.
2. Statement of compliance with regulatory requirements and single source responsibility.
3. Distributor's Qualifications: Firm with 3 years experience in the distribution of commercial hardware.
 - a. Distributor to employ full time Architectural Hardware Consultants (AHC) for the purpose of scheduling and coordinating hardware and establishing keying schedule.
 - b. Hardware Schedule shall be prepared and signed by an AHC.
4. Installer's Qualifications: Firm with 3 years experienced in installation of similar hardware to that required for this Project, including specific requirements indicated.
5. Regulatory Label Requirements: Provide testing agency label or stamp on hardware for labeled openings.
 - a. Provide UL listed hardware for labeled and 20 minute openings in conformance with requirements for class of opening scheduled.
 - b. Underwriters Laboratories requirements have precedence over this specification where conflict exists.
6. Single Source Responsibility: Except where specified in hardware schedule, furnish products of only one manufacturer for each type of hardware.

- ##### B. Review Project for extent of finish hardware required to complete the Work. Where there is a conflict between these Specifications and the existing hardware, notify the Architect in writing and furnish hardware in compliance with the Specification unless otherwise directed in writing by the Architect.

1.5 DELIVERY, STORAGE, AND HANDLING

A. Packing and Shipping: Comply with Division 1.

1. Deliver products in original unopened packaging with legible manufacturer's identification.
2. Package hardware to prevent damage during transit and storage.
3. Mark hardware to correspond with "reviewed hardware schedule".
4. Deliver hardware to door and frame manufacturer upon request.

- ##### B. Storage and Protection: Comply with manufacturer's recommendations.

1.6 PROJECT CONDITIONS:

- A. Coordinate hardware with other work. Furnish hardware items of proper design for use on doors and frames of the thickness, profile, swing, security and similar requirements indicated, as necessary for the proper installation and function, regardless of omissions or conflicts in the information on the Contract Documents.
- B. Review Shop Drawings for doors and entrances to confirm that adequate provisions will be made for the proper installation of hardware.

1.7 WARRANTY:

- A. Refer to Conditions of the Contract
- B. Manufacturer's Warranty:
 - 1. Closers: Ten years
 - 2. Exit Devices: Five Years
 - 3. Locksets & Cylinders: Three years
 - 4. All other Hardware: Two years.

1.8 OWNER'S INSTRUCTION:

- A. Instruct Owner's personnel in operation and maintenance of hardware units.

1.9 MAINTENANCE:

- A. Extra Service Materials: Deliver to Owner extra materials from same production run as products installed. Package products with protective covering and identify with descriptive labels. Comply with Division 1 Closeout Submittals Section.
 - 1. Special Tools: Provide special wrenches and tools applicable to each different or special hardware component.
 - 2. Maintenance Tools: Provide maintenance tools and accessories supplied by hardware component manufacturer.
 - 3. Delivery, Storage and Protection: Comply with Owner's requirements for delivery, storage and protection of extra service materials.
- B. Maintenance Service: Submit for Owner's consideration maintenance service agreement for electronic products installed.

PART 2 - PRODUCTS

2.1 MANUFACTURERS:

- A. The following manufacturers are approved subject to compliance with requirements of the Contract Documents. Approval of manufacturers other than those listed shall be in accordance with Division 1.

<u>Item:</u>	<u>Manufacturer:</u>
Hinges	Stanley
Continuous Hinges	Stanley
Locksets	K2t
Cylinders	Best Patented Cormax
Exit Devices	Precision

Closers	K2
Push/Pull Plates	Trimco
Protection Plates	Trimco
Overhead Stops	ABH
Door Stops	Trimco
Flush Bolts	Trimco
Threshold & Gasketing	Zero

2.2 MATERIALS:

A. Hinges:

1. Template screw hole locations
2. Minimum of 2 permanently lubricated non-detachable bearings
3. Equip with easily seated, non-rising pins
4. Sufficient size to allow 180-degree swing of door
5. Furnish hinges with five knuckles and flush **[concealed]** bearings
6. Provide hinge type as listed in schedule.
7. Furnish 3 hinges per leaf to 7 foot 6 inch height. Add one for each additional 30 inches in height or fraction thereof.
8. Certified by BHMA for all applicable ANSI Standards for type, size, function and finish
9. UL10C listed for Fire

B. Cylindrical Type Locks and Latchsets:

1. Tested and approved by BHMA for ANSI A156.2, Series 4000, Operational Grade 1, Extra-Heavy Duty, and be UL10C listed.
2. Provide 9001-Quality Management and 14001-Environmental Management.
3. Fit modified ANSI A115.2 door preparation.
4. Locksets and cores to be of the same manufacturer to maintain complete lockset warranty
5. Locksets to have anti-rotational studs that are thru-bolted
6. Keyed lever shall not have exposed "keeper" hole
7. Each lever to have independent spring mechanism controlling it
8. 2-3/4 inch (70 mm) backset
9. 9/16 inch (14 mm) throw latchbolt
10. Outside lever sleeve to be seamless, of one-piece construction made of a hardened steel alloy
11. Keyed lever to be removable only after core is removed, by authorized control key
12. Provide locksets with 7-pin removable and interchangeable core cylinders
13. Hub, side plate, shrouded rose, locking pin to be a one-piece casting with a shrouded locking lug.
14. Locksets outside locked lever must withstand minimum 1400 inch pounds of torque. In excess of that, a replaceable part will shear. Key from outside and inside lever will still operate lockset.
15. Core face must be the same finish as the lockset.
16. Functions and design as indicated in the hardware groups.

C. Exit Devices shall:

1. Tested and approved by BHMA for ANSI 156.3, Grade 1
2. Provide 9001-Quality Management and 14001-Environmental Management.
3. Provide a deadlocking latchbolt
4. Non-fire rated exit devices shall have cylinder dogging.
5. Touchpad shall be "T" style

6. Exposed components shall be of architectural metals and finishes.
 7. Lever design shall match lockset lever design
 8. Provide strikes as required by application.
 9. Fire exit devices to be listed for UL10C
 10. UL listed for Accident Hazard
 11. Shall consist of a cross bar or push pad, the actuating portion of which extends across, shall not be less than one half the width of the door leaf.
 12. Provide vandal resistant or breakaway trim
 13. Aluminum vertical rod assemblies are acceptable only when provide with the manufacturers optional top and bottom stainless steel rod guard protectors.
- D. Cylinders:
1. Provide the necessary cylinder housings, collars, rings & springs as recommended by the manufacturer for proper installation.
 2. Provide the proper cylinder cams or tail piece as required to operate all locksets and other keyed hardware items listed in the hardware sets.
 3. Coordinate and provide as required for related sections.
- E. Door Closers shall:
1. Tested and approved by BHMA for ANSI 156.4, Grade 1
 2. UL10C certified
 3. Provide 9001-Quality Management and 14001-Environmental Management.
 4. Closer shall have extra-duty arms and knuckles
 5. Conform to ANSI 117.1
 6. Maximum 2 7/16 inch case projection with non-ferrous cover
 7. Separate adjusting valves for closing and latching speed, and backcheck
 8. Provide adapter plates, shim spacers and blade stop spacers as required by frame and door conditions
 9. Full rack and pinion type closer with 1½" minimum bore
 10. Mount closers on non-public side of door, unless otherwise noted in specification
 11. Closers shall be non-handed, non-sized and multi-sized.
- F. Door Stops: Provide a dome floor or wall stop for every opening as listed in the hardware sets.
1. Wall stop and floor stop shall be wrought bronze, brass or stainless steel.
 2. Provide fastener suitable for wall construction.
 3. Coordinate reinforcement of walls where wall stop is specified.
 4. Provide dome stops where wall stops are not practical. Provide spacers or carpet riser for floor conditions encountered
- G. Over Head Stops: Provide a Surface mounted or concealed overhead when a floor or wall stop cannot be used or when listed in the hardware set.
1. Concealed overhead stops shall be heavy duty bronze or stainless steel.
 2. Surface overhead stops shall be heavy duty bronze or stainless steel.
- H. Push Plates: Provide with four beveled edges ANSI J301, .050 thickness, size as indicated in hardware set. Furnish oval-head countersunk screws to match finish.
- I. Pulls with plates: Provide with four beveled edges ANSI J301, .050 thickness Plate s with ANSI J401 Pull as listed in hardware set. Provide proper fasteners for door construction.

- J. Kickplates: Provide with four beveled edges ANSI J102, 10 inches high by width less 2 inches on single doors and 1 inch on pairs of doors. Furnish oval-head countersunk screws to match finish.
- K. Mop plates: Provide with four beveled edges ANSI J103, 4 inches high by width less 1 inch on single doors and 1 inch on pairs of doors. Furnish oval-head countersunk screws to match finish.
- L. Door Bolts: Flush bolts for wood or metal doors.
1. Provide a set of Automatic bolts, Certified ANSI/BHMA 156.3 Type 25 for hollow metal label doors.
 2. Provide a set of Automatic bolts, Certified ANSI/BHMA 156.3 Type 27 at wood label doors.
 3. Manual flush bolts, Certified ANSI/BHMA 156.16 at openings where allowed local authority.
 4. Provide Dust Proof Strike, Certified ANSI/BHMA 156.16 at doors with flush bolts without thresholds.
- M. Coordinator and Brackets: Provide a surface mounted coordinator when automatic bolts are used in the hardware set.
1. Coordinator, Certified ANSI/BHMA A1156.3 Type 21A for full width of the opening.
 2. Provide mounting brackets for soffit applied hardware.
 3. Provide hardware preparation (cutouts) for latches as necessary.
- N. Weatherstripping: Provide at head and jambs only those units where resilient or flexible seal strip is easily replaceable. Where bar-type weatherstrip is used with parallel arm mounted closers install weatherstrip first.
1. Weatherstrip shall be resilient seal of (Neoprene, Polyurethane, Vinyl, Pile, Nylon Brush, Silicone)
 2. UL10C Positive Pressure rated seal set when required.
- O. Door Bottoms/Sweeps: Surface mounted or concealed door bottom where listed in the hardware sets.
1. Door seal shall be resilient seal of (Neoprene, Polyurethane, Nylon Brush, Silicone)
 2. UL10C Positive Pressure rated seal set when required.
- P. Thresholds: Thresholds shall be aluminum beveled type with maximum height of ½" for conformance with ADA requirements. Furnish as specified and per details. Provide fasteners and screws suitable for floor conditions.
- Q. Provide one wall mounted Telkee, Lund or MMF series key cabinet complete with hooks, index and tags to accommodate 50% expansion. Coordinate mounting location with architect.
- R. Silencers: Furnish silencers on all interior frames, 3 for single doors, 2 for pairs. Omit where any type of seals occur.

2.3 FINISH:

- A. Designations used in Schedule of Finish Hardware - 3.5, and elsewhere to indicate hardware finishes are those listed in ANSI/BHMA A156.18 including coordination with traditional U.S. finishes shown by certain manufacturers for their products
- B. Powder coat door closers to match other hardware, unless otherwise noted.
- C. Aluminum items shall be finished to match predominant adjacent material. Seals to coordinate with frame color.

2.4 KEYS AND KEYING:

- A. Provide keyed brass construction cores and keys during the construction period. Construction control and operating keys and core shall not be part of the Owner's permanent keying system or furnished in the same keyway (or key section) as the Owner's permanent keying system. Permanent cores and keys (prepared according to the accepted keying schedule) will be furnished to the Owner.
- B. Cylinders, removable and interchangeable core keyed to the existing Best Patented Cormax Masterkey System.
- C. Permanent keys and cores: Stamped with the applicable key mark for identification. These visual key control marks or codes will not include the actual key cuts. Permanent keys will also be stamped "Do Not Duplicate."
- D. Transmit Grand Masterkeys, Masterkeys and other Security keys to Owner by Registered Mail, return receipt requested.
- E. Furnish keys in the following quantities:
 - 1. 1 each Grand Masterkeys
 - 2. 4 each Masterkeys
 - 3. 2 each Change keys each keyed core
 - 4. 10 each Construction masterkeys
 - 5. 1 each Control keys
- F. The Owner, or the Owner's agent, will install permanent cores and return the construction cores to the Hardware Supplier. Construction cores and keys remain the property of the Hardware Supplier.
- G. Keying Schedule: Arrange for a keying meeting, with Architect Owner and hardware supplier, and other involved parties to ensure locksets and locking hardware, are functionally correct and keying complies with project requirements. Furnish 3 typed copies of keying schedule to Architect.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Verification of conditions: Examine doors, frames, related items and conditions under which Work is to be performed and identify conditions detrimental to proper and or timely completion.
 - 1. Do not proceed until unsatisfactory conditions have been corrected.

3.2 HARDWARE LOCATIONS:

- A. Mount hardware units at heights indicated in the following publications except as specifically indicated or required to comply with the governing regulations.
 - 1. Recommended Locations for Builder's Hardware for Standard Steel Doors and Frames, by the Door and Hardware Institute (DHI).
 - 2. Recommended locations for Architectural Hardware for flush wood doors (DHI).
 - 3. WDMA Industry Standard I.S.-1A-04, Industry Standard for Architectural wood flush doors.

3.3 INSTALLATION:

- A. Install each hardware item per manufacturer's instructions and recommendations. Do not install surface mounted items until finishes have been completed on the substrate. Set units level, plumb and true to line and location. Adjust and reinforce the attachment substrate as necessary for proper installation and operation.
- B. Conform to local governing agency security ordinance.
- C. Install Conforming to ICC/ANSI A117.1 Accessible and Usable Building and Facilities.
 - 1. Adjust door closer sweep periods so that from the open position of 70 degrees, the door will take at least 3 seconds to move to a point 3 inches from the latch, measured to the landing side of the door.
- D. Installed hardware using the manufacturers fasteners provided. Drill and tap all screw holes located in metallic materials. Do not use "Riv-Nuts" or similar products.

3.4 FIELD QUALITY CONTROL AND FINAL ADJUSTMENT

- A. Contractor/Installers, Field Services: After installation is complete, contractor shall inspect the completed door openings on site to verify installation of hardware is complete and properly adjusted, in accordance with both the Contract Documents and final shop drawings.
 - 1. Check and adjust closers to ensure proper operation.
 - 2. Check latchset, lockset, and exit devices are properly installed and adjusted to ensure proper operation.
 - a. Verify levers are free from binding.
 - b. Ensure latchbolts and dead bolts are engaged into strike and hardware is functioning.
 - 3. Report findings, in writing, to architect indicating that all hardware is installed and functioning properly. Include recommendations outlining corrective actions for improperly functioning hardware if required.

3.5 SCHEDULE OF FINISH HARDWARE:

Manufacturer List

<u>Code</u>	<u>Name</u>
AB	ABH Manufacturing Inc.
BE	Best Access Systems
K2	K2 Hardware
PR	Precision
ST	Stanley
TR	Trimco
ZE	Zero

Option List

<u>Code</u>	<u>Description</u>
CD	CYLINDER DOGGING
SN	Sex Nuts (Pkg. of 4)
ALK	ALARM, BATTERY OPERATED
R704	STRAIGHT CYLINDER RING - 1/4"
SEX BOLTS	SEX BOLTS
J MTG	TYPE J MOUNTING

Finish List

<u>Code</u>	<u>Description</u>
AL	Aluminum
626	Satin Chromium Plated
628	Satin Aluminum, Clear Anodized
630	Satin Stainless Steel
689	Aluminum Painted
GREY	Grey
US26D	Chromium Plated, Dull
US32D	Stainless Steel, Dull

Hardware Sets

**SET #1
Door #5**

3 Hinges	FBB179 4 1/2 X 4 1/2 NRP	US26D	ST
1 Exit Device	2403CD x Less Pull	630	PR
1 Rim Cylinder	1E-72 PATD R704	626	BE
1 Mortise Cylinder	1E-74 PATD R704	626	BE
1 Door Pull	7160 x J MTG	630	TR
1 Door Closer	QDC211TJ Slim Cover	689	K2
1 Threshold	566A		ZE

NOTE: Balance of Seals by Alum. Door Mfg.

SET #2**Door # 1 8 9 10**

6 Hinges	FBB179 4 1/2 X 4 1/2 NRP	US26D	ST
2 Flush Bolt	3915 12	626	TR
1 Storeroom Lockset	QCL171 SUM x Cormax Core	626	K2
1 Latch Protector	5000-T	626	TR
2 Overhead Holder	3500 HD	S1	AB
1 Threshold	656A		ZE
1 Weatherstrip	314AA Set@ Head & Jambs		ZE
1 Astragal	41A (Mount Inside In-Active Leaf)		ZE
2 Sweep	8198A	628	ZE

SET #3**Door #14**

3 Hinges	FBB179 4 1/2 X 4 1/2 NRP	US26D	ST
1 Alarm Exit Device	2103 x 1703A ALK	630	PR
1 Rim Cylinder	1E-72 PATD R704	626	BE
1 Mortise Cylinder	1E-74 PATD R704	626	BE
1 Closer	QDC214 FC SNB	689	K2
1 Threshold	65A		ZE
1 Weatherstrip	314AA Set@ Head & Jambs		ZE

SET #4**Door #2 3**

6 Hinges	FBB179 4 1/2 X 4 1/2 NRP	US26D	ST
2 Flush Bolt	3915	626	TR
1 Dustproof Strike	3910	630	TR
1 Classroom Lockset	QCL161 SUM x Cormax Core	626	K2
2 Kickplate	KO050 10" X 1" LDW X B4E X CSK	630	TR
2 Door Silencers	1229A	GREY	TR

SET #5**Door #4 6 7**

3 Hinges	FBB179 4 1/2 X 4 1/2 NRP	US26D	ST
1 Classroom Lockset	QCL161 SUM x Cormax Core	626	K2
1 Closer	QDC311 FC SNB	US32D	K2
1 Kickplate	KO050 10" X 1" LDW X B4E X CSK	630	TR
3 Door Silencers	1229A	GREY	TR

SET #6**Door #12 13**

3 Hinges	FBB179 4 1/2 X 4 1/2	US26D	ST
1 Closer	QDC311 FC SNB	US32D	K2
1 Push Plate	1001-3	630	TR
1 Pull Plate	1015-3	630	TR
1 Kickplate	KO050 10" X 2" LDW X B4E X CSK	630	TR
1 Mop Plate	KM050 4" X 1" LDW X B4E X CSK	630	TR
1 Wall Bumper	1270WV	630	TR
3 Door Silencers	1229A	GREY	TR

END OF SECTION

SECTION 08800

GLAZING

PREFACE

The general provisions of the Contract, including the conditions of the Contract (General, Supplementary and other Conditions) and Division 1, as appropriate, apply to the Work specified in this section.

1.0 SCOPE

1.1 SUMMARY

- A. This Section includes glazing for the following products, including those specified in other Sections where requirements are specified by reference to this Section:
 - 1. Window units.
 - 2. Entrances and other doors.

1.2 DEFINITIONS

- A. Manufacturer is used in this Section to refer to a firm that produces primary glass or fabricated glass as defined in the referenced glazing standard

1.3 SYSTEM PERFORMANCE REQUIREMENTS

- A. General: Provide glazing systems that are produced, fabricated, and installed to withstand normal thermal movement, wind loading, and impact loading (where applicable), without failure including loss or glass breakage attributable to the following: defective manufacture, fabrication, and installation; failure of sealants or gaskets to remain watertight and airtight; deterioration of glazing materials; and other defects in construction.
- B. Glass Design: Glass thickness indicated on Drawings is for detailing only. Conform glass thickness by analyzing Project loads and in-service conditions. Provide glass lites for the various size openings in the thickness and strengths (annealed or heat-treated) to meet or exceed the following criteria.

1. Provide thickness indicated or, if not otherwise indicated, as recommended by glass manufacturer for application indicated.
- C. Normal thermal movement results from the following maximum change range in ambient and surface temperatures acting on glass framing members and glazing components. Base engineering calculation on materials' actual surface temperatures due to both solar heat gain and nighttime sky heat loss.
1. Temperature Change (Range): 120 deg F (67 deg C), ambient; 180 deg F (100 deg C), material surfaces.

1.4 SUBMITTALS

- A. General: Submit the following according to Conditions of Contract and Division 1 Specification Sections.
- B. Product Data for each glass product and glazing material indicated.
- C. Product certificates signed by glazing materials manufacturers certifying that their products comply with specified requirements.
 1. Separate certifications are not required for glazing materials bearing manufacturer's permanent labels designating type and thickness of glass, provided labels represent a quality control program of a recognized certification agency or independent testing agency acceptable to authorities having jurisdiction.
- D. Compatibility and adhesion test reports from sealant manufacturer indicating that glazing materials were tested for compatibility and adhesion with glazing sealants. Include sealant manufacturer's interpretation of test results relative to sealant performance and recommendations for primers and substrate preparation needed for adhesion.
- E. Product test reports for each type of glazing sealant and gasket indicated, evidencing compliance with requirements specified.
- F. Maintenance data for glass and other glazing materials to include in Operating and Maintenance Manual specified in Division 1.

1.5 QUALITY ASSURANCE

- A. Glazing Publications: Comply with published recommendations of glass product manufacturers and organizations below, except where more stringent requirements are indicated. Refer to the publication for glazing terms not otherwise defined in this Section or in referenced standards.

1. FGMA Publications: "FGMA Glazing Manual" and "Sealant Manual."
- B. Safety Glass: Where safety glass is indicated or required by authorities having jurisdiction, provide type of products complying with ANSI Z97.1 and testing requirements of 16 CFR Part 1201 for Category II materials.
- C. Glazier Qualifications: Engage an experienced glazier who has completed glazing similar in material, design, and extent to that indicated for Project with a record of successful in service performance.
- D. Single Source Responsibility for Glass: Obtain glass from one source for each product indicated below:
 1. Primary glass of each (ASTM C 1036) type and class indicated.
 2. Heat-treated glass of each (ASTM c 1048) condition indicated.
- E. Single Source Responsibility for Glazing Accessories: Obtain glazing accessories from one source for each product and installation method indicated.
- F. Testing is not required when glazing sealant manufacturer can submit required preparation data that is acceptable to Architect and is based on previous testing of current sealant products for adhesion to and compatibility with submitted glazing materials.

1.6 DELIVERY, STORAGE, AND HANDLING

- A. Protect glazing materials to comply with manufacturer's directions and as needed to prevent damage to glass and glazing materials from condensation, temperature changes, direct exposure to sun, or other causes.
 1. Where insulating glass units will be exposed to substantial altitude changes, comply with insulating glass fabricator's recommendations for venting and sealing to avoid hermetic seal ruptures.

1.7 PROJECT CONDITIONS

- A. Environmental Conditions: Do not proceed with glazing when ambient and substrate temperature conditions are outside the limits permitted by glazing materials manufacturer or when glazing channel substrates are wet from rain, frost, condensation, or other causes.

1. Install liquid sealants at ambient and substrate temperatures above 40 deg F (4.4 deg C).

2.0 PRODUCTS

2.1 MANUFACTURERS

- A. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products which may be incorporated in the work included; but are not limited to, the following:

1. Prime Glass Manufacturers

AFG Industries, Inc.
Ford Glass Division
Guardian Industries Corp.
LOF Glass, Inc.
PPG Industries, Inc.
Saint-Gobain/ Euroglass

2.2 PRIMARY GLASS PRODUCTS

All exterior glass in storefronts, doors and windows to be insulated, low E. Tempered glass where indicated on schedule and as mandated by the Uniform Building Code . Contractor to provide a sample for architect's approval.

2.3 HEAT TREATED FLOAT GLASS

- A. Uncoated, Clear, Heat Treated Float Glass: ASTM C 1048, Condition A (uncoated surfaces), Type I (transparent glass flat), Class 1 (clear), Quality q3 (glazing select), kind as indicated below.

1. Kind FT (fully tempered) where indicated.

- B. Uncoated, Tinted, Heat Treated Float Glass: ASTM C 1048, Condition A (uncoated surfaces), Type I (transparent glass flat) Class 2 (tinted heat absorbing and light reducing), Quality q3 (glazing select), with grey color; king as indicated below.

1. Kind FT (fully tempered) where indicated.

- C. Available Manufacturers: Subject to compliance with requirement, manufacturers offering heat treated glass products that may be incorporated in the Work include, but are not limited to, the following companies.

AFG Industries, Inc.

Artistic Glass Products Co.
Cardinal IG
Saint-Gobain
Falconer Glass Industries
Glasstemp, Inc.
Guardian Industries Corp.
HGP Industries
PPG Industries, Inc.
Spectrum Glass Products, Inc.
Tempglass
Viracon, Inc.

2.5 MISCELLANEOUS GLAZING MATERIALS

- A. General: Provide products of material, size, and shape complying with referenced glazing standard, requirements of manufacturers of glass and other glazing materials involved for glazing application indicated, and with a proven record of compatibility with surfaces contacted in installation.
- B. Cleaners, Primers and Sealers: Type recommended by sealant or gasket manufacturer.
- C. Setting Blocks: Elastomeric material with a Shore A durometer hardness of 85 plus or minus 5.
- D. Spacers: Elastomeric blocks or continuous extrusions with a Shore A durometer hardness required by glass manufacturer to maintain glass lites in place for installation indicated.
- E. Edge Blocks: Elastomeric material of hardness needed to limit glass lateral movement (side-walking).
- F. Plastic Foam Joint Fillers: Preformed, compressible, resilient, nonstaining, nonextruding, nonoutgassing, strips of closed-cell plastic foam of density, size and shape to control sealant depth and otherwise contribute to produce optimum sealant performance.

3.0 EXECUTION

3.1 EXAMINATION

- A. Examine glass framing with glazier present, for compliance with the following:
 - 1. Manufacturing and installation tolerances, including those for size, squareness, offsets at corners.

2. Presence and functioning a weep system.
 3. Minimum required face or edge clearances.
 4. Effective sealing between joints of glass-framing members.
- B. Do not proceed with glazing until satisfactory conditions have been corrected.

3.2 PREPARATION

- A. Clean glazing channels and other framing members receiving glass immediately before glazing. Remove coatings that are not firmly bonded to substrate.

3.3 GLAZING GENERAL

- A. Comply with combined recommendations of manufacturers of glass, sealants, gaskets, and other glazing materials, except where more stringent requirements are indicated, including those in referenced glazing publications.
- B. Glazing channel dimensions as indicated on Drawings provide necessary bite on glass, minimum edge and face clearances, and adequate sealant thickness, with reasonable tolerances. Adjust as required by Project conditions during installation.
- C. Protect glass from edge damage during handling and installation as follows:
1. Use rolling block in rotating glass units to prevent damage to glass corners. Do not impact glass with metal framing. Use suction cups to shift glass units within openings; do not raise or drift glass with a pry bar. Rotate glass lites with flares or bevels on bottom horizontal edges so edges so edges are located at top of opening, unless otherwise indicated by manufacturer's label.
 2. Remove damaged glass from Project site and legally dispose of off site. Damaged glass is glass with edge damage or other imperfections that, when installed, weaken glass and impair performance and appearance.
- D. Apply primers to joint surfaces where required for adhesion of sealants, as determined by pre-construction sealant-substrate testing.
- E. Install elastomeric-setting blocks in sill rabbets, sized and located to comply with reference glazing standard, unless otherwise required by glass manufacturer. Set blocks in thin course of compatible sealant suitable for heel bead.

- F. Do not exceed edge pressures stipulated by glass manufacturers for installing glass lites.
- G. Provide spacers for glass sizes larger than 50 united inches (length plus height) as follows:
 - 1. Locate spacers inside, outside, and directly opposite each other. Install correct size and spacing to preserve required face clearances, except where gaskets and glazing tapes are used that have demonstrated ability to maintain required face clearances and comply with system performance requirements.
 - 2. Provide 1/8" inch minimum bite of spacers on glass and use thickness equal to sealant width. With glazing tape, use thickness slightly less than final compressed thickness of tape.
- H. Provide edge blocking to comply with requirements of referenced glazing publications, unless otherwise required by glass manufacturer.
- I. Set glass lites in each series with uniform pattern, draw, bow, and similar characteristics.

3.4 TAPE GLAZING

- A. Position tapes on fixed stops so that when compressed by glass their exposed edges are flush with or protrude slightly above sightline of stops.
- B. Install tapes continuously but not in one continuous length. Do not stretch tapes to make them fit opening.
- C. Where framing joints are vertical, cover these joints by applying tapes to heads and sills first and then to jambs. Where framing joints are horizontal, cover these joints by applying tapes to jambs and then to heads and sills.
- D. Place joints in tapes at corners of opening with adjoining lengths butted together, not lapped. Seal joints in tapes with compatible sealant approved by tape manufacturer.
- E. Do not remove release paper from tape until just before each lite is installed.

3.5 SEALANT GLAZING (WET)

- A. Provide compressible filler rods or equivalent back-up material, as recommended by sealant and glass manufacturers, to prevent sealant from extruding into glass channel weep systems and from adhering to joints back surface as well as to control depth of sealant for optimum performance, unless otherwise indicated.

- B. Force sealants into glazing channels to eliminate voids and to ensure complete wetting or bond of sealant to glass and channel surfaces.
- C. Tool exposed surfaces of sealants to provide a substantial wash away from glass. Install pressurized gaskets to protrude slightly out of channel to eliminate dirt and moisture pockets.
- D. Where wedge-shaped gaskets are driven into one side of channel to pressurize sealant or gasket on opposite side, provide adequate anchorage to ensure that gasket will not "walk" out when installations subjected to movement.
- E. Miter cut wedge shaped gaskets at corners and install gaskets in manner recommended by gasket manufacturer to prevent pull away at corners; seal corner joints and butt joints with sealant recommended by gasket manufacturer.

3.6 PROTECTION AND CLEANING

- A. Protect exterior glass from breakage immediately after installation by attaching crossed streamers to framing held away from glass. Do not apply markers to glass surface. Remove nonpermanent labels and clean surfaces.
- B. Protect glass from contact with contaminating substances resulting from construction operations including weld spatter. If, despite such protection, contaminating substances do come into contact with glass, remove them immediately as recommended by glass manufacturer.
- C. Examine glass surfaces adjacent to or below exterior concrete and other masonry surfaces at frequent intervals during construction, but not less than

once a month, for build-up of dirt scum, alkali deposits, or stains, and remove as recommended by glass manufacturer.
- D. Remove and replace glass that is broken, chipped, cracked, abraded, or damaged in any way, including natural causes, accidents and vandalism, during construction period.
- E. Wash glass on both faces in each area of Project not more than 4 days prior to date scheduled for inspections that establish date of Substantial Completion. Wash glass as recommended by glass manufacturer.

END OF SECTION

SECTION 09250
GYPSUM DRYWALL

PREFACE

The general provisions of the Contract, including the Conditions of the Contract (General, Supplementary and other Conditions) and Division 1 as appropriate, apply to the Work specified in this Section.

1.0 SCOPE

- 1.1 This Section includes all work required to complete the Gypsum Drywall indicated on the Drawings and all supplementary items necessary for its proper installation. This work includes:
- A. Gypsum drywall including screw-type metal support system.
 - B. Drywall finishing (joint tape and compound treatment)
 - C. Metal stud wall framing.
- 1.2 Related Sections:
- A. Section 06200 - Finish Carpentry.
 - B. Section 09900 - Painting.
- 1.3 References:
- A. ANSI/ASTM C36 - Gypsum Wallboard
 - B. ANSI/ASTM C475 - Joint Treatment Materials for Gypsum Wallboard Construction.
 - C. ANSI/ASTM C645 - Non-Load (Axial) Bearing Steel Studs, Runners (Track), and Rigid Furring Channels for Screw Application of Gypsum Board.
 - D. ANSI/ASTM C646 - Steel Drill Screws for the Application of Gypsum Sheet Material to Light Gage Steel Studs.
 - E. ANSI/ASTM C754 - Installation of Framing Members to Receive Screw Attached Gypsum Wallboard, or Water Resistant Backing Board.
 - F. ANSI/ASTM E119 - Fire Tests of Building Construction and Materials.
 - G. GA-201 - Gypsum Board for Walls and Ceilings.
 - H. GA-216 - Recommended Specifications for the Application and Finishing of Gypsum Board.
- 1.4 Quality Assurance:
- A. Fire-Resistance Rating: Where gypsum drywall is indicated on drawings,

provide fire-resistive gypsum drywall. Provide materials and installations which are identical with those of applicable assemblies tested per ASTM

E119 by fire testing laboratories acceptable to authorities having jurisdiction. Conform to applicable code for fire rated assemblies.

- B. Gypsum Board Terminology Standard: GA-505 Association.
- C. Single-Source Responsibility: Obtain gypsum board products from a single manufacturer, or from manufacturers recommended by the prime manufacturer of gypsum boards.
- D. Applicator shall be a company specializing in Gypsum Board systems.

1.5 Delivery, Storage and Handling:

- A. Deliver materials in original packages, containers or bundles bearing brand name and identification of manufacturer or supplier.
- B. Store materials inside under cover and in a manner to keep them dry, protected from weather, direct sunlight, surface contamination, corrosion and damage from construction traffic and other causes. Neatly stack gypsum boards flat to prevent sagging.
- C. Handle gypsum boards to prevent damage to edges, ends or surfaces. Protect metal corner beads and trim from being bent or damaged.
- D. Light gage metal components such as steel studs and runners, furring channels and resilient channels should be given adequate protection in the warehouse and on the job site against rusting caused by moisture.

1.6 Submittals: Provide product data on metal furring, gypsum board, joint tape and other accessory elements of wall board systems.

1.7 Project Conditions:

- A. Comply with requirements of referenced gypsum board application standards and recommendations of gypsum board manufacturer, for environmental conditions before, during and after application of gypsum board.
- B. Ventilate building spaces as required to remove water in excess of that required for drying of joint treatment material immediately after its application. Avoid drafts during dry, hot weather to prevent too rapid drying.

2.0 MATERIALS

2.1 Acceptable Manufacturers:

- A. Subject to compliance with requirements, manufacturers offering products

which may be incorporated in the work includes, but is not limited to, the following:

1. American Gypsum Co.
2. Georgia-Pacific Corp.
3. Gold Bond Building Products Div., National Gypsum Co.
4. United States Gypsum Co.

2.2 Gypsum Board:

- A. Gypsum Wallboard: ANSI/ASTM C36, of types, edge configuration and thickness indicated below; in maximum lengths available to minimize end-to-end butt joints. Refer to Drawings for application.

1. 5/8-inch gypsum wallboard with tapered edges.

- B. Trim Accessories: Provide manufacturer's standard trim accessories of types indicated for drywall work, formed of galvanized steel unless otherwise indicated, with either knurled and perforated or expanded flanges for nailing or stapling, and beaded for concealment of flanges in joint compound. Provide corner beads (WSG # 103), L-type edge trim-beads (USG # 200-13 series), U-type edge trim-beads, and one piece control joint beads.

- C. Joint Treatment Materials: ANSI/ASTM C475; reinforcing tape, joint compound and adhesive type recommended by the manufacturer for the application indicated.

- D. Miscellaneous Materials: Provide auxiliary materials for gypsum drywall work of the type and grade recommended by the manufacturer of the gypsum board.

1. Gypsum Board Screws: Comply with ASTM C646.

- E. Texture Finish Materials:

1. Primer: Of type recommended by manufacturer.
2. Finish: Full Float Finish

- F. Wall Framing and Ceiling: Partitions shall be framed with steel studs. All studs shall be of size as required for partition thickness shown and shall be spaced not more than 16 inches on center at exterior and fire rated assembly walls and 16 inches on center at all other walls if not otherwise noted.

1. Studs shall be positioned plumb in runners and securely attached top and bottom with not less than one screw on each side of stud ends. Studs shall be in continuous lengths. Types shall be as follows and as shown on drawings.
 - a. Metal Studs: 3-5/8 & 6" inches wide, 20 gauge at interior walls unless otherwise indicated.
2. Floor runners shall be accurately aligned and securely fastened to floor with expansion shields or suitable power-activated fasteners. Ceiling runners and floor runners shall be in long lengths with butted joints. Types shall be as follows and as shown on drawings:
 - a. C-Shaped runners: Same gauge as studs
3. Wall Openings: Steel frames shall be securely attached by anchors to the nearest stud each side of opening with wall-board screws or double strands of tie wire. A ceiling runner channel section will be cut 24 inches longer than the rough opening width and shall be installed horizontally over each opening and runner ends shall be bent, nested and attached to adjacent studs with screws.

3.0 EXECUTION

3.1 General Gypsum Board Installation Requirements:

- A. Gypsum Board Application and Finishing Standards: ASTM C840 and GA216.
- B. Locate exposed end-butt joints as far from center of wall and ceilings as possible, and stagger not less than 1'-0" in alternate courses of board.
- C. Install exposed gypsum board with face side out. Do not install imperfect, damaged or damp boards. Butt boards together for a light contact at edges and ends with not more than 1/16 inch open space between boards. Do not force into place.
- D. Locate either edge or end joints over supports, except in horizontal applications or where intermediate supports or gypsum board back-blocking is provided behind end joints. Position boards so that like edges abut tapered edges against tapered edges and mill-cut or field-cut ends against mill-cut or field-cut ends. Do not place tapered edges against cut edges or ends. Stagger vertical joints over different studs on opposite sides of partition.
- E. Attach gypsum board to supplementary framing and blocking provided for

additional support at openings and cutouts.

- F. Form control joints and expansion joints with space between edges of boards, prepared to receive trim accessories.
- G. Space fasteners in gypsum boards in accordance with referenced standards and manufacturer's recommendations, except as otherwise indicated.

3.2 Methods of Gypsum Drywall Application:

- A. Single-Layer Fastening Methods: Apply gypsum boards to supports as follows:
 1. Position all ends and edges of all gypsum panels over framing members, except when joints are at right angles to framing members as in perpendicular application or when end joints are back blocked.
 2. When applicable apply gypsum panels first to the ceiling and then to the walls. Extend ceiling board into corners and make firm contact with top plate. To minimize end joints use panels of maximum practical lengths. Fit ends and edges closely, but not forced together. Stagger end joints in successive courses with joints on opposite sides of a partition placed on different studs.
 3. Attach panels to framing supports by power driven screws. Space fasteners not less than 3/8-inch from edges and ends of panel and drive as recommended for specified fastening method. Drive fasteners in field of panels first, working toward ends and edges. Hold panel in firm contact with framing while driving fasteners. Drive fastener heads slightly below surface of gypsum panels in a uniform dimple without breaking face paper.
 4. Cut ends, edges & scribe or make cutouts within field of panels in a workmanlike manner.
 5. Install trim at all internal and external angles formed by the intersection of either panel surfaces or other surfaces. Apply corner bead to all vertical or horizontal external corners in accordance with manufacturer directions.

3.3 Installation of Drywall Trim Accessories: Where feasible, use the same fasteners to anchor trim accessory flanges as required to fasten flanges by nailing or stapling in accordance with manufacturer's instructions and recommendations.

- A. Install metal corner beads at external corners of dry wall work.
- B. Install metal edge trim whenever edge of gypsum board would otherwise be

exposed or semi-exposed, and except where plastic trim is indicated. Provide type with face flange to receive joint compound except where semi-finishing type is indicated.

- B. Install L-type trim where work is tightly abutted to other work, and install special kerf-type where other work is kerfed to receive long leg of L-type

trim. Install U-type trim where edge is exposed, revealed, gasketed or sealant-filled (including expansion joints).

- D. Install metal control joint (beaded-type) where indicated.

- 3.4 Finishing Drywall: Apply treatment at gypsum board joints (both directions), flanges of trim accessories, penetrations, fastener heads, surface defects and elsewhere as required to prepare work for decoration.

- A. Apply joint tape at joints between gypsum boards, except where trim accessories are indicated.

- B. Apply joint compound in three coats (not including prefill of openings in base), and sand between last two coats and after last coat.

- 3.5 Application of Texture Finish: **FULL FLOAT FINISH**

- A. Surface Preparation and Primer: Prepare and prime dry wall and other surfaces in strict accordance with texture finish manufacturer's instructions. Apply primer to all surfaces to achieve texture finish.

- B. Finish Application: Mix and apply finish to drywall and other surfaces indicated to receive finish in strict accordance with manufacturer's instructions to produce a uniform texture without starved spots or other evidence of thin application, and free of application patterns.

- C. Remove any texture droppings or over spray from door frames, windows and other adjoining work.

- 3.6 Protection of Work:

- A. Provide final protection and maintain conditions, in a manner suitable to Installer, which ensures gypsum drywall work being done without damage or deterioration at time of substantial completion.

END OF SECTION

SECTION 09300

TILE

PREFACE

The general provisions of the Contract, including the Conditions of the Contract (General, Supplementary and other Conditions) and Division 1 as appropriate, apply to the Work specified in this Section.

1.0 SCOPE

- 1.1 This Section includes: Floor and wall tile as noted on the plans.

2.0 MATERIALS

- 2.1 **Ceramic tile at Toilet Room Walls and Base:** 4" x 4" as shown and noted on drawings. Provide linear rope trim cap at Top of 48" wainscot wall.
Dal-Tile or equal. See allowances
- 2.2 Grout: Commercial, unsanded Portland Cement type, Upco Hydroment or equal.
- 2.3 Standard tile color and grout selection by architect upon submittal of samples
- 2.4 **Porcelain Tile at Toilet Room Floors:** 12" x 12" with minimum joint width.

Consult architect for color See allowances

3.0 EXECUTION

3.1 Ceramic

- .1 Install ceramic tile as called for in this specification and as directed by the manufacturer.
- .2 Tile shall be set in Portland Cement mortar.
- .3 Tile shall be firmly in place with finished surfaces in true planes. Joints shall be straight, uniform in width and solidly filled. Completed work shall be free from hollow sounding areas and loose, cracked or defective tile.
- .4 Tile work shall be laid out so that no tiles less than one half of full tile shall occur.

END OF SECTION

SECTION 09680 – CARPET TILES

PREFACE

The general provisions of the Contract, including the Conditions of the Contract (General, Supplementary and other Conditions) and Division 1 as appropriate, apply to the Work specified in this Section.

1.0 SCOPE

- 1.1 This Section covers the furnishings and installation of carpet tiles, reducer strips and accessories required to properly install carpeting complete, including all labor, materials, equipment and incidentals necessary and required for their completion.
- 1.2 All carpet shall be delivered to the job site in original containers. Store under cover in well ventilated spaces as soon as delivered; protect from dirt, damage, stains and moisture.
- 1.3 Surfaces to receive carpet shall be thoroughly clean, dry and in condition satisfactory to carpet installer. Residual material remaining on concrete floor left from the removal of previous carpet will need to be removed in its entirety. Moisture conditions of surface should be considered in order to determine whether adhesive used will supply bond between backing and floor.

2.0 MATERIALS

- 2.1 Carpet Tiles manufactured by: Milliken Contract or approved equal
 - A: Style Name : Southern Analog Collection
 - B. Style Number: Panoramic & Viewfinder
 - C. Color Number: TBS
 - D. Stain Resist: Stain Smart
 - E. Antimicrobial: Alpha - San Built-In Protection
 - F. Construction: Tufted, Textured Loop
 - G. Warranty: Lifetime Commercial Limited
 - H. Adhesive: TractionBack
 - I. Installation Method: Quarter Turn - 50 cm x 50 cm carpet tile
- 2.2 Accessories: Leveling compound: Self underlayment concrete model K-15 as manufactured by Ardex Engineered Cements, Inc. Use at uneven or damaged concrete slabs.
- 2.3 Sub-floor Filler: White premix latex, type recommended by flooring manufacturer
- 2.4 Primers and adhesives: Waterproof of types recommended by carpet manufacturer
- 2.5 Flame spread & Smoke density as per city requirements

Contractor to submit samples for approval

3.0 EXECUTION

- 3.1 WORKMANSHIP: Carpet installation must be done by men skilled in this trade.
- 3.2 Carpet remnants and usable scraps shall be packaged, identified and delivered to the Owner as the Owner's property. Color as selected by Owner.
- 3.3 After installation is complete, clean up all dirt and debris. Clean carpet of all spots with proper spot remover. The entire installation shall be left clean and in an approved condition.

END OF SECTION

SECTION 09900

PAINTING

PREFACE

The general provisions of the Contract, including the Conditions of the Contract (General, Supplementary and other Conditions) and Division 1 as appropriate, apply to the Work specified in this Section.

1.0 SCOPE

- 1.1 This Section covers the labor, materials, and equipment required for painting and proper finishing of:
- Interior Painting:** Gyp board walls and ceilings where they occur, wood base, steel doors and frames, exposed steel framing (columns, cross bracing, beams, attachments, angles, etc.).
 - Interior Clear Sealing of Wood:** All Maple doors, cabinets, and interior walls where Maple occurs.
 - Exterior Painting:** Steel columns and framework.

2.0 MATERIALS

- 2.1 Where materials are specified by name, only those materials are to be used, unless the expression "or approved equal" is included in the Specifications in which case any substitution required the Architect's approval and his decision is final.
- 2.2 In general, manufacturer's names and trade names are not included in these Specifications. It is intended that only the best quality of material prepared by the manufacturer to be used in each individual case to best suit the surfaces to be covered. Materials: equal in quality to the best materials as manufactured by Benjamin Moore, DeVoe, Dupont, Pratt & Lambert, Coronado, Pittsburgh, Sherwin Williams, or Glidden. Only products of recognized standard manufacturers will be considered.
- 2.3 The number of coats specified herein is to be considered as the minimum number of coats required, and it shall be the responsibility of the Contractor for this Section of the Work to apply materials of proper type and in sufficient quantities and coats to properly cover the surface and obtain a first quality finished surface on each of the surfaces treated.

3.0 EXECUTION

3.1 Precautions:

- .1 Provide for ventilating and drying in spaces in which painting is to be accomplished.
- .2 Do not apply paint under conditions that could adversely affect finish. Do not apply paint when surrounding temperature is below 50 degrees F. or when excessive humidity is present.
- .3 Protect painted surfaces from exposure to direct rays of sun until surface is sufficiently dry to prevent damage.

3.2 Preparation of Wood:

- .1 Woodwork to be painted or finished shall be in condition before coating; surfaces being clean, smooth and dry.
- .2 Woodwork to be painted shall have all knots and pitch streaks shellacked two (2) coats before priming is applied.

3.3 Mixing and Colors:

- .1 Apply paint at the consistency recommended by the Manufacturer. Additional thinning permitted only with specific approval.
- .2 Use factory mixed colors, shades and tints except as indicated. Job mixing permitted only with specific approval.
- .3 Match approved color chips or approved samples. Do not proceed with finish painting until samples have been approved.
- .4 The Owner and Architect will select colors for all areas.
- .5 The painting sub-contractor, before starting work, shall prepare and submit for the Architect's approval, a complete schedule of all makes and names of paint materials proposed for each particular use. Once approved, no change shall be made from the schedule.

3.4 Application:

- .1 Apply painting materials according to manufacturer's instructions and recommendations. Spread or flow materials to produce a finish free from runs, sags, or thin spots.

- .3 Do not apply a coat over another coat until the preceding one has thoroughly dried. Do not apply additional coats until previous coat has been approved. Do not apply finish over surfaces containing excessive moisture.
- .4 Tint priming coats to approximate shade of finish. Use first coat lighter than second coat.
- .5 Make edges of paint sharp, clean and straight. Prevent overlapping of colors.
- .6 All surfaces to be painted will be inspected after being prepared and after being finished, and in each case will be subject to the review of the Architect. Any unsatisfactory work shall be put in the proper condition and where necessary the finish paint shall be removed and the surface refinished. A first-class job of painting and finishing in all particulars will be required.

3.5 Paint Finishes: Sherwin Williams or approved equal

Interior Painting Schedule:

- .1 Gypsum Board: Sherwin Williams

Prime Coat:	PrepRite Classic Interior Latex Primer
Intermediate:	SuperPaint Interior Latex Satin
Finish Coat:	SuperPaint Interior Latex Satin
- .2 Hollow Metal Doors and Frames (where indicated):

Prime Coat:	Kem Kromik Universal Metal Primer VOC
Intermediate:	Pro Industrial Urethane Alkyd Enamel Semi Gloss
Finish Coat:	Pro Industrial Urethane Alkyd Enamel Semi Gloss
- .3 Wood Trim, cabinets, doors, wood at wall (where shown as clear or natural finish):

Prime Coat:	WoodClassics Interior Oil clear finish
Intermediate Coat:	WoodClassics Int. Alkyd FD Sanding Sealer
Finish Coat:	Oil Base H.R. Satin
- .5 Interior Steel -where shown/Steel unless indicated to be galvanized:

Prime Coat:	Kem Kromik Universal Metal Primer VOC
Intermediate Coat:	Industrial Enamel

Finish Coat: Industrial Enamel

.6 Wood Trim (where shown to be painted):

Prime Coat: PrepRite Wall and Wood Alkyd Primer

Intermediate Coat: ProClassic Interior Alkyd Semi Gloss

Finish Coat: ProClassic Interior Alkyd Semi Gloss

Exterior Painting Schedule :

.1 Exterior Steel unless indicated to be galvanized:

Prime Coat: Kem Kromik Universal Metal Primer VOC

Intermediate Coat: Pro Industrial Urethane Alkyd Enamel

Finish Coat: Pro Industrial Urethane Alkyd Enamel

3.6 Miscellaneous Mechanical Equipment at Interior: To be left without paint and in its natural Finished condition.

3.7 Cleaning

.1 Protect adjacent surroundings and surfaces from dropped, spattered and spilled paint.

.2 Remove soil, stain and extraneous materials, caused by painting work from adjacent surfaces.

.3 Remove and replace items and materials that cannot be satisfactorily cleaned.

.4 Clean and finish painted surfaces as recommended by manufacturers of materials.

END OF SECTION

SECTION 10160

TOILET PARTITIONS

PREFACE

The general provisions of the Contract, including the Conditions of the Contract (General, Supplementary and other Conditions) and Division 1 as appropriate, apply to the Work specified in this Section.

1.0 SCOPE

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division 1 Specifications Sections, apply to this Section.

1.2 SUMMARY

- A. Extent of toilet partitions is indicated on drawings.
- B. Types of toilet compartments include:
 - 1. Plastic laminate finish.
- C. Toilet accessories, such as toilet paper holders, grab bars, purse shelves, are specified elsewhere in Division 10.

1.3 SUBMITTALS

- A. Product Data: Submit manufacturer's detailed technical data for materials fabrication, and installation, including catalog cuts of anchors, hardware, fastenings, and accessories.
- B. Shop Drawings: Submit shop drawings for fabrication and erection of toilet partition assemblies not fully described by product drawings, templates, and instructions for installation of anchorage devices built into other work.
- C. Samples: Submit full range of color samples for each type of unit required. Submit 6" square samples of each color and finish on same substrate to be used in work, for color verification after selections have been made.

1.4 QUALITY ASSURANCE

- A. Field Measurements: Take field measurements prior to preparation of shop drawings and fabrication where possible, to ensure proper fitting of work. However, allow for adjustments within specified tolerances whenever taking of field measurements before fabrication might delay work.
- B. Coordination: Furnish inserts and anchorages which must be built into other work for installation of toilet partitions and related work: coordinate delivery with other work to avoid delay.

2.0 PRODUCTS

2.1 MANUFACTURERS

- A. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products which may be incorporated in the work include, but are not limited to, the following:

All American Metal Corp.
American Sanitary Partition Corp.
Ampco Products Inc.
Bobrick Washroom Equipment, Inc.
Columbia Partitions, Inc.
Flush-Metal Partition Corp.
Global Steel Products Corp. Knickerbocker Partition Corp.
Metpar Steel Products Corp.
Monarch Toilet Partition, Inc.
Santana Products Co.
Sanymetal Products Co.

2.2 MATERIALS

- A. General: Provide materials which have been selected for surface flatness and smoothness. Exposed surfaces which exhibit pitting, seam marks, roller marks, stains, discolorations, telegraphing of core material, or other imperfections on finished units are not acceptable.
- B. Plastic Laminate: NEMA Std. LD-3, minimum 0.050" thick, color and pattern as indicated or if not indicated, as selected by Architect from manufacturer's standards.
- C. Core Material for Plastic Laminate: Manufacturer's standard particleboard, in thickness to provide nominal dimension of 1" minimum for all components.
- D. Pilaster Shoes: ASTM A 167, Type 302/304 stainless steel, not less than 3" high, 20 gage, finished to match hardware.

- E. Stirrup Brackets: Manufacturer's standard design for attaching panels to walls and pilasters, either chromium-plated non ferrous cast alloy ("Zamac")
- F. Hardware and Accessories: Manufacturer's standard exposed fasteners of stainless steel, chromium-plated steel, or brass finished to match hardware, with theft resistant type heads and nuts. For concealed anchors, use hot dip galvanized cadmium plated, or other rust resistant protective coated steel.

2.3 FABRICATION

- A. General: Furnish standard doors, panels, screens, and pilasters fabricated for partition system unless otherwise indicated. Furnish units with cutouts, drilled holes, and internal reinforcement to receive partition mounted hardware, accessories, and grab bars, as indicated.
- B. Door Dimensions: Unless otherwise indicated, furnish 24" wide inswinging doors for ordinary toilet stalls and 32" wide (clear opening) outswinging doors at stalls equipped for use by handicapped.
- C. Plastic Laminate Partitions and Screens:
- D. General: Pressure laminate one piece face sheets to core material with no splices or joints, and with edges straight and sealed. Seal exposed core material at cutouts to protect against moisture.
- E. Overhead Braced Partitions: Furnish galvanized steel supports and leveling bolts at pilasters recommended by manufacturer to suit floor conditions. Make provisions for setting and securing continuous extruded aluminum anti-grip overhead bracing at top of each pilaster. Furnish shoe at each pilaster to conceal supports and leveling mechanism.
 - 1. Hinges: Cutout inset type, adjustable to hold door open at any angle up to 90 degrees. Provide gravity type, spring-action cam type, or concealed torsion rod type, to suit manufacturer's standards.
 - 2. Latch and Keeper: Recessed latch unit, designed for emergency access, with combination rubber-faced door strike and keeper.
 - 3. Latch and Keeper: Manufacturer's standard surface-mounted latch unit, designed for emergency access, with combination rubber faced door strike and keeper.
 - 4. Coat Hook: Manufacturer's standard unit, combination hook and rubber tipped bumper, sized to prevent door hitting mounted accessories.

5. Door Pull: Manufacturer's standard unit for out swing door.

3.0 EXECUTION

3.1 INSTALLATION

- A. General: Comply with manufacturer's recommended procedures and installation sequence. Install partitions rigid, straight, plumb and level. Provide clearances of not more than 1/2" between pilasters and panels, and not more than 1" between panels and walls. Secure panels to walls with not less than two stirrup brackets attached near top and bottom of panel. Locate wall brackets so that holes for wall anchorages occur in masonry or tile joints. Secure panels to pilasters with not less than two stirrups brackets located to align with stirrup brackets located to align with stirrup brackets at wall. Secure panels in position with manufacturer's recommended anchoring devices.
- B. Overhead Braced Partitions: Secure pilasters to floor, and level, plumb and tighten installation with devices furnished. Secure overhead brace to each pilaster with not less than two fasteners. Hang doors and adjust so that tops of doors are parallel with overhead brace when doors are in closed position.
- C. Screens: attach with concealed anchoring devices, as recommended by manufacturer to suit supporting structure. Set units to provide support and to resist lateral impact.
- D. Accessories: Mount accessories to partition units in accordance with manufacturer's instructions.

3.2 ADJUST AND CLEAN

- A. Hardware Adjustment: Adjust and lubricate hardware for proper operation. Set hinges on inswinging doors to hold open approximately 30 degrees from closed position when unlatched. Set hinges on outswinging doors (and entrance swing doors) to return to fully closed position.
- B. Clean exposed surfaces of partition systems using materials and methods recommended by manufacturer, and provide protection as necessary to prevent damage during remainder of construction period.

END OF SECTION

SECTION 10520

FIRE EXTINGUISHERS, CABINETS AND ACCESSORIES

PREFACE

The general provisions of the Contract, including the Conditions of the Contract (General, Supplementary and other Conditions) and Division 1 as appropriate, apply to the Work specified in this Section.

1.0 SCOPE

- 1.1 This Section includes all labor, material, services, equipment and appliances required for the complete installation of:

Fire extinguishers (see plan for locations). Noted by "FEC" on the drawings.
Cabinets
Accessories

- 1.2 Submittals: Provide product data on extinguisher cabinet dimensions, operational features, color and finish, anchorage details and rough-in requirements.

2.0 MATERIALS

- 2.1 Manufacturer: Larson's Manufacturing Company
- 2.2 Cabinets: Larson's Architectural Series or approved equal, wire glass door style, Model No. 2712-R, fully recessed with 5/16" flat trim. Primed and painted white with red decal "Fire Extinguisher".
- 2.3 Fire Extinguishers: Model MP10, 10 lb. Capacity suitable for Type A, B and C fires. Provide extinguishers fully charged as indicated on drawings.
- 2.4 Accessories: Fire department lock box 4" x 6" x 1-1/2"

3.0 EXECUTION

- 3.1 Examination: Verify rough openings for cabinet are correctly sized and located.
- 3.2 Installation: Install in accordance with manufacturer's instructions. Install cabinets plumb and level in wall openings, 40" from finished floor to top of door handle. Secure rigidly in place.

END OF SECTION

SECTION 13121 - METAL BUILDING SYSTEMS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes metal building systems that consist of integrated sets of mutually dependent components including structural framing and accessories.
- B. Related Sections include the following:
 - 1. Division 3 Section "Cast-in-Place Concrete" for concrete foundations, slabs, and anchor-bolt installation.
 - 2. Division 7 Section "Building Insulation" for insulation installed in roof and wall panel assemblies.
 - 3. Division 7 Section "Sheet Metal Roofing" for factory-formed metal roof panels.
 - 4. Division 8 Section "Steel Doors and Frames".
 - 5. Division 8 Section "Sectional Overhead Doors."
 - 6. Division 8 Section "Aluminum Windows."
 - 7. Division 8 Section "Door Hardware".
 - 8. Division 9 Section "Gypsum Board Assemblies" for installing gypsum board as part of metal panel assemblies.
 - 9. Division 9 painting Sections for finish painting of shop-primed structural framing.
 - 10. Division 10 Section "Louvers and Vents" for metal louvers.

1.3 DEFINITIONS

- A. Bay: Dimension between main frames measured normal to frame (at centerline of frame) for interior bays, and dimension from centerline of first interior main frame measured normal to end wall (outside face of end-wall girt) for end bays.

- B. Building Length: Dimension of the building measured perpendicular to main framing from end wall to end wall (outside face of girt to outside face of girt).
- C. Building Width: Dimension of the building measured parallel to main framing from sidewall to sidewall (outside face of girt to outside face of girt).
- D. Clear Span: Distance between supports of beams, girders, or trusses (measured from lowest level of connecting area of a column and a rafter frame or knee).
- E. Eave Height: Vertical dimension from finished floor to eave (the line along the sidewall formed by intersection of the planes of the roof and wall).
- F. Clear Height under Structure: Vertical dimension from finished floor to lowest point of any part of primary or secondary structure, not including crane supports, located within clear span.
- G. Terminology Standard: Refer to MBMA's "Metal Building Systems Manual" for definitions of terms for metal building system construction not otherwise defined in this Section or in referenced standards.

1.4 SYSTEM DESCRIPTION

- A. General: Provide a complete, integrated set of mutually dependent components and assemblies that form a metal building system capable of withstanding structural and other loads, thermally induced movement, and exposure to weather without failure or infiltration of water into building interior. Include primary and secondary framing and accessories complying with requirements indicated.
 - 1. Provide metal building system of size and with spacings, slopes, and spans indicated.
- B. Primary Frame Type:
 - 1. Rigid Clear Span: Solid-member, structural-framing system without interior columns
 - 2. Lean To: Solid- or truss-member, structural-framing system without interior columns, designed to be partially supported by another structure.

- C. End-Wall Framing: Manufacturer's standard, for buildings not required to be expandable, consisting of primary frame, capable of supporting one-half of a bay design load, and end-wall columns
- D. Secondary Frame Type: Manufacturer's standard purlins and joists and girts.
- E. Eave Height: refer to drawings.
- F. Bay Spacing: refer to drawings.
- G. Roof Slope: Refer to drawings.

1.5 SYSTEM PERFORMANCE REQUIREMENTS

- A. Structural Performance: Provide metal building systems capable of withstanding the effects of gravity loads and the following loads and stresses within limits and under conditions indicated:
 - 1. Engineer metal building systems according to procedures in MBMA's "Metal Building Systems Manual."
 - 2. Design Loads: As indicated.
 - 3. Live Loads: Include vertical loads induced by the building occupancy indicated on Drawings. Include loads induced by maintenance workers, materials, and equipment for roof live loads.
 - a. Building Occupancy: As indicated on Drawings.
 - 4. Roof Snow Loads: Refer to Drawings.
 - 5. Wind Loads: Refer to Drawings.
 - 6. Collateral Loads: Include additional dead loads other than the weight of metal building system for permanent items such as sprinklers, mechanical systems, electrical systems, and ceilings.
 - 7. Auxiliary Loads: Include dynamic live loads, such as those generated by cranes and materials-handling equipment indicated on Drawings.
 - 8. Load Combinations: Design metal building systems to withstand the most critical effects of load factors and load combinations as required.
 - 9. Deflection Limits: Engineer assemblies to withstand design live loads with deflections no greater than the following:
 - a. Purlins and Rafters: Vertical deflection of **1/240** of the span.
 - b. Girts: Horizontal deflection of **1/240** of the span. At areas to receive cement plaster wall finish, limit deflection to **1/360** of the span.

10. Design secondary framing system to accommodate deflection of primary building structure and construction tolerances, and to maintain clearances at openings.

B. Seismic Performance: Design and engineer metal building systems capable of withstanding the effects of earthquake motions determined according to ASCE 7, "Minimum Design Loads for Buildings and Other Structures": Section 9, "Earthquake Loads."

1.6 SUBMITTALS

A. Product Data: Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for each type of the following metal building system components:

1. Structural-framing system.
2. Accessories.

B. Shop Drawings: For the following metal building system components. Include plans, elevations, sections, details, and attachments to other work.

1. For installed products indicated to comply with design loads, include structural analysis data signed and sealed by the qualified professional engineer responsible for their preparation.
2. Anchor-Bolt Plans: Submit anchor-bolt plans before foundation work begins. Include location, diameter, and projection of anchor bolts required to attach metal building to foundation. Indicate column reactions at each location.
3. Structural-Framing Drawings: Show complete fabrication of primary and secondary framing; include provisions for openings. Indicate welds and bolted connections, distinguishing between shop and field applications. Include transverse cross-sections.

a. Show provisions for attaching **roof curbs and pipe racks**.

4. Accessory Drawings: Include details of the following items, at a scale of not less than 1-1/2 inches per 12 inches (1:8).

- a. Flashing and trim.
- b. Gutters.
- c. Downspouts.

- d. Roof ventilators.
 - e. Louvers.
 - f. Service walkways.
- C. Samples for Initial Selection: For each type of building component with factory-applied color finish.
- D. Samples for Verification: For each type of exposed finish required, prepared on Samples of sizes indicated below.
- 1. Flashing and Trim: Nominal 12 inches (300 mm) long. Include fasteners and other exposed accessories.
 - 2. Accessories: Nominal 12-inch- (300-mm-) long Samples for each type of accessory.
- E. Product Certificates: For each type of metal building system, signed by product manufacturer.
- 1. Letter of Design Certification: Signed and sealed by a qualified professional engineer. Include the following:
 - a. Name and location of Project.
 - b. Order number.
 - c. Name of manufacturer.
 - d. Name of Contractor.
 - e. Building dimensions including width, length, height, and roof slope.
 - f. Indicate compliance with AISC standards for hot-rolled steel and AISI standards for cold-rolled steel, including edition dates of each standard.
 - g. Governing building code and year of edition.
 - h. Design Loads: Include dead load, roof live load, collateral loads, roof snow load, deflection, wind loads/speeds and exposure, seismic design category or effective peak velocity-related acceleration/peak acceleration, and auxiliary loads (cranes).
 - i. Load Combinations: Indicate that loads were applied acting simultaneously with concentrated loads, according to governing building code.
 - j. Column base plate loads: Based on loads/ load combinations identified in h & i.
 - k. Building-Use Category: Indicate category of building use and its effect on load importance factors.

- I. AISC Certification for Category MB: Include statement that metal building system and components were designed and produced in an AISC-Certified Facility by an AISC-Certified Manufacturer.
- F. Welding certificates.
- G. Erector Certificate: Signed by manufacturer certifying that erector complies with requirements.
- H. Manufacturer Certificate: Signed by manufacturer certifying that products comply with requirements.
- I. Qualification Data: For firms and persons specified in "Quality Assurance" Article to demonstrate their capabilities and experience. Include lists of completed projects with project names and addresses, names and addresses of architects and owners, and other information specified.
- J. Material Test Reports: Signed by manufacturers certifying that the following products comply with requirements:
 - 1. Structural steel including chemical and physical properties.
 - 2. Bolts, nuts, and washers including mechanical properties and chemical analysis.
 - 3. Tension-control, high-strength, bolt-nut-washer assemblies.
 - 4. Shop primers.
 - 5. Nonshrink grout.
- K. Source quality-control test reports.
- L. Field quality-control test reports.
- M. Product Test Reports: Based on evaluation of comprehensive tests performed by manufacturer and witnessed by a qualified testing agency, for insulation and vapor retarders. Include reports for thermal resistance, fire-test-response characteristics, water-vapor transmission, and water absorption.
- N. Surveys: Show final elevations and locations of major members. Indicate discrepancies between actual installation and the Contract Documents. Have surveyor who performed surveys certify their accuracy.
- O. Warranties: Special warranties specified in this Section.
- P. Other Action Submittals:

1. Door Schedule: For doors and frames. Use same designations indicated on Drawings. Include details of reinforcement.
 - a. Door Hardware Schedule: Include details of fabrication and assembly of door hardware. Organize schedule into door hardware sets indicating complete designations of every item required for each door or opening.
 - b. Keying Schedule: Detail Owner's final keying instructions for locks. Include schematic keying diagram and index each key set to unique door designations.

1.7 QUALITY ASSURANCE

- A. Erector Qualifications: An experienced erector who has specialized in erecting and installing work similar in material, design, and extent to that indicated for this Project and who is acceptable to manufacturer.
- B. Manufacturer Qualifications: A qualified manufacturer and member of MBMA.
 1. AISC Certification for Category MB: An AISC-Certified Manufacturer that designs and produces metal building systems and components in an AISC-Certified Facility.
 2. Engineering Responsibility: Preparation of Shop Drawings and comprehensive engineering analysis by a qualified professional engineer.
- C. Land Surveyor Qualifications: A professional land surveyor who is legally qualified to practice in jurisdiction where Project is located and who is experienced in providing surveying services of the kind indicated.
- D. Testing Agency Qualifications: An independent agency qualified according to ASTM E 329 for testing indicated, as documented according to ASTM E 548.
- E. Source Limitations: Obtain primary metal building system components, including structural framing and metal panel assemblies, through one source from a single manufacturer.
- F. Product Options: Drawings indicate size, profiles, and dimensional requirements of metal building system and are based on the specific system indicated. Refer to Division 1 Section "Product Requirements."
 1. Do not modify intended aesthetic effects, as judged solely by Architect, except with Architect's approval. If modifications are proposed, submit comprehensive explanatory data to Architect for review.

- G. Welding: Qualify procedures and personnel according to AWS D1.1, "Structural Welding Code--Steel," and AWS D1.3, "Structural Welding Code--Sheet Steel."
- H. Structural Steel: Comply with AISC's "Specification for Structural Steel Buildings--Allowable Stress Design, Plastic Design," or AISC's "Load and Resistance Factor Design Specification for Structural Steel Buildings," for design requirements and allowable stresses.
- I. Cold-Formed Steel: Comply with AISI's "Specification for the Design of Cold-Formed Steel Structural Members," or AISI's "Load and Resistance Factor Design Specification for Steel Structural Members," for design requirements and allowable stresses.
- J. Pre-Erection Conference: Conduct conference at Project site to comply with requirements in Division 1 Section "Project Management and Coordination." Review methods and procedures related to metal building systems including, but not limited to, the following:
 - 1. Inspect and discuss condition of foundations and other preparatory work performed by other trades.
 - 2. Review structural load limitations.
 - 3. Review and finalize construction schedule and verify availability of materials, Erector's personnel, equipment, and facilities needed to make progress and avoid delays.
 - 4. Review required testing, inspecting, and certifying procedures.
 - 5. Review weather and forecasted weather conditions and procedures for unfavorable conditions.

1.8 DELIVERY, STORAGE, AND HANDLING

- A. Deliver components, sheets, panels, and other manufactured items so as not to be damaged or deformed. Package metal panels for protection during transportation and handling.
- B. Unload, store, and erect metal panels in a manner to prevent bending, warping, twisting, and surface damage.
- C. Stack metal panels horizontally on platforms or pallets, covered with suitable weathertight and ventilated covering. Store metal panels to ensure dryness and with positive slope for drainage of water. Do not store metal panels in contact with other materials that might cause staining, denting, or other surface damage.
- D. Protect foam-plastic insulation as follows:

1. Do not expose to sunlight, except to extent necessary for period of installation and concealment.
2. Protect against ignition at all times. Do not deliver foam-plastic insulation materials to Project site before installation time.
3. Complete installation and concealment of plastic materials as rapidly as possible in each area of construction.

1.9 PROJECT CONDITIONS

- A. Weather Limitations: Proceed with installation only when weather conditions permit metal panels to be installed according to manufacturers' written instructions and warranty requirements.
- B. Field Measurements:
 1. Established Dimensions for Foundations: Comply with established dimensions on approved anchor-bolt plans, establishing foundation dimensions and proceeding with fabricating structural framing without field measurements. Coordinate anchor-bolt installation to ensure that actual anchorage dimensions correspond to established dimensions.

1.10 COORDINATION

- A. Coordinate size and location of concrete foundations and casting of anchor-bolt inserts into foundation walls and footings. Concrete, reinforcement, and formwork requirements are specified in Division 3 Section "Cast-in-Place Concrete."
- B. Coordinate installation of roof curbs, equipment supports, and roof penetrations, which are specified in Division 7 Section "Roof Accessories."
- C. Coordinate sheet metal assemblies with rain drainage work, flashing, trim, and construction of supports and other adjoining work to provide a leakproof, secure, and noncorrosive installation.

PART 2 - PRODUCTS**2.1 MANUFACTURERS**

- A. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
1. Butler Manufacturing Company.
 2. Ceco Building Systems; Division of Robertson-Ceco Corporation.
 3. Gulf States Manufacturers, Inc.
 4. Mesco Metal Buildings; Division of NCI Building Systems, LLP.
 5. Metallic Metal Building Company; Division of NCI Building Systems, LLP.
 6. VP Buildings, Inc.; a United Dominion Company.

2.2 STRUCTURAL-FRAMING MATERIALS

- A. W-Shapes: ASTM A 992/A 992M; ASTM A 572/A 572M, Grade 50 or 55 (345 or 380); or ASTM A 529/A 529M, Grade 50 or 55 (345 or 380).
- B. Channels, Angles, M-Shapes, and S-Shapes: ASTM A 36/A 36M; ASTM A 572/A 572M, Grade 50 or 55 (345 or 380); or ASTM A 529/A 529M, Grade 50 or 55 (345 or 380).
- C. Plate and Bar: ASTM A 36/A 36M; ASTM A 572/A 572M, Grade 50 or 55 (345 or 380); or ASTM A 529/A 529M, Grade 50 or 55 (345 or 380).
- D. Steel Pipe: ASTM A 53/A 53M, Type E or S, Grade B.
- E. Cold-Formed Hollow Structural Sections: ASTM A 500, Grade B or C, structural tubing.
- F. Structural-Steel Sheet: Hot-rolled, ASTM A 1011/A 1011M, Structural Steel (SS), Grades 30 through 55 (205 through 380), or High-Strength Low Alloy Steel (HSLAS), Grades 45 through 70 (310 through 480); or cold-rolled, ASTM A 1008/A 1008M, Structural Steel (SS), Grades 25 through 80 (170 through 550), or High-Strength Low Alloy Steel (HSLAS), Grades 45 through 70 (310 through 480).
- G. Metallic-Coated Steel Sheet: ASTM A 653/A 653M, Structural Steel (SS), Grades 33 through 80 (230 through 550) or High-Strength Low Alloy Steel

(HSLAS), Grades 50 through 80 (340 through 550); with G60 (Z180) coating designation; mill phosphatized.

- H. Metallic-Coated Steel Sheet Prepainted with Coil Coating: Steel sheet metallic coated by the hot-dip process and prepainted by the coil-coating process to comply with ASTM A 755/A 755M.
1. Zinc-Coated (Galvanized) Steel Sheet: ASTM A 653/A 653M, Structural Steel (SS), Grades 33 through 80 (230 through 550) or High-Strength Low Alloy Steel (HSLAS), Grades 50 through 80 (340 through 550); with G90 (Z275) coating designation.
 2. Aluminum-Zinc Alloy-Coated Steel Sheet: ASTM A 792/A 792M, Structural Steel (SS), Grade 50 or 80 (340 or 550); with Class AZ50 (AZM150) coating.
- I. Non-High-Strength Bolts, Nuts, and Washers: ASTM A 307, Grade A (ASTM F 568M, Property Class 4.6), carbon-steel, hex-head bolts; ASTM A 563 (ASTM A 563M) carbon-steel hex nuts; and ASTM F 844 plain (flat) steel washers.
1. Finish: Hot-dip zinc coating, ASTM A 153/A 153M, Class C.
- J. High-Strength Bolts, Nuts, and Washers: ASTM A 325 (ASTM A 325M), Type 1, heavy hex steel structural bolts; ASTM A 563 (ASTM A 563M) heavy hex carbon-steel nuts; and ASTM F 436 (ASTM F 436M) hardened carbon-steel washers.
1. Finish: Hot-dip zinc coating, ASTM A 153/A 153M, Class C.
 2. Tension-Control, High-Strength Bolt-Nut-Washer Assemblies: ASTM F 1852, Type 1, heavy-hex-head steel structural bolts with splined ends.
 - a. Finish: Mechanically deposited zinc coating, ASTM B 695, Class 50.
- K. High-Strength Bolts, Nuts, and Washers: ASTM A 490 (ASTM A 490M), Type 1, heavy hex steel structural bolts; ASTM A 563 (ASTM A 563M) heavy hex carbon-steel nuts; and ASTM F 436 (ASTM F 436M) hardened carbon-steel washers, plain.
- L. Unheaded Anchor Rods: [ASTM F 1554, Grade 36] [ASTM A 572/A 572M, Grade 50 (345)] [ASTM A 36/A 36M] [ASTM A 307, Grade A (ASTM F 568M, Property Class 4.6)].
1. Configuration: Straight.
 2. Nuts: ASTM A 563 (ASTM A 563M) [heavy] hex carbon steel.

3. Plate Washers: ASTM A 36/A 36M carbon steel.
 4. Washers: ASTM F 436 (ASTM F 436M) hardened carbon steel.
 5. Finish: [Plain] [Hot-dip zinc coating, ASTM A 153/A 153M, Class C] [Mechanically deposited zinc coating, ASTM B 695, Class 50].
- M. Headed Anchor Rods: [ASTM F 1554, Grade 36] [ASTM A 307, Grade A (ASTM F 568M, Property Class 4.6)], straight.
1. Nuts: ASTM A 563 (ASTM A 563M) [heavy] hex carbon steel.
 2. Plate Washers: ASTM A 36/A 36M carbon steel.
 3. Washers: ASTM F 436 (ASTM F 436M) hardened carbon steel.
 4. Finish: [Plain] [Hot-dip zinc coating, ASTM A 153/A 153M, Class C] [Mechanically deposited zinc coating, ASTM B 695, Class 50].
- N. Threaded Rods: [ASTM A 193/A 193M] [ASTM A 572/A 572M, Grade 50 (345)] [ASTM A 36/A 36M] [ASTM A 307, Grade A (ASTM F 568M, Property Class 4.6)].
1. Nuts: ASTM A 563 (ASTM A 563M) [heavy] hex carbon steel.
 2. Washers: [ASTM F 436 (ASTM F 436M) hardened] [ASTM A 36/A 36M] carbon steel.
 3. Finish: [Plain] [Hot-dip zinc coating, ASTM A 153/A 153M, Class C] [Mechanically deposited zinc coating, ASTM B 695, Class 50].
- O. Primer: SSPC-Paint 15, Type I, red oxide.

2.3 MISCELLANEOUS MATERIALS

- A. Fasteners: Self-tapping screws, bolts, nuts, self-locking rivets and bolts, end-welded studs, and other suitable fasteners designed to withstand design loads. Provide fasteners with heads matching color of materials being fastened by means of plastic caps or factory-applied coating.
1. Fasteners for Metal Roof Panels: Self-drilling or self-tapping, zinc-plated, hex-head carbon-steel screws, with a stainless-steel cap or zinc-aluminum-alloy head and EPDM or neoprene sealing washer.
 2. Fasteners for Flashing and Trim: Blind fasteners or self-drilling screws with hex washer head.
 3. Blind Fasteners: High-strength aluminum or stainless-steel rivets.
- B. Bituminous Coating: Cold-applied asphalt mastic, SSPC-Paint 12, compounded for 15-mil (0.4-mm) dry film thickness per coat. Provide inert-type noncorrosive compound free of asbestos fibers, sulfur components, and other deleterious impurities.

2.4 FABRICATION, GENERAL

- A. General: Design components and field connections required for erection to permit easy assembly.
 - 1. Mark each piece and part of the assembly to correspond with previously prepared erection drawings, diagrams, and instruction manuals.
 - 2. Fabricate structural framing to produce clean, smooth cuts and bends. Punch holes of proper size, shape, and location. Members shall be free of cracks, tears, and ruptures.
- B. Tolerances: Comply with MBMA's "Metal Building Systems Manual": Chapter IV, Section 9, "Fabrication and Erection Tolerances."

2.5 STRUCTURAL FRAMING

- A. General:
 - 1. Primary Framing: Shop fabricate framing components to indicated size and section with baseplates, bearing plates, stiffeners, and other items required for erection welded into place. Cut, form, punch, drill, and weld framing for bolted field assembly.
 - a. Make shop connections by welding or by using high-strength bolts.
 - b. Join flanges to webs of built-up members by a continuous submerged arc-welding process.
 - c. Brace compression flange of primary framing with steel angles or cold-formed structural tubing between frame web and purlin or girt web, so flange compressive strength is within allowable limits for any combination of loadings.
 - d. Weld clips to frames for attaching secondary framing members.
 - e. Shop Priming: Prepare surfaces for shop priming according to SSPC-SP 2. Shop prime primary structural members with specified primer after fabrication.
 - 2. Secondary Framing: Shop fabricate framing components to indicated size and section by roll-forming or break-forming, with baseplates, bearing plates, stiffeners, and other plates required for erection welded into place. Cut, form, punch, drill, and weld secondary framing for bolted field connections to primary framing.
 - a. Make shop connections by welding or by using non-high-strength bolts.

steel sheet prepainted with coil coating, unless otherwise indicated, to comply with the following:

1. Purlins: C- or Z-shaped sections; fabricated from minimum 0.0598-inch- (1.5-mm-) thick steel sheet, built-up steel plates, or structural-steel shapes; minimum 2-1/2-inch- (64-mm-) wide flanges.
 - a. Depth: As required to comply with system performance requirements.
 2. Girts: C- or Z-shaped sections; fabricated from minimum 0.0598-inch- (1.5-mm-) thick steel sheet, built-up steel plates, or structural-steel shapes. Form ends of Z-sections with stiffening lips angled 40 to 50 degrees to flange and with minimum 2-1/2-inch- (64-mm-) wide flanges.
 - a. Depth: As required to comply with system performance requirements.
 3. Eave Struts: Unequal-flange, C-shaped sections; fabricated from 0.0598-inch- (1.5-mm-) thick steel sheet, built-up steel plates, or structural-steel shapes; to provide adequate backup for metal panels.
 4. Flange Bracing: Minimum 2-by-2-by-1/8-inch (51-by-51-by-3-mm) structural-steel angles or 1-inch (25-mm) diameter, cold-formed structural tubing to stiffen primary frame flanges.
 5. Sag Bracing: Minimum 1-by-1-by-1/8-inch (25-by-25-by-3-mm) structural-steel angles.
 6. Base or Sill Angles: Minimum 3-by-2-by-0.0598-inch (76-by-51-by-1.5-mm) zinc-coated (galvanized) steel sheet.
 7. Purlin and Girt Clips: Minimum 0.0598-inch- (1.5-mm-) thick, steel sheet. Provide galvanized clips where clips are connected to galvanized framing members.
 8. Secondary End-Wall Framing: Manufacturer's standard sections fabricated from minimum 0.0598-inch- (1.5-mm-) thick, [zinc-coated (galvanized) steel sheet] [structural-steel sheet].
 9. Framing for Openings: Channel shapes; fabricated from minimum 0.0598-inch- (1.5-mm-) thick, cold-formed, structural-steel sheet or structural-steel shapes. Frame head and jamb of door openings, and head, jamb, and sill of other openings.
 10. Miscellaneous Structural Members: Manufacturer's standard sections fabricated from cold-formed, structural-steel sheet; built-up steel plates; or zinc-coated (galvanized) steel sheet; designed to withstand required loads.
- E. Canopy Framing: Manufacturer's standard structural-framing system, designed to withstand required loads, fabricated from shop-welded, built-up steel plates or

structural-steel shapes. Provide frames with attachment plates and splice members, factory drilled for field-bolted assembly.

1. Type: As indicated.

F. Bracing: Provide adjustable wind bracing as follows:

1. Rods: ASTM A 36/A 36M; ASTM A 572/A 572M, Grade 50 (345); or ASTM A 529/A 529M, Grade 50 (345); minimum 1/2-inch- (13-mm-) diameter steel; threaded full length or threaded a minimum of 6 inches (152 mm) at each end.
2. Cable: ASTM A 475, 1/4-inch- (6-mm-) diameter, extra-high-strength grade, Class B zinc-coated, 7-strand steel; with threaded end anchors.
3. Angles: Fabricated from structural-steel shapes to match primary framing, of size required to withstand design loads.
4. Rigid Portal Frames: Fabricate from shop-welded, built-up steel plates or structural-steel shapes to match primary framing; of size required to withstand design loads.
5. Fixed-Base Columns: Fabricate from shop-welded, built-up steel plates or structural-steel shapes to match primary framing; of size required to withstand design loads.
6. Diaphragm Action of Metal Panels: Design metal building to resist wind forces through diaphragm action of metal panels.
7. Bracing: Provide wind bracing using any method specified above, at manufacturer's option.

G. Bolts: Provide plain finish bolts for structural-framing components that are primed or finish painted. Provide hot-dipped galvanized bolts for structural-framing components that are galvanized.

H. Factory-Primed Finish: Apply specified primer immediately after cleaning and pretreating.

1. Prime primary, secondary, and end-wall structural-framing members to a minimum dry film thickness of 1 mil (0.025 mm).
 - a. Prime secondary steel framing formed from uncoated steel sheet to a minimum dry film thickness of 0.5 mil (0.013 mm) on each side.
2. Prime galvanized members with specified primer, after phosphoric acid pretreatment.

2.6 METAL ROOF PANELS

- A. Refer to Section 07610 "Sheet Metal Roofing".

2.7 METAL SOFFIT PANELS

- A. Refer to Section 07610 "Sheet Metal Roofing". (Addendum 2)

2.8 ACCESSORIES

- A. General: Provide accessories as standard with metal building system manufacturer and as specified. Fabricate and finish accessories at the factory to greatest extent possible, by manufacturer's standard procedures and processes. Comply with indicated profiles and with dimensional and structural requirements.
 - 1. Form exposed sheet metal accessories that are without excessive oil canning, buckling, and tool marks and that are true to line and levels indicated, with exposed edges folded back to form hems.
- B. Flashing and Trim: Formed from minimum 0.0159-inch- (0.40-mm-) thick, metallic-coated steel sheet or aluminum-zinc alloy-coated steel sheet prepainted with coil coating; finished to match adjacent metal panels.
 - 1. Provide flashing and trim as required to seal against weather and to provide finished appearance. Locations include, but are not limited to, eaves, rakes, corners, bases, framed openings, ridges, fasciae, and fillers.
 - 2. Opening Trim: Minimum 0.0269-inch- (0.70-mm-) thick, metallic-coated steel sheet or aluminum-zinc alloy-coated steel sheet prepainted with coil coating. Trim head and jamb of door openings, and head, jamb, and sill of other openings.
- C. Gutters: Formed from minimum 0.0159-inch- (0.40-mm-) thick, metallic-coated steel sheet or aluminum-zinc alloy-coated steel sheet prepainted with coil coating; finished to match roof fascia and rake trim. Match profile of gable trim, complete with end pieces, outlet tubes, and other special pieces as required. Fabricate in minimum 96-inch- (2438-mm-) long sections, sized according to SMACNA's "Architectural Sheet Metal Manual."
 - 1. Gutter Supports: Fabricated from same material and finish as gutters; spaced 36 inches (900 mm) o.c.
 - 2. Strainers: Bronze, copper, or aluminum wire ball type at outlets.

- D. Downspouts: Formed from 0.0159-inch- (0.4-mm-) thick, zinc-coated (galvanized) steel sheet or aluminum-zinc alloy-coated steel sheet prepainted with coil coating; finished to match metal wall panels. Fabricate in minimum 10-foot- (3-m-) long sections, complete with formed elbows and offsets.
 - 1. Mounting Straps: Fabricated from same material and finish as gutters; spaced 10 feet (3 m) o.c.
- E. Louvers: Refer to Section 10200 "Louvers & Vents".

2.9 FINISHES, GENERAL

- A. Comply with NAAMM's "Metal Finishes Manual for Architectural and Metal Products" for recommendations for applying and designating finishes.
- B. Appearance of Finished Work: Variations in appearance of abutting or adjacent pieces are acceptable if they are within one-half of the range of approved Samples. Noticeable variations in the same piece are not acceptable. Variations in appearance of other components are acceptable if they are within the range of approved Samples and are assembled or installed to minimize contrast.

2.10 SOURCE QUALITY CONTROL

- A. Testing Agency: Contractor shall engage a qualified testing and inspecting agency to perform the following tests and inspections and to submit reports.
- B. Special Inspector: Owner will engage a qualified special inspector to perform the following tests and inspections and to submit reports. Special Inspector will verify that manufacturer maintains detailed fabrication and quality-control procedures and will review the completeness and adequacy of those procedures to perform the Work.
 - 1. Special inspections will not be required if fabrication is performed by a manufacturer registered and approved by authorities having jurisdiction to perform such Work without special inspection.
 - a. After fabrication, submit certificate of compliance with copy to authorities having jurisdiction certifying that Work was performed according to Contract requirements.
- C. Tests and Inspections:

1. Bolted Connections: Shop-bolted connections shall be tested and inspected according to RCSC's "Specification for Structural Joints Using ASTM A 325 or A 490 Bolts."
 2. Welded Connections: In addition to visual inspection, shop-welded connections shall be tested and inspected according to AWS D1.1 and the following inspection procedures, at inspector's option:
 - a. Liquid Penetrant Inspection: ASTM E 165.
 - b. Magnetic Particle Inspection: ASTM E 709; performed on root pass and on finished weld. Cracks or zones of incomplete fusion or penetration will not be accepted.
 - c. Ultrasonic Inspection: ASTM E 164.
 - d. Radiographic Inspection: ASTM E 94.
- D. Correct deficiencies in Work that test reports and inspections indicate do not comply with the Contract Documents.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates, areas, and conditions, with Erector present, for compliance with requirements for installation tolerances and other conditions affecting performance of work.

3.2 PREPARATION

- A. Clean and prepare surfaces to be painted according to manufacturer's written instructions for each particular substrate condition.
- B. Provide temporary shores, guys, braces, and other supports during erection to keep structural framing secure, plumb, and in alignment against temporary construction loads and loads equal in intensity to design loads. Remove temporary supports when permanent structural framing, connections, and bracing are in place, unless otherwise indicated.

3.3 ERECTION OF STRUCTURAL FRAMING

- A. Erect metal building system according to manufacturer's written erection instructions and erection drawings.

- B. Do not field cut, drill, or alter structural members without written approval from metal building system manufacturer's professional engineer.
- C. Set structural framing accurately in locations and to elevations indicated and according to AISC specifications referenced in this Section. Maintain structural stability of frame during erection.
- D. Base Plates: Clean concrete- and masonry-bearing surfaces of bond-reducing materials, and roughen surfaces prior to setting plates. Clean bottom surface of plates.
 - 1. Set plates for structural members on wedges, shims, or setting nuts as required.
 - 2. Tighten anchor rods after supported members have been positioned and plumbed. Do not remove wedges or shims but, if protruding, cut off flush with edge of plate before packing with grout.
 - 3. Promptly pack grout solidly between bearing surfaces and plates so no voids remain. Neatly finish exposed surfaces; protect grout and allow to cure. Comply with manufacturer's written installation instructions for shrinkage-resistant grouts.
- E. Align and adjust structural framing before permanently fastening. Before assembly, clean bearing surfaces and other surfaces that will be in permanent contact with framing. Perform necessary adjustments to compensate for discrepancies in elevations and alignment.
 - 1. Level and plumb individual members of structure.
 - 2. Make allowances for difference between temperature at time of erection and mean temperature when structure will be completed and in service.
- F. Primary Framing and End Walls: Erect framing true to line, level, plumb, rigid, and secure. Level baseplates to a true even plane with full bearing to supporting structures, set with double-nutted anchor bolts. Use grout to obtain uniform bearing and to maintain a level base-line elevation. Moist cure grout for not less than seven days after placement.
 - 1. Make field connections using high-strength bolts installed according to RCSC's "Specification for Structural Joints Using ASTM A 325 or A 490 Bolts" for type of bolt and type of joint specified.
 - a. Joint Type: Snug tightened or pretensioned.

- G. Secondary Framing: Erect framing true to line, level, plumb, rigid, and secure. Fasten secondary framing to primary framing using clips with field connections using non-high-strength bolts.
1. Provide rake or gable purlins with tight-fitting closure channels and fasciae.
 2. Locate and space wall girts to suit openings such as doors and windows.
 3. Locate canopy framing as indicated.
 4. Provide supplemental framing at entire perimeter of openings, including doors, windows, louvers, ventilators, and other penetrations of roof and walls.
- H. Bracing: Install bracing in roof and sidewalls where indicated on erection drawings.
1. Tighten rod and cable bracing to avoid sag.
 2. Locate interior end-bay bracing only where indicated.
- I. Framing for Openings: Provide shapes of proper design and size to reinforce openings and to carry loads and vibrations imposed, including equipment furnished under mechanical and electrical work. Securely attach to structural framing.
- J. Erection Tolerances: Maintain erection tolerances of structural framing within AISC's "Code of Standard Practice for Steel Buildings and Bridges."

3.4 ACCESSORY INSTALLATION

- A. General: Install accessories with positive anchorage to building and weathertight mounting, and provide for thermal expansion. Coordinate installation with flashings and other components.
1. Install components required for a complete metal roof panel assembly including trim, copings, ridge closures, seam covers, flashings, sealants, gaskets, fillers, closure strips, and similar items.
 2. Install components for a complete metal wall panel assembly including trim, copings, corners, seam covers, flashings, sealants, gaskets, fillers, closure strips, and similar items.
 3. Where dissimilar metals will contact each other or corrosive substrates, protect against galvanic action by painting contact surfaces with bituminous coating, by applying rubberized-asphalt underlayment to each contact surface, or by other permanent separation as recommended by manufacturer.

- B. Flashing and Trim: Comply with performance requirements, manufacturer's written installation instructions, and SMACNA's "Architectural Sheet Metal Manual." Provide concealed fasteners where possible, and set units true to line and level as indicated. Install work with laps, joints, and seams that will be permanently watertight and weather resistant.
1. Install exposed flashing and trim that is without excessive oil canning, buckling, and tool marks and that is true to line and levels indicated, with exposed edges folded back to form hems. Install sheet metal flashing and trim to fit substrates and to result in waterproof and weather-resistant performance.
 2. Expansion Provisions: Provide for thermal expansion of exposed flashing and trim. Space movement joints at a maximum of 10 feet (3 m) with no joints allowed within 24 inches (600 mm) of corner or intersection. Where lapped or bayonet-type expansion provisions cannot be used or would not be sufficiently weather resistant and waterproof, form expansion joints of intermeshing hooked flanges, not less than 1 inch (25 mm) deep, filled with mastic sealant (concealed within joints).
- C. Gutters: Join sections with riveted and soldered or lapped and sealed joints. Attach gutters to eave with gutter hangers spaced not more than 4 feet (1.2 m) o.c. using manufacturer's standard fasteners. Provide end closures and seal watertight with sealant. Provide for thermal expansion.
- D. Downspouts: Join sections with 1-1/2-inch (38-mm) telescoping joints. Provide fasteners designed to hold downspouts securely 1 inch (25 mm) away from walls; locate fasteners at top and bottom and at approximately 60 inches (1500 mm) o.c. in between.
1. Provide elbows at base of downspouts to direct water away from building.
 2. Tie downspouts to underground drainage system indicated.
- E. Roof Curbs: Install curbs at locations indicated on Drawings. Install flashing around bases where they meet metal roof panels.
- F. Pipe Flashing: Form flashing around pipe penetration and metal roof panels. Fasten and seal to panel as recommended by manufacturer.

3.5 FIELD QUALITY CONTROL

- A. Testing Agency: Contractor shall engage a qualified testing and inspecting agency to perform the following tests and inspections and to submit reports.

- B. Special Inspector: Owner will engage a qualified special inspector to perform the following tests and inspections and to submit reports.
- C. Tests and Inspections:
 - 1. High-Strength, Field-Bolted Connections: Connections shall be inspected during installation according to RCSC's "Specification for Structural Joints Using ASTM A 325 or A 490 Bolts."
 - 2. Welded Connections: In addition to visual inspection, field-welded connections shall be tested and inspected according to AWS D1.1 and the following inspection procedures, at inspector's option:
 - a. Liquid Penetrant Inspection: ASTM E 165.
 - b. Magnetic Particle Inspection: ASTM E 709; performed on root pass and on finished weld. Cracks or zones of incomplete fusion or penetration will not be accepted.
 - c. Ultrasonic Inspection: ASTM E 164.
 - d. Radiographic Inspection: ASTM E 94.
- D. Correct deficiencies in Work that test reports and inspections indicate do not comply with the Contract Documents.

3.6 CLEANING AND PROTECTION

- A. Repair damaged galvanized coatings on galvanized items with galvanized repair paint according to ASTM A 780 and manufacturer's written instructions.
- B. Remove and replace glass that has been broken, chipped, cracked, abraded, or damaged during construction period.
- C. Touchup Painting: After erection, promptly clean, prepare, and prime or reprime field connections, rust spots, and abraded surfaces of prime-painted structural framing and accessories.
 - 1. Clean and prepare surfaces by SSPC-SP 2, "Hand Tool Cleaning," or SSPC-SP 3, "Power Tool Cleaning."
 - 2. Apply a compatible primer of same type as shop primer used on adjacent surfaces.
- D. Touchup Painting: Cleaning and touchup painting are specified in Division 9 painting Sections.

END OF SECTION 13121